

[MS-RPL]: Report Page Layout (RPL) Binary Stream Format Structure Specification

Intellectual Property Rights Notice for Open Specifications Documentation

- **Technical Documentation.** Microsoft publishes Open Specifications documentation for protocols, file formats, languages, standards as well as overviews of the interaction among each of these technologies.
- **Copyrights.** This documentation is covered by Microsoft copyrights. Regardless of any other terms that are contained in the terms of use for the Microsoft website that hosts this documentation, you may make copies of it in order to develop implementations of the technologies described in the Open Specifications and may distribute portions of it in your implementations using these technologies or your documentation as necessary to properly document the implementation. You may also distribute in your implementation, with or without modification, any schema, IDL's, or code samples that are included in the documentation. This permission also applies to any documents that are referenced in the Open Specifications.
- **No Trade Secrets.** Microsoft does not claim any trade secret rights in this documentation.
- **Patents.** Microsoft has patents that may cover your implementations of the technologies described in the Open Specifications. Neither this notice nor Microsoft's delivery of the documentation grants any licenses under those or any other Microsoft patents. However, a given Open Specification may be covered by Microsoft's Open Specification Promise (available here: <http://www.microsoft.com/interop/osp>) or the Community Promise (available here: <http://www.microsoft.com/interop/cp/default.mspx>). If you would prefer a written license, or if the technologies described in the Open Specifications are not covered by the Open Specifications Promise or Community Promise, as applicable, patent licenses are available by contacting iplq@microsoft.com.
- **Trademarks.** The names of companies and products contained in this documentation may be covered by trademarks or similar intellectual property rights. This notice does not grant any licenses under those rights.
- **Fictitious Names.** The example companies, organizations, products, domain names, e-mail addresses, logos, people, places, and events depicted in this documentation are fictitious. No association with any real company, organization, product, domain name, email address, logo, person, place, or event is intended or should be inferred.

Reservation of Rights. All other rights are reserved, and this notice does not grant any rights other than specifically described above, whether by implication, estoppel, or otherwise.

Tools. The Open Specifications do not require the use of Microsoft programming tools or programming environments in order for you to develop an implementation. If you have access to Microsoft programming tools and environments you are free to take advantage of them. Certain Open Specifications are intended for use in conjunction with publicly available standard specifications and network programming art, and assumes that the reader either is familiar with the aforementioned material or has immediate access to it.

Revision Summary

Date	Revision History	Revision Class	Comments
08/07/2009	0.1	Major	First release.
11/06/2009	0.2	Minor	Updated the technical content.
03/05/2010	1.0	Major	Updated and revised the technical content.

Contents

1 Introduction	9
1.1 Glossary.....	9
1.2 References.....	12
1.2.1 Normative References	12
1.2.2 Informative References	12
1.3 Structure Overview (Synopsis)	12
1.3.1 Byte Ordering.....	13
1.3.2 Organization of This Documentation	13
1.4 Relationship to Protocols and Other Structures	13
1.5 Applicability Statement.....	14
1.6 Versioning and Localization	14
1.7 Vendor-Extensible Fields	14
2 Structures	15
2.1 Stream Structure	15
2.1.1 RPL Stream.....	15
2.1.2 Record.....	15
2.1.3 Simple Data Type Structures	15
2.1.3.1 Writing Strings to an RPL Stream	16
2.1.3.2 Writing the Length Value of the String to an RPL Stream	16
2.1.3.3 Reading Strings from an RPL Stream	16
2.2 Report Structures.....	16
2.2.1 Report.....	16
2.2.2 Version	18
2.2.3 ReportProperties	18
2.2.4 OffsetsArrayElement	19
2.2.5 PageContent	20
2.2.5.1 PageContent (RPL 10.6).....	20
2.2.5.2 PageContent (RPL 10.4 and 10.5).....	21
2.2.5.3 PageContent (RPL 10.3).....	22
2.2.6 Page	23
2.2.7 PageProperties	24
2.2.8 PageLayout.....	25
2.2.9 Section	26
2.2.10 SimpleSection	26
2.2.11 MixedSection.....	27
2.2.12 SectionProperties	29
2.2.13 BodyAreaElement.....	30
2.2.13.1 BodyAreaElement (RPL 10.4).....	30
2.2.13.2 BodyAreaElement (RPL 10.3).....	31
2.2.14 PageHeaderElement	32
2.2.15 PageFooterElement	33
2.2.16 BodyElement.....	34
2.2.17 ElementProperties	35
2.2.18 SharedElementProperties	36
2.2.19 UseSharedElementProperties.....	36
2.2.20 InlineSharedElementProperties.....	37
2.2.21 NonSharedElementProperties	38
2.2.22 Style	40
2.2.23 SharedStyleProperties	42

2.2.24	NonSharedStyleProperties	43
2.2.25	ActionInfo	43
2.2.26	ActionInfoContent	44
2.2.27	Action	45
2.2.28	ActionImageMapAreas	45
2.2.29	ActionInfoWithMaps	46
2.2.30	DynamicImageData	47
2.2.31	ImageConsolidationOffsets	47
2.2.32	ReportItem	48
2.2.33	Line	49
2.2.34	Image	50
2.2.35	ImageDataProperties	51
2.2.36	UseSharedImageDataProperties	51
2.2.37	InlineSharedImageDataProperties	52
2.2.38	NonSharedImageDataProperties	53
2.2.39	ImageData	54
2.2.40	ImageMapAreas	54
2.2.41	ImageMapArea	55
2.2.42	Chart	56
2.2.43	GaugePanel	57
2.2.44	Map	58
2.2.45	Rectangle	59
2.2.46	SubReport	61
2.2.47	RichTextBox	62
2.2.48	ParagraphContent	64
2.2.49	TextRun	64
2.2.50	Paragraph	65
2.2.51	RichTextBoxStructure	67
2.2.52	Tablix	68
2.2.53	TablixContent	69
2.2.54	TablixStructure	69
2.2.55	TablixMeasurements	70
2.2.56	ColumnsWidths	71
2.2.57	ColumnInfo	71
2.2.58	Row Heights	72
2.2.59	Row Info	73
2.2.60	TablixRow	74
2.2.61	TablixRow Cell	74
2.2.62	TablixCorner	74
2.2.63	TablixColumnHeader	75
2.2.64	TablixRow Header	76
2.2.65	TablixBodyRow Cells	77
2.2.66	TablixBodyRow	78
2.2.67	TablixBodyCell	78
2.2.68	TablixRow MembersDef	79
2.2.69	TablixColMembersDef	80
2.2.70	TablixMemberDef	80
2.2.71	Measurements	81
2.2.72	Measurement	82
2.2.73	ReportElementEnd	84
2.3	Properties	85
2.3.1	ID	85
2.3.2	ColumnCount	86

2.3.3	ColumnSpacing	86
2.3.4	UniqueName	87
2.3.5	Name	87
2.3.6	Label	88
2.3.7	Bookmark	89
2.3.8	ToolTip	89
2.3.9	ToggleItem	90
2.3.10	Description	90
2.3.11	Location	91
2.3.12	ConsumeContainerWhiteSpace (RPL 10.6)	91
2.3.13	Language	92
2.3.14	ExecutionTime	93
2.3.15	Author	94
2.3.16	AutoRefresh	94
2.3.17	ReportName	95
2.3.18	PageHeight	95
2.3.19	PageWidth	96
2.3.20	MarginTop	96
2.3.21	MarginLeft	97
2.3.22	MarginRight	98
2.3.23	MarginBottom	98
2.3.24	Columns	99
2.3.25	PageName (RPL 10.6)	99
2.3.26	Slant	100
2.3.27	CanGrow	100
2.3.28	CanShrink	101
2.3.29	Value	102
2.3.30	ToggleState	102
2.3.31	CanSort	103
2.3.32	SortState	104
2.3.33	Formula	104
2.3.34	IsToggleParent	105
2.3.35	TypeCode	105
2.3.36	OriginalValue	106
2.3.37	IsSimple	107
2.3.38	ContentOffset	107
2.3.39	StreamName	108
2.3.40	Sizing	109
2.3.41	LinkToChild	109
2.3.42	PrintOnFirstPage	110
2.3.43	PrintBetweenSections (RPL 10.4)	110
2.3.44	FormattedValueExpressionBased	111
2.3.45	ProcessedWithError	112
2.3.46	ImageMIMEType	113
2.3.47	ImageName	113
2.3.48	Width	114
2.3.49	Height	115
2.3.50	HorizontalResolution	115
2.3.51	VerticalResolution	116
2.3.52	RawFormat	116
2.3.53	Hyperlink	117
2.3.54	BookmarkLink	117
2.3.55	DrillthroughId	118

2.3.56	DrillthroughUrl	119
2.3.57	BorderColor	119
2.3.58	BorderColorLeft	120
2.3.59	BorderColorRight	120
2.3.60	BorderColorTop	121
2.3.61	BorderColorBottom	122
2.3.62	BorderStyle	122
2.3.63	BorderStyleLeft	123
2.3.64	BorderStyleRight	123
2.3.65	BorderStyleTop	124
2.3.66	BorderStyleBottom	124
2.3.67	BorderWidth	125
2.3.68	BorderWidthLeft	126
2.3.69	BorderWidthRight	126
2.3.70	BorderWidthTop	127
2.3.71	BorderWidthBottom	127
2.3.72	PaddingLeft	128
2.3.73	PaddingRight	129
2.3.74	PaddingTop	129
2.3.75	PaddingBottom	130
2.3.76	FontStyle	130
2.3.77	FontFamily	131
2.3.78	FontSize	132
2.3.79	FontWeight	132
2.3.80	Format	133
2.3.81	TextDecoration	133
2.3.82	TextAlign	134
2.3.83	VerticalAlign	134
2.3.84	Color	135
2.3.85	LineHeight	135
2.3.86	Direction	136
2.3.87	WritingMode	137
2.3.88	UnicodeBiDi	137
2.3.89	BackgroundImage	138
2.3.90	BackgroundColor	138
2.3.91	BackgroundRepeat	139
2.3.92	NumeralLanguage	139
2.3.93	NumeralVariant	140
2.3.94	Calendar	141
2.3.95	ColumnHeaderRows	141
2.3.96	RowHeaderColumns	142
2.3.97	ColsBeforeRowHeader	143
2.3.98	LayoutDirection	143
2.3.99	DefinitionPath	144
2.3.100	Level	144
2.3.101	MemberCellIndex	145
2.3.102	CellItemOffset	146
2.3.103	ColSpan	146
2.3.104	RowSpan	147
2.3.105	DefIndex	148
2.3.106	ColumnIndex	148
2.3.107	RowIndex	149
2.3.108	GroupLabel	150

2.3.109	RecursiveToggleLevel	150
2.3.110	ListStyle.....	151
2.3.111	ListLevel.....	152
2.3.112	ParagraphNumber	152
2.3.113	RightIndent.....	153
2.3.114	LeftIndent.....	154
2.3.115	HangingIndent	154
2.3.116	SpaceBefore.....	155
2.3.117	SpaceAfter	155
2.3.118	FirstLine.....	156
2.3.119	Markup.....	156
2.3.120	ContentTop	157
2.3.121	ContentLeft.....	158
2.3.122	ContentWidth	158
2.3.123	ContentHeight.....	159
2.3.124	State.....	160
2.3.125	CellItemState	160
2.3.126	MemberDefState	161
2.4	Enumerations.....	162
2.4.1	SortOptions.....	162
2.4.2	Sizings.....	162
2.4.3	ShapeType.....	162
2.4.4	ImageRawFormat.....	162
2.4.5	FontStyles.....	163
2.4.6	FontWeights.....	163
2.4.7	TextDecorations	163
2.4.8	TextAlignments	164
2.4.9	VerticalAlignments	164
2.4.10	Directions.....	164
2.4.11	WritingModes	165
2.4.12	UnicodeBiDiTypes.....	165
2.4.13	Calendars.....	165
2.4.14	BorderStyles	166
2.4.15	BackgroundRepeatTypes	166
2.4.16	ListStyles	166
2.4.17	MarkupStyles	167
2.4.18	TypeCode.....	167
2.4.19	StateValues.....	167
2.4.20	TablixMemberStateValues.....	169
2.4.21	TablixMemberDefStateValues	169
2.4.22	RPLSize.....	170
3	Structure Examples	172
3.1	Line	172
3.2	Image.....	173
3.3	Chart	174
3.4	GaugePanel.....	176
3.5	SubReport.....	178
3.6	RichTextBox.....	180
3.7	Tablix.....	186
3.8	Report.....	193
3.9	Report 2008.....	209

4 Security Considerations	225
5 Appendix A: Product Behavior	226
6 Change Tracking	231
7 Index.....	234

1 Introduction

The Report Page Layout (RPL) Stream Format Structure Specification specifies the Report Page Layout stream format. The RPL stream format is an internal binary format used by Microsoft® SQL Server® Reporting Services when communicating with viewer controls, to offload some of the rendering work from the server to the client viewer control. By using RPL, implementers can create custom report designers that will create RPL, as well as custom report renderers that process and display RPL to display reports.

1.1 Glossary

The following terms are defined in [\[MS-GLOS\]](#):

Augmented Backus-Naur Form (ABNF)
big-endian
little-endian
stream
object
Unicode

The following terms are specific to this document:

absolute URL: A URL that specifies the exact [Location](#) of a [Report](#), and that takes the form protocol://hostname/other_information (ex: http://www.msn.com/myReport.rdl).

action: An interactivity event such as a hyperlink, bookmark link, or drillthrough link that is associated with an item in a **report**.

ancestor: A record that contains or is contained in another record.

body area: The area containing the detail and grouped data within a **page**.

body: The main component of the **report** within which the details and contents are included.

bookmark: An anchor that is used in a **report** to assist navigation, typically through the use of hyperlinks. Bookmarks are specified by the [Bookmark](#) element.

calendar: A property that allows the user to format dates based on the [Calendar](#) used.

chart: Displays data or the relationships between sets of data in a visual form. A chart instance is specified by using the [Chart](#) element.

column header: The header area of a column in a data region layout. The tablix column header is specified by the [TablixColumnHeader](#) element.

column member: An ordered list of members within a column **hierarchy** of a data region. **Tablix** column members are specified by the [TablixColMembersDef](#) element.

document map: A navigation pane that is generated at run time from labels specified in a report definition.

drillthrough report: A report that can be executed and viewed after clicking a **report item** that contains an action with a drillthrough link.

element: The data that makes up an array of structures. Each element inherits the attributes from the parent structure.

enumeration: A fixed set of integer values or **String** constants that are used to specify the value of certain properties.

footer area: The area at the bottom of each **page** of a **report** containing the layout of **report items**. The layout is specified by the [PageFooterElement](#) record.

gauge panel: The encompassing outer element that contains one or more radial gauges and linear gauges. Use the gauge panel to define properties that apply to all gauges in a gauge panel. A gauge panel instance is specified by using the [GaugePanel](#) element.

grandparent record: A type of **ancestor** record that contains child records. The record specifies the parent's **element** of the current record.

header area: The area at the top of each **page** of a **report** containing the layout of **report items**. The layout is specified by the [PageHeaderElement](#) record.

hierarchy: A logical tree structure that organizes a record such that each member has one parent member and zero or more child members.

horizontal resolution: The number of elements, dots, or columns from left to right in a fixed area—typically one inch. The resolution is specified by a [HorizontalResolution](#) element with a floating point value.

image: A rectangular grid of pixels that has a definite height and a definite width and is specified by the [Image](#) element.

image map: An image map is comprised of one or more areas that specify the coordinates of a clickable region of an **image**.

image map area: A set of coordinates in an **image map** making a polygon that can be assigned an **action**. The image map area is specified by the [ImageMapArea](#) element.

language: A text value that contains a language and culture code. The value of the language is specified by the [Language](#) element.

MIME type: A method that is used by protocol clients to associate files of a certain type (such as specific image formats) with applications that can open or access files of that type.

page: Specifies information pertaining to [PageContent](#). The details provided for a page include properties, header, and footer. A page is specified by the [Page](#) element.

parent record: An **ancestor** record. The record specifies the containing **element** that is a record.

physical-page oriented renderer: A renderer that generates page breaks based on physical measurements. The renderer can set properties to precisely control how the pages will break in reports.

raw format: Defines the contents of a raw image that has all the information needed to create an **image**. The format of an image is specified by the [RawFormat](#) element.

recursive toggle: Enables the user to toggle the display of the hidden data in a tablix **column header** and **row header**. The recursive toggling for the **tablix** is specified by the [RecursiveToggleLevel](#) element.

report item: An object that exists on a report layout. A report item is defined by the [ReportItem](#) element.

rich text box: A text box with advanced features, specified by the [RichTextBox](#) element.

report: A collection of information comprising data, layout, and properties. A report is specified by the Report element.

row header: Contains any **report item** that is set to be displayed in the row **header area** of a **tablix**. The row header area contains the headers of the visible row fields of a tablix data region. The row header of a tablix is specified by the [TablixRowHeader](#) element.

row member: A member in a data region layout that represents a row, including an optional header, an optional grouping of data, and an optional inner **hierarchy**.

RPLIF: An RPL Stamp, which is a **String** value that specifies the type of the stream. The current value of the RPL Stamp is "RPLIF" for an RPL stream.

section: Specifies the layout and structure information of a **report**. A **report section** is comprised of a **body**, a header, and a footer. A section is specified by the [Section](#) element.

sort state: Specifies how the data in a **report item** is organized. The sort state is defined by the [SortState](#) property.

stream name: A **String** value that uniquely identifies the name of a stream for an item. The stream name is specified by the [StreamName](#) element.

tablix: A data region that contains rows and columns resembling a table or matrix, possibly sharing characteristics of both. A tablix instance is specified by the [Tablix](#) element.

tablix body area: The area containing the detail and grouped data within a **tablix**.

tablix member: An ordered list of members for a tablix row **hierarchy** or a tablix column hierarchy in a **tablix** data region. The tablix member can contain a nested tablix members list.

text decoration: A visual ornamentation added to the text, specified by the [TextDecoration](#) element.

text run: The value and formatting of a contiguous span of text. A text run is specified by the [TextRun](#) element.

toggle state: Defines the value that specifies the current state of toggle of a control, which is either expanded or collapsed. The toggle state is defined by the [ToggleState](#) property.

token: The byte that specifies the start of a record.

version: A number that identifies the specific release and version of RPL. The version is specified by using major, minor, and build fields.

vertical resolution: The number of rows, dots, or lines from top to bottom on a fixed area—typically one inch. The vertical resolution is specified by a [VerticalResolution](#) element with a floating point value.

zIndex: Specifies the drawing order of an item within the containing item. Items are drawn in order according to the **zIndex element** for the item. Items with lower indices are drawn first, appearing behind items with higher indices.

MAY, SHOULD, MUST, SHOULD NOT, MUST NOT: These terms (in all caps) are used as described in [\[RFC2119\]](#). All statements of optional behavior use either MAY, SHOULD, or SHOULD NOT.

1.2 References

1.2.1 Normative References

We conduct frequent surveys of the normative references to assure their continued availability. If you have any issue with finding a normative reference, please contact dochelp@microsoft.com. We will assist you in finding the relevant information. Please check the archive site, <http://msdn2.microsoft.com/en-us/library/E4BD6494-06AD-4aed-9823-445E921C9624>, as an additional source.

[ISO-639] International Organization for Standardization, "Codes for the Representation of Names of Languages", ISO 639, <http://www.loc.gov/standards/iso639-2/>

[ISO-3166-1] International Organization for Standardization, "ISO 3166-1 decoding table", ISO 3166, http://www.iso.org/iso/iso-3166-1_decoding_table

[MS-GLOS] Microsoft Corporation, "[Windows Protocols Master Glossary](#)", March 2007.

[MS-RDL200801] Microsoft Corporation, "Report Definition Language (RDL) 2008", <http://schemas.microsoft.com/sqlserver/reporting/2008/01/reportdefinition>

[RFC2119] Bradner, S., "Key words for use in RFCs to Indicate Requirement Levels", BCP 14, RFC 2119, March 1997, <http://www.ietf.org/rfc/rfc2119.txt>

[RFC5234] Crocker, D., Ed., and Overell, P., "Augmented BNF for Syntax Specifications: ABNF", STD 68, RFC 5234, January 2008, <http://www.ietf.org/rfc/rfc5234.txt>

[RFC2781] Hoffman, P., and Yergeau, F., "UTF-16, an encoding of ISO 10646", RFC 2781, February 2000, <http://www.ietf.org/rfc/rfc2781.txt>

1.2.2 Informative References

[MS-RDL200501] Microsoft Corporation, "Report Definition Schema", <http://schemas.microsoft.com/sqlserver/reporting/2005/01/reportdefinition>

[MS-RDLS05SPEC] Microsoft Corporation, "Report Definition Language Specification", November 2005, <http://download.microsoft.com/download/c/2/0/c2091a26-d7bf-4464-8535-dbc31fb45d3c/rdlNov05.pdf>

[MS-RDLS08SPEC] Microsoft Corporation, "Report Definition Language Specification", July 2008, http://download.microsoft.com/download/6/5/7/6575f1c8-4607-48d2-941d-c69622e11c32/RDL_spec_08.pdf

[MS-RS2008WP] Microsoft Corporation, "Microsoft SQL Server 2008 Reporting Services White Paper", August 2007, <http://download.microsoft.com/download/a/c/d/acd8e043-d69b-4f09-bc9e-4168b65aaa71/RSinSQL2008.doc>

1.3 Structure Overview (Synopsis)

This document specifies the Report Page Layout (RPL) format, a binary stream format that is used to represent metadata for a **page** of a **report**. The **stream** is described by a collection of nested records, each of which contains information about the type of the record, and where applicable, type-specific fields that further specify the record. Type-specific fields contain information that further specify the RPL format. Specifications of the fields for a given record type are in the [Record](#) section.

For a detailed overview of specific file architecture and content, see [Stream Structure](#).

1.3.1 Byte Ordering

Some computer architectures number bytes in a binary word from left to right, which is referred to as **big-endian**. This documentation uses big-endian bit diagrams. Other architectures number the bytes in a binary word from right to left, which is referred to as **little-endian**. The underlying stream format **enumerations**, **objects**, and records in RPL are stored in little-endian.

Using big-endian and little-endian methods, the number 0x12345678 would be stored as shown in the following table.

Byte order	Byte 0	Byte 1	Byte 2	Byte 3
Big-endian	0x12	0x34	0x56	0x78
Little-endian	0x78	0x56	0x34	0x12

1.3.2 Organization of This Documentation

Section [2](#) of this document is arranged with overviews of higher-level concepts, which are followed by more detailed concepts. Section 2.1, in particular, covers higher-level concepts that are required to understand the remainder of the document, and should be read before reading the remainder of section 2.

Section [2.1](#) specifies the structures and concepts that are used to organize and structure an RPL stream file.

Section [2.2](#) through section [2.2.73](#) specifies the details of each of the structures that can be included in an RPL stream.

Section [2.3](#) through section [2.3.126](#) specifies the details of each of the properties that can be included in an RPL stream.

Section [2.4](#) through section [2.4.22](#) specifies the details of each of the enumerations that can be included in an RPL stream.

Section [3](#) provides specific examples intended to illustrate the concepts, records, and structures of this stream format.

Appendix [5](#) is a list of version-specific behaviors. It is not intended to be read alone, but rather to be understood in the context of the specifications in section [2](#). Specifications in section [2](#) provide links to relevant items in the appendix.

1.4 Relationship to Protocols and Other Structures

The RPL binary stream format uses UTF-16 encoding of **Unicode** characters as specified in [\[RFC2781\]](#).

In addition to other file formats, RPL can be used as a protocol for reports that are created in Report Definition Language (RDL). The schema of the Report Definition Language is defined in [\[MS-RDL200801\]](#).

For more information about RDL, see [\[MS-RDL200501\]](#), [\[MS-RDLS05SPEC\]](#), and [\[MS-RDLS08SPEC\]](#).

The two protocols that carry RPL are HTTP and the Report Server ReportExecution Web service [\[MS-RSWSRE2005\]](#).

1.5 Applicability Statement

This document specifies the format for an RPL stream.

The RPL stream is applicable for use as a protocol to allow custom report designers to create rendering instructions in RPL, and to allow custom report renderers to process and display these rendering instructions to display reports

1.6 Versioning and Localization

This document covers versioning issues in the following areas:

Structure Versions: There are four **versions** of RPL. The structures and properties in this document apply to all versions; if a particular structure or properties applies only to a certain version, the version is specified.

The information in this specification is applicable to the following RPL versions: 10.3, 10.4, 10.5 and 10.6.

Localization: There are no localization-dependent structures in the RPL stream format.

1.7 Vendor-Extensible Fields

None.

2 Structures

This section specifies all RPL structures, including report structures, report properties, and enumerations, in an RPL stream and their associated grammar. Every structure includes the following:

- A definition of the structure.
- The ABNF grammar for the structure.
- A bit diagram of the structure.
- Definitions of all fields contained within the structure, including the sizes of all related structures. Fields following a variable length field can be unaligned; that is, they can start on an even or an odd byte boundary from the beginning of the structure.

2.1 Stream Structure

This section specifies the overall structure of a stream that conforms to this specification.

The stream structure contains a series of [records](#). Each record contains zero or more structured fields that contain the report layout.

2.1.1 RPL Stream

This document specifies the structures and format required to create an RPL stream. The RPL stream **MUST** have only one [Report](#) record and the stream **MUST** be written as a series of binary records that preserve the report **hierarchy**.

The left and top properties of an item are relative to a parent. **Report item** measurements are saved at the parent level. The stream has a built-in offset-based hierarchy that allows a reader to jump from a parent to a child and read the rendering runtime sizes without having to read all the properties. All offsets are stored on 8 bytes. To optimize space, some structures are shared between report items so they will be written only once. All numeric values are declared as **Int32** unless otherwise specified. **Datetime** values are written as long values.

This document uses Augmented Backus-Naur Form (ABNF) as specified in [\[RFC5234\]](#) to specify the sequence for RPL records.

This document uses information from Report Definition Language (RDL) as described in [\[MS-RDLS08SPEC\]](#) and [\[RS2008WP\]](#) to describe the RPL records.

2.1.2 Record

A record is the basic building block used to store information about a report. Each record is a variable-length sequence of bytes. A record consists of two components: a record type and the record data that is specific to that record type.

The record type is one byte that specifies what type of information is specified by the record and how the structure of the record data pertaining to the record is ordered and structured. The record value is dependent on the type of data that is specific to that record.

2.1.3 Simple Data Type Structures

The following table specifies the data types in an RPL stream.

Data type	Description format
Int64	Represents a 64-bit (8-byte) signed integer.
Int32	Represents a 32-bit (4-byte) signed integer.
Float	Represents a 32-bit (4-byte) single-precision floating point value.
Boolean	Represents an 8-bit (1-byte) logical Boolean type value that MUST be true (1) or false (0).
Long	Represents a 64-bit (8-byte) signed integer.
String	All String values within the protocol MUST be UNICODE UTF-16. By default, all String values start with an integer that defines the length of the String . String values are represented in the protocol as an array of bytes; the number of bytes MUST be equal to the number of characters in the String multiplied by two.

2.1.3.1 Writing Strings to an RPL Stream

Strings are written as a length-prefixed **String** to the RPL stream using UTF-16 encoding as specified in [\[RFC2781\]](#). After the length of the string is written, the current position of the stream is advanced in accordance with the encoding and the specific characters being written to the stream.

2.1.3.2 Writing the Length Value of the String to an RPL Stream

The length of a **String** is written to the RPL stream seven bits at a time, starting with the seven least-significant bits. The high bit of a byte indicates whether there are more bytes to be written after the current one.

If a value fits in seven bits, the value takes only one byte of space. If the value does not fit in seven bits, the high bit is set on the first byte and written out. The value is then shifted by seven bits and the next byte is written. This process is repeated until the entire integer has been written.

2.1.3.3 Reading Strings from an RPL Stream

Strings MUST be prefixed with an integer that defines the length of the **String** and is encoded using the rules specified in section [2.1.3.2](#).


2.2 Report Structures

This section defines all the report structures along with their definitions, grammar, and a bit diagram. The structures include the definitions and sizes of their related structures and **elements**.

2.2.1 Report

The **Report** record is the root record of the [RPL Stream](#) and specifies the content of the stream. There MUST be one and only one record of this type in the stream.

```
Report = RPLStamp Version reportStart ReportProperties *PageContent OffsetsArrayElement
ReportElementEnd Version
```

RPLStamp (variable): A **String** that specifies the type of the stream. The value of the **RPLStamp** field MUST be "**RPLIF**".<1>

version (6 bytes): A [Version](#) record that specifies the version of RPL used to generate the RPL stream. The value of this **Version** record MUST be the same as the subsequent **Version** record in the stream.

reportStart (1 byte): A byte that specifies the start of the **Report** record content. The value of the **reportStart** field MUST be 0x00.

properties (variable): A [ReportProperties](#) record that specifies the properties applicable to the **Report** record.

pages (variable): An array of [PageContent](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [OffsetArrayElement](#) record specified by the **offsetsArrayElement** field.

offsetsArrayElement (variable): An **OffsetsArrayElement** record that specifies the position of pages in the RPL stream.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Report** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **offsetsArrayElement** field of the **Report** record in the RPL stream.

version (6 bytes): A **Version** record that specifies the version of RPL used to generate the RPL stream. The value of this **Version** record MUST be the same as the previous **Version** record in the stream.

2.2.2 Version

The **Version** record specifies the version of RPL that is used in the current stream.

Version = majorVersion minorVersion build

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
majorVersion										minorVersion										build											
...																															

majorVersion (1 byte): A field that represents the major version of RPL that is used in the stream. The value of the **majorVersion** field MUST be 0x0A.

minorVersion (1 byte): A field that represents the minor version of RPL that is used in the stream. The value of the **minorVersion** field MUST be 0x03 or 0x04 or 0x05 or 0x06. [<2>](#)

build (4 bytes): An integer that represents the build version of RPL that is used in the stream. The value of the **build** field MUST be 0x00000000 or 0x00000001 when **minorVersion** is RPL version 10.3 and MUST be 0x00000000 when **minorVersion** is RPL version 10.4 or 10.5 or 10.6.

2.2.3 ReportProperties

The **ReportProperties** record specifies the properties applicable to a [Report](#) record.

ReportProperties = reportPropertiesStart [itemProperties] delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
reportPropertiesStart										itemProperties (variable)										...											

delimiter

reportPropertiesStart (1 byte): A byte that specifies the start of the **ReportProperties** record. The value of the **reportPropertiesStart** field MUST be 0x02.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The collection can be empty. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
Description
Location
Language
ExecutionTime
Author
AutoRefresh
ReportName
ConsumeContainerWhiteSpace

delimiter (1 byte): A byte that specifies the end of the **ReportProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.4 OffsetsArrayElement

The **OffsetsArrayElement** record specifies information about the position of the **reportStart** field of the [Report](#) record in the RPL stream and the position of the **reportElementEnd** field of the [PageContent](#) records that are part of a **Report** record.

OffsetsArrayElement = offsetsArrayElementStart offset count offsetsPageContent

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
offsetsArrayElementStart										offset																					
...																															
...										count																					
...										offsetsPageContent (variable)																					

...

offsetsArrayElementStart (1 byte): A byte that specifies the start of the **OffsetsArrayElement** record. The value of the **offsetsArrayElementStart** field MUST be 0x12.

offset (8 bytes): A signed integer that specifies the position of the **reportStart** field of the **parent record** of type **Report** in the RPL stream.

count (4 bytes): A signed integer that MUST be equal to the number of **PageContent** records in the parent **Report** record.

offsetsPageContent (variable): An array of 8-byte signed integers. The number of elements in the array MUST be equal to the value of the **count** field. Every element of the array MUST specify the position of the corresponding **reportElementEnd** field of the **PageContent** record in the RPL stream. The order of the elements in the array MUST match the order of the **PageContent** records in the parent **Report** record.

2.2.5 PageContent

The **PageContent** record specifies the content of a page.

2.2.5.1 PageContent (RPL 10.6)

Applies to RPL version 10.6 and later

The **PageContent** record specifies the content of a page of a report.

PageContent = pageContentStart PageLayout *Section Measurements [PageLayout] ReportElementEnd

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
pageContentStart										pageLayoutStar (variable)																							
...																																	
sections (variable)																																	
...																																	
measurements (variable)																																	
...																																	
pageLayoutEnd (variable)																																	

...									
reportElementEnd									
...									
...									

pageContentStart (1 byte): A byte that specifies the start of the **PageContent** record. The value of the **pageContentStart** field MUST be 0x13.

pageLayoutStar (variable): A [PageLayout](#) record that specifies properties that are applicable to the **PageContent** record.

sections (variable): An array of [Section](#) records. The number of records in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field in the **PageContent** record.

measurements (variable): A record of type **Measurements** that specifies the size, location, and state properties for every element of the sections array. The order of elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of **Section** records in the sections array. [<3>](#)

pageLayoutEnd (variable): A **PageLayout** record that specifies properties that are applicable to the **PageContent** record. If the same property is specified as part of the **pageLayoutStart** and **pageLayoutEnd** fields, the value that is specified as **pageLayoutEnd** MUST be used.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **PageContent** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **PageContent** record in the RPL stream.

2.2.5.2 PageContent (RPL 10.4 and 10.5)

Applies to RPL version 10.4 and 10.5

The **PageContent** record specifies the content of a page of a report.

PageContent = pageContentStart PageLayout *Section Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	1	2	3	4	5	6	7	8	9	20	1	2	3	4	5	6	7	8	9	30	1		
pageContentStart										pageLayout (variable)																							
...																																	
sections (variable)																																	

...
measurements (variable)
...
reportElementEnd
...
...

pageContentStart (1 byte): A byte that specifies the start of the **PageContent** record. The value of the **pageContentStart** field MUST be 0x13.

pageLayout (variable): A [PageLayout](#) record that specifies properties applicable to the **PageContent** record.

sections (variable): An array of [Section](#) records. The number of records in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field in the **PageContent** record.

measurements (variable): A record of type **Measurements** that specifies the size, location, and state properties for every element of the **sections** array. The order of elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of **Section** records in the **sections** array.<4>

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **PageContent** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **PageContent** record in the RPL stream.

2.2.5.3 PageContent (RPL 10.3)

Applies to RPL version 10.3

The **PageContent** record specifies the content of a page of a report.

PageContent = pageContentStart BodyAreaElement Page Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
pageContentStart										bodyArea (variable)																					
...																															

page (variable)
...
measurements (variable)
...
reportElementEnd
...
...

pageContentStart (1 byte): A byte that specifies the start of the **PageContent** record. The value of the **pageContentStart** field MUST be 0x13.

bodyArea (variable): A [BodyAreaElement](#) record that specifies the content of the **body area** of the **PageContent** record.

page (variable): A [Page](#) record that specifies the properties, header, and footer of a page.

measurements (variable): A record of type [Measurements](#) that specifies the size, location, and state properties for the **bodyArea** record and for the **pageHeaderElement** and **pageFooterElement** fields of the **Page** record.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **PageContent** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **PageContent** record in the RPL stream.

2.2.6 Page

Applies to RPL version 10.3

The **Page** record specifies the properties, header, and footer that apply to a [PageContent](#) record.

Page = pageStart PageProperties [PageHeaderElement] [PageFooterElement] delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
pageStart										pageProperties (variable)																										
...																																				
pageHeaderElement (variable)																																				

...	
pageFooterElement (variable)	
...	
delimiter	

pageStart (1 byte): A byte that specifies the start of the **Page** record. The value of the **pageStart** field MUST be 0x01.

pageProperties (variable): A [PageProperties](#) record that specifies the properties applicable to the **Page** record.

pageHeaderElement (variable): A [PageHeaderElement](#) record that specifies the content of the **header area** of a **Page** record.

pageFooterElement (variable): A [PageFooterElement](#) record that specifies the content of the **footer area** of a **Page** record.

delimiter (1 byte): A byte that specifies the end of the **Page** record. The value of the **delimiter** field MUST be 0xFF.

2.2.7 PageProperties

Applies to RPL version 10.3

The **PageProperties** record specifies the properties applicable to a [Page](#) record.

```
PageProperties = pagePropertiesStart [itemProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
pagePropertiesStart										itemProperties (variable)																					
...																															
delimiter																															

pagePropertiesStart (1 byte): A byte that specifies the start of the **PageProperties** record. The value of the **pagePropertiesStart** field MUST be 0x03.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The collection can be empty. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
ID
UniqueName
PageHeight
PageWidth
MarginTop
MarginLeft
MarginBottom
MarginRight
Columns
ColumnSpacing
Style

delimiter (1 byte): A byte that specifies the end of the **PageProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.8 PageLayout

Applies to RPL version 10.4 and later

The **PageLayout** record specifies the properties applicable to a [PageContent](#) record.

```
PageLayout = pagePropertiesStart [itemProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
pagePropertiesStart										itemProperties (variable)																							
...																																	
delimiter																																	

pagePropertiesStart (1 byte): A byte that specifies the start of the **PageLayout** record. The value of the **pagePropertiesStart** field MUST be 0x03.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The collection can be empty. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
PageHeight
PageWidth
MarginTop
MarginLeft
MarginBottom
MarginRight
Style
PageName (RPL 10.6)

delimiter (1 byte): A byte that specifies the end of the **PageLayout** record. The value of the **delimiter** field MUST be 0xFF.

2.2.9 Section

Applies to RPL version 10.4 and later

The **Section** record specifies the structure and layout information for a report **section**. Every report section is defined by a **body**, a header, and a footer.

Section = SimpleSection / MixedSection

2.2.10 SimpleSection

Applies to RPL version 10.4 and later

The **SimpleSection** record specifies the structure and layout for one report section.

SimpleSection = sectionStart SectionProperties BodyAreaElement [PageFooterElement]
[PageHeaderElement] Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
sectionStart										sectionProperties (variable)																					
...																															
bodyAreaElement (variable)																															
...																															

pageFooterElement (variable)
...
pageHeaderElement (variable)
...
measurements (variable): (variable)
...
reportElementEnd
...
...

sectionStart (1 byte): A byte that specifies the start of the **SimpleSection** record. The value of the **sectionStart** field MUST be 0x15.

sectionProperties (variable): A [SectionProperties](#) record that specifies the properties applicable to the **SimpleSection** record.

bodyAreaElement (variable): A [BodyAreaElement](#) record that specifies the content of the body area of the **SimpleSection** record.

pageFooterElement (variable): A [PageFooterElement](#) record that specifies the content of the footer area of the **SimpleSection** record.

pageHeaderElement (variable): A [PageHeaderElement](#) record that specifies the content of the header area of the **SimpleSection** record.

measurements (variable): (variable): A [Measurements](#) record that specifies the size, location, and state properties for **BodyAreaElement**, **PageFooterElement**, and **PageHeaderElement** records. The order of the elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of the **BodyAreaElement**, **PageFooterElement**, and **PageHeaderElement** records in the **SimpleSection** record. <5>

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **SimpleSection** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **SimpleSection** record in the RPL stream.

2.2.11 MixedSection

Applies to RPL version 10.4 and later

The **MixedSection** record specifies the structure and layout information for more than one report section.

MixedSection = sectionStart SectionProperties BodyAreaElement [PageFooterElement] Section
 [PageHeaderElement] Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
sectionStart										sectionProperties (variable)																							
...																																	
bodyAreaElement (variable)																																	
...																																	
pageFooterElement (variable)																																	
...																																	
section (variable)																																	
...																																	
pageHeaderElement (variable)																																	
...																																	
measurements (variable)																																	
...																																	
reportElementEnd																																	
...																																	
...																																	

sectionStart (1 byte): A byte that specifies the start of the **MixedSection** record. The value of the **sectionStart** field MUST be 0x15.

sectionProperties (variable): A [SectionProperties](#) record that specifies the properties applicable to the **MixedSection** record.

bodyAreaElement (variable): A [BodyAreaElement](#) record that specifies the content of the body area of the **MixedSection** record.

pageFooterElement (variable): A [PageFooterElement](#) record that specifies the content of the footer area of the **MixedSection** record.

section (variable): A [Section](#) record that specifies the content of the subsequent section in the sections field array of the [PageContent \(RPL 10.4\)](#) record.

pageHeaderElement (variable): A [PageHeaderElement](#) record that specifies the content of the header area of the **MixedSection** record.

measurements (variable): A [Measurements](#) record that specifies the size, location, and state properties for **BodyAreaElement**, **PageFooterElement**, and **PageHeaderElement** records. The order of the elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of the **bodyAreaElement**, **pageFooterElement**, and **pageHeaderElement** records in the **MixedSection** record. <6>

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **MixedSection** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **MixedSection** record in the RPL stream.

2.2.12 SectionProperties

Applies to RPL versions 10.4, 10.5, and later

The **SectionProperties** record specifies the properties applicable to a [Section](#) record.

SectionProperties = sectionPropertiesStart [itemProperties] delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
sectionPropertiesStart										itemProperties (variable)																					
...																															
delimiter																															

sectionPropertiesStart (1 byte): A byte that specifies the start of the **SectionProperties** record. The value of the **sectionPropertiesStart** field MUST be 0x16.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The collection can be empty. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
ID
ColumnCount

Property
ColumnSpacing

delimiter (1 byte): A byte that specifies the end of the **SectionProperties** record. The value of this field MUST be 0xFF.

2.2.13 BodyAreaElement

The **BodyAreaElement** record specifies the content of the body area of a [Section](#) or, in RPL 10.3, a [PageContent](#) record.

2.2.13.1 BodyAreaElement (RPL 10.4)

Applies to RPL version 10.4 and later

The **BodyAreaElement** record specifies the content of the body area of a section.

BodyAreaElement = columns *BodyElement Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
columns										bodyArea (variable)																										
...																																				
measurements (variable)																																				
...																																				
reportElementEnd																																				
...																																				
...																																				

columns (1 byte): A byte that specifies the start of the **BodyAreaElement** record. The value of the **columns** field MUST be 0x14.

bodyArea (variable): An array of [BodyElement](#) records. The number of elements in the **bodyArea** array MUST be equal to the value of the **count** field of the [Measurements](#) record specified in the **measurements** field of the **BodyAreaElement** record. The number of elements MUST NOT be greater than the **ColumnCount** property specified in the [SectionProperties](#) record. <7>

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element in the **bodyArea** array. The order of the elements in the

measurementsContent field array of the **Measurements** record MUST match the order of the **BodyElement** records in the **bodyArea** array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **BodyAreaElement** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **BodyAreaElement** record in the RPL stream.

2.2.13.2 BodyAreaElement (RPL 10.3)

Applies to RPL version 10.3

The **BodyAreaElement** record specifies the content of the body of a page.

BodyAreaElement = columns *BodyElement Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
columns										bodyArea (variable)																										
...																																				
measurements (variable)																																				
...																																				
reportElementEnd																																				
...																																				
...																																				

columns (1 byte): A byte that specifies the start of the **BodyAreaElement** record. The value of the **columns** field MUST be 0x14.

bodyArea (variable): An array of [BodyElement](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field. The number of elements MUST NOT be greater than the [Columns](#) property specified in the [Page](#) record.<8>

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **bodyArea** array. The order of the elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of **BodyElement** records in the **bodyArea** array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **BodyAreaElement** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **BodyAreaElement** record's **measurements** field in the RPL stream.

2.2.14 PageHeaderElement

The **PageHeaderElement** record specifies the content of the header area of a [Section](#) or [Page](#) record.

PageHeaderElement = pageHeader [ElementProperties] *ReportItems Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
pageHeader										elementProperties (variable)																										
...																																				
reportItems (variable)																																				
...																																				
measurements (variable)																																				
...																																				
reportElementEnd																																				
...																																				
...																																				

pageHeader (1 byte): A byte that specifies the start of the **PageHeaderElement** record. The value of the **pageHeader** field MUST be 0x04.

elementProperties (variable): A record of type [ElementProperties](#) that specifies a collection of properties applicable to the **PageHeaderElement** record. The order of the structures in the collection is arbitrary. The collection can be empty. Each structure contained in the **elementProperties** field MUST be one of the following.

Property
ID
Style
PrintOnFirstPage
PrintBetweenSections (RPL 10.4)
UniqueName

reportItems (variable): An array of [ReportItem](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field.

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **reportItems** field array. The order of elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of **ReportItem** records in the **reportItems** field array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **PageHeaderElement** record. The **offset** of the **ReportElementEnd** record MUST specify the position of the **measurements** field in the RPL stream.

2.2.15 PageFooterElement

The **PageFooterElement** record specifies the content of the footer area of a [Section](#) or [Page](#) record.

PageFooterElement = pageFooter [ElementProperties] *ReportItems Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
pageFooter										elementProperties (variable)																							
...																																	
reportItems (variable)																																	
...																																	
measurements (variable)																																	
...																																	
reportElementEnd																																	
...																																	
...																																	

pageFooter (1 byte): A byte that specifies the start of the **PageFooterElement** record. The value of the **pageFooter** field MUST be 0x05.

elementProperties (variable): A record of type [ElementProperties](#) that specifies a collection of properties applicable to the **PageFooterElement** record. The order of the structures in the

collection is arbitrary. Each structure contained in the **elementProperties** field MUST be one of the following.

Property
ID
Style
PrintOnFirstPage
PrintBetweenSections (RPL 10.4)
UniqueName

reportItems (variable): An array of [ReportItem](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field.

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **reportItems** field array. The order of elements in the array MUST match the order of **ReportItem** records in the **reportItems** field array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **PageFooterElement** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **PageFooterElement** in the RPL stream.

2.2.16 BodyElement

The **BodyElement** record specifies the content of an element of the **bodyArea** field array of the **BodyAreaElement** record.

BodyElement = body [ElementProperties] *ReportItem ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
body										elementProperties (variable)																										
...																																				
reportItems (variable)																																				
...																																				
measurements (variable)																																				
...																																				

reportElementEnd	
...	
...	

body (1 byte): A byte that specifies the start of a **BodyElement** record. The value of the **body** field MUST be 0x06.

elementProperties (variable): A record of type [ElementProperties](#) that specifies a collection of properties applicable to the **BodyElement** record. The order of the structures in the collection is arbitrary. Each structure contained in the **elementProperties** field MUST be one of the following.

Property
ID
Style
UniqueName

reportItems (variable): An array of [ReportItem](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified by the **measurements** field.

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **reportItems** field array. The order of elements in the **measurementsContent** field array of the **Measurements** record MUST match the order of the **ReportItem** records in the **reportItems** field array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **BodyElement** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **BodyElement** record in the RPL stream.

2.2.17 ElementProperties

The **ElementProperties** record specifies the properties applicable to the [BodyElement](#), [PageHeaderElement](#), [PageFooterElement](#), [ReportItem](#), [TextRun](#), and [Paragraph](#) records.

```
ElementProperties = elementPropertiesStart SharedElementProperties
[NonSharedElementProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1						
elementPropertiesStart										sharedElementProperties (variable)																											
...																																					

nonSharedElementProperties (variable)	
...	
delimiter	

elementPropertiesStart (1 byte): A byte that specifies the start of the **ElementProperties** record. The value of the **elementPropertiesStart** field MUST be 0x0F.

sharedElementProperties (variable): A [SharedElementProperties](#) record.

nonSharedElementProperties (variable): A [NonSharedElementProperties](#) record.

delimiter (1 byte): A byte that specifies the end of the **ElementProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.18 SharedElementProperties

The **SharedElementProperties** record specifies the properties that can be shared by multiple [ElementProperties](#) records.

`SharedElementProperties = UseSharedElementProperties / InlineSharedElementProperties`

2.2.19 UseSharedElementProperties

The **UseSharedElementProperties** record specifies the location of shared properties applicable to a **grandparent record** in the RPL stream.

`UseSharedElementProperties = useShared offset`

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
useShared										offset																										
...																																				
...																																				

useShared (1 byte): A byte that specifies the start of the **UseSharedElementProperties** record. The value of the **useShared** field MUST be 0x02.

offset (8 bytes): A signed integer that MUST specify the start of an [ElementProperties](#) record in the RPL stream, which MUST have an [InlineSharedElementProperties](#) record.

2.2.20 InlineSharedElementProperties

The **InlineSharedElementProperties** record specifies the properties that can be shared by multiple [ElementProperties](#) records.

InlineSharedElementProperties = shared [itemProperties] delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
shared										itemProperties (variable)																										
...																																				
delimiter																																				

shared (1 byte): A byte that specifies the start of the **InlineSharedElementProperties** record. The value of the **shared** field MUST be 0x00.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. If the [OriginalValue](#) property and the [TypeCode](#) property are in the collection, the **OriginalValue** property MUST appear in the collection after the **TypeCode** property. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
ID
Name
Label
Bookmark
ToolTip
Style
ToggleItem
Slant
CanGrow
CanSort
CanShrink
Value
Formula
IsToggleParent

Property
TypeCode
OriginalValue
IsSimple
Sizing
LinkToChild
PrintOnFirstPage
PrintBetweenSections (RPL 10.4)
FormattedValueExpressionBased
ReportName
Markup
ListStyle
ListLevel
LeftIndent
RightIndent
HangingIndent
SpaceBefore
SpaceAfter

delimiter (1 byte): A byte that specifies the end of the **InlineSharedElementProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.21 NonSharedElementProperties

The **NonSharedElementProperties** record specifies the properties that are specific to its parent [ElementProperties](#) record. These properties are not shared by multiple **ElementProperties** records.

```
NonSharedElementProperties = nonShared [itemProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
nonShared										itemProperties (variable)																							
...																																	

delimiter

nonShared (1 byte): A byte that specifies the start of the **NonSharedElementProperties** record. The value of the **nonShared** field MUST be 0x01.

itemProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. If the [OriginalValue](#) property and the [TypeCode](#) property are in the collection, the **OriginalValue** property MUST appear in the array after the **TypeCode** property. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
UniqueName
Label
Bookmark
ToolTip
Style
ActionInfo
Value
ToggleState
SortState
IsToggleParent
TypeCode
OriginalValue
ProcessedWithError
ContentOffset
ContentHeight
ActionImageMapAreas
DynamicImageData
StreamName
ImageDataProperties
Language
Markup
ListStyle
ListLevel


Property
LeftIndent
RightIndent
HangingIndent
SpaceBefore
SpaceAfter
ParagraphNumber
FirstLine
ContentTop
ContentLeft
ContentWidth

delimiter (1 byte): A byte that specifies the end of the **NonSharedElementProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.22 Style

The **Style** record specifies the properties associated with the style for the parent record. The parent record for this property MUST be an [InlineSharedElementProperties](#), [NonSharedElementProperties](#), [PageProperties](#), or [PageLayout](#) record.

Style = styleStart [SharedStyleProperties] [NonSharedStyleProperties] [delimiter]



styleStart (1 byte): A byte that specifies the start of the **Style** record. The value of the **styleStart** field MUST be 0x06.

sharedStyleProperties (variable): A [SharedStyleProperties](#) record. This field MUST NOT be present if the parent record is **NonSharedElementProperties**. <9>

nonSharedStyleProperties (variable): A [NonSharedStyleProperties](#) record. This field MUST NOT be present if the parent record is **InlineSharedElementProperties**.<10>

The structures specified by the **sharedStyleProperties** and the **nonSharedStyleProperties** fields MUST be on the following list.

Property
BorderColor
BorderColorLeft
BorderColorRight
BorderColorTop
BorderColorBottom
BorderStyle
BorderStyleLeft
BorderStyleRight
BorderStyleTop
BorderStyleBottom
BorderWidth
BorderWidthLeft
BorderWidthRight
BorderWidthTop
BorderWidthBottom
PaddingLeft
PaddingRight
PaddingTop
PaddingBottom
FontStyle
FontFamily
FontSize
FontWeight
Format
TextDecoration
TextAlign


Property
VerticalAlign
Color
LineHeight
Direction
WritingMode
UnicodeBiDi
Language
BackgroundImage
BackgroundColor
BackgroundRepeat
NumeralLanguage
NumeralVariant
Calendar
ImageDataProperties

delimiter (1 byte): A byte that specifies the end of the **Style** record. The value of the **delimiter** field MUST be 0xFF. The field MUST be present when the parent record is **PageProperties** or **PageLayout**. The field MUST NOT be present when the parent record is **InlineSharedElementProperties** or **NonSharedElementProperties**.

2.2.23 SharedStyleProperties

The **SharedStyleProperties** record specifies the style properties that can be shared by multiple records.

SharedStyleProperties = shared [styleProperties] delimiter



shared (1 byte): A byte that specifies the start of the **SharedStyleProperties** record. The value of the **shared** field MUST be 0x00.

styleProperties (variable): A collection of structures that specifies style properties that are shared by multiple records. The order of the structures in the collection is arbitrary. The collection can be empty.

delimiter (1 byte): A byte that specifies the end of the **SharedStyleProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.24 NonSharedStyleProperties

The **NonSharedStyleProperties** record specifies the style properties that are specific to a record.

```
NonSharedStyleProperties = nonShared [styleProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
nonshared										styleProperties (variable)																					
...																															
delimiter																															

nonshared (1 byte): A byte that specifies the start of the **NonSharedStyleProperties** record. The value of the **nonshared** field MUST be 0x01.

styleProperties (variable): A collection of structures that specifies style properties that are specific to a record. The order of the structures in the collection is arbitrary. The collection can be empty.

delimiter (1 byte): A byte that specifies the end of the **NonSharedStyleProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.25 ActionInfo

The **ActionInfo** property specifies a structure that defines the actions for an [Image](#), [RichTextBox](#), or [TextRun](#) record. If this property is specified, it MUST be part of one of the following records:

- [Image.ElementProperties.NonSharedElementProperties](#)
- **RichTextBox.ElementProperties.NonSharedElementProperties**
- **TextRun.ElementProperties.NonSharedElementProperties**

```
ActionInfo = actionInfoStart [ActionInfoContent] delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
actionInfoStart										actionInfoContent (variable)																										
...																																				
delimiter																																				

actionInfoStart (1 byte): A byte that specifies the start of the **ActionInfo** record. The value of the **actionInfoStart** field MUST be one of the following.

Value	Parent record
0x07	ElementProperties.NonSharedElementProperties for Image ElementProperties.NonSharedElementProperties for RichTextBox
0x0B	ElementProperties.NonSharedElementProperties for TextRun

actionInfoContent (variable): An [ActionInfoContent](#) record.

delimiter (1 byte): A byte that specifies the end of the **ActionInfo** record. The value of the **delimiter** field MUST be 0xFF.

2.2.26 ActionInfoContent

The **ActionInfoContent** record specifies an array of [Action](#) records.

ActionInfoContent = actionsStart count actions

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
actionsStart										count																										
...										actions (variable)																										
...																																				

actionsStart (1 byte): A byte that specifies the start of the **ActionInfoContent** record. The value of the **actionsStart** field MUST be 0x02.

count (4 bytes): A signed integer that specifies the number of **Action** record elements in the array.

actions (variable): An array of **Action** records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.27 Action

The **Action** record specifies the properties of an **action**.

Action = actionStart actionInfoProperties delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
actionStart										actionInfoProperties (variable)																					
...																															
delimiter																															

actionStart (1 byte): A byte that specifies the start of the **Action** record. The value of the **actionStart** field MUST be 0x03.

actionInfoProperties (variable): A collection of structures that specifies the properties applicable to the **Action** record. The order of the structures in the collection is arbitrary. The **actionInfoProperties** collection can be empty. If the **actionInfoProperties** collection is specified, it MUST contain one and only one of the following structures:

Property
Label
HyperLink
BookmarkLink
DrillthroughId
DrillthroughUrl

delimiter (1 byte): A byte that specifies the end of the **Action** record. The value of the **delimiter** field MUST be 0xFF.

2.2.28 ActionImageMapAreas

The **ActionImageMapAreas** property specifies a structure that defines a set of actions associated with areas of a [Chart](#), [Image](#), [Map](#), or [GaugePanel](#) record. If the **ActionImageMapAreas** is specified, it MUST be part of one of the following records:

- [Chart.ElementProperties.NonSharedElementProperties](#)
- **Image.ElementProperties.NonSharedElementProperties**
- **Map.ElementProperties.NonSharedElementProperties**
- **GaugePanel.ElementProperties.NonSharedElementProperties**

ActionImageMapAreas = actionImageMapAreasStart count *ActionInfoWithMaps

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
actionImageMapAreasStart										count																							
...										actionInfoWithMaps (variable)																							
...																																	

actionImageMapAreasStart (1 byte): A byte that specifies the start of the **ActionImageMapAreas** record. The value of the **actionImageMapAreasStart** field MUST be 0x26.

count (4 bytes): A signed integer that specifies the number of [ActionInfoWithMaps](#) record elements in the array.

actionInfoWithMaps (variable): An array of **ActionInfoWithMaps** records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.29 ActionInfoWithMaps

The **ActionInfoWithMaps** record specifies an array of image areas for a [Chart](#), [Image](#), [Map](#), or [GaugePanel](#) record and the actions associated with these image areas.

ActionInfoWithMaps = actionInfoStart [ActionInfoContent] [ImageMapAreas] delimiter

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
actionInfoStart										actionInfoContent (variable)																							
...																																	
imageMapAreas (variable)																																	
...																																	
delimiter																																	

actionInfoStart (1 byte): A byte that specifies the start of the **ActionInfoWithMaps** record. The value of the **actionInfoStart** field MUST be 0x07.

actionInfoContent (variable): An [ActionInfoContent](#) record.

imageMapAreas (variable): An [ImageMapAreas](#) record.

delimiter (1 byte): A byte that specifies the end of the **ActionInfoWithMaps** record. The value of the **delimiter** field MUST be 0xFF.

2.2.30 DynamicImageData

The **DynamicImageData** property specifies a structure that defines the dynamically generated **images** for a [Chart](#), [Map](#), or [GaugePanel](#) record. If the **DynamicImageData** property is specified, it MUST be part of one of the following records:

- [Chart.ElementProperties.NonSharedElementProperties](#)
- **Map.ElementProperties.NonSharedElementProperties**
- **GaugePanel.ElementProperties.NonSharedElementProperties**

DynamicImageData = dynamicImageDataStart count dynamicImageContent

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
dynamicImageDataStart										count																							
...										dynamicImageContent (variable)																							
...																																	

dynamicImageDataStart (1 byte): A byte that specifies the start of the **DynamicImageData** record. The value of the **dynamicImageDataStart** field MUST be 0x27.

count (4 bytes): A signed integer that specifies the number of bytes that comprise the image content.

dynamicImageContent (variable): An array of bytes that comprise the a **Chart**, **Map**, or **GaugePanel**. The number of bytes in the array MUST be equal to the value of the **count** field.

2.2.31 ImageConsolidationOffsets

Applies to RPL 10.3.1

Applies to RPL 10.6 and later

The **ImageConsolidationOffsets** property specifies a structure that defines the range of pixels within a consolidated image that contains the actual target image ([Image](#), [Chart](#), [Map](#), or [GaugePanel](#) record). If the **ImageConsolidationOffsets** property is specified, it MUST be part of one of the following records:

- [Chart.ElementProperties.NonSharedElementProperties](#)

- **Map.ElementProperties.NonSharedElementProperties**
- **GaugePanel.ElementProperties.NonSharedElementProperties**
- **Image.ElementProperties.NonSharedElementProperties.ImageDataProperties.NonSharedImageDataProperties**

ImageConsolidationOffsets = imageConsolidationOffsetsStart (left, top, width, height)

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
imageConsolidationOffsetsStart										left																					
...										top																					
...										width																					
...										height																					
...																															

imageConsolidationOffsetsStart (1 byte): A byte that specifies the start of the **ImageConsolidationOffsets** record. The value of the **imageConsolidationOffsetStart** field MUST be 0x2F for RPL version 10.3.1 and the value of the **imageConsolidationOffsetStart** field MUST be 0x31 for RPL version 10.6 and later.

left (4 bytes): A field that specifies the left position, expressed in pixels, of the image relative to the consolidated image.

top (4 bytes): A field that specifies the top position, expressed in pixels, of the image relative to the consolidated image.

width (4 bytes): A field that specifies the width, expressed in pixels, of the image relative to the consolidated image.

height (4 bytes): A field that specifies the height, expressed in pixels, of the image relative to the consolidated image.

2.2.32 ReportItem

The **ReportItem** record specifies the structure types used to define the content of [BodyElement](#), [PageHeaderElement](#), and [PageFooterElement](#) records. Report items include [Line](#), [Image](#), [Chart](#), [Map](#), [GaugePanel](#), [Rectangle](#), [SubReport](#), [RichTextBox](#), and [Tablix](#). **Chart**, **Map**, **GaugePanel**, **SubReport**, or **Tablix** records MUST NOT be part of a **PageHeaderElement** or **PageFooterElement** record. <11>

ReportItem = Line / Image / Chart / GaugePanel / Map / Rectangle / SubReport / RichTextBox / Tablix

2.2.33 Line

The **Line** record specifies the properties applicable to a **Line** in a [Report](#).

Line = lineToken lineProperties ReportElementEnd

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
lineToken										lineProperties (variable)																							
...																																	
reportElementEnd																																	
...																																	
...																																	

lineToken (1 byte): A byte that specifies the start of the **Line** record. The value of the **lineToken** field MUST be 0x08.

lineProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Line** record. Each structure contained in this field MUST be one of the following.


Property
UniqueName
Slant
ID
Name
Tooltip
Bookmark
Label
ToggleItem
Style

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Line** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **lineToken** field of the **Line** record in the RPL stream.

2.2.34 Image

The **Image** record specifies the properties applicable to an **Image** within a [Report](#).

Image = imageStart imageProperties ReportElementEnd



imageStart (1 byte): A byte that specifies the start of the **Image** record. The value of the **imageStart** field MUST be 0x09.

imageProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Image** record. Each structure contained in the **imageProperties** field MUST be one of the following.

Property
UniqueName
ID
Name
Tooltip
Bookmark
Label
ToggleItem
Style
Sizing
ActionInfo

Property
ActionImageMapAreas
ImageDataProperties

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Image** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **imageToken** field of the **Image** record in the RPL stream.

2.2.35 ImageDataProperties

The **ImageDataProperties** record specifies a collection of properties applicable to the [Image](#) record and the [BackgroundImage](#) style property. The parent record for the **ImageDataProperties** record MUST be one of the following:

- [Image.ElementProperties.NonSharedElementProperties](#)
- [Style.SharedStyleProperties](#)
- [Style.NonSharedStyleProperties](#)

```
ImageDataProperties = imageStart (UseSharedImageDataProperties /
InlineSharedImageDataProperties / NonSharedImageDataProperties)
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
imageStart										imageDataProperties (variable)																										
...																																				


imageStart (1 byte): A byte that specifies the start of the **ImageDataProperties** record. The value of the **imageStart** field MUST be 0x2A.

imageDataProperties (variable): A [UseSharedImageDataProperties](#), [InlineSharedImageDataProperties](#), or [NonSharedImageDataProperties](#) record. When the parent record is **Style.SharedStyleProperties**, the **imageDataProperties** MUST be **UseSharedImageDataProperties** or **InlineSharedImageDataProperties**. The **imageDataProperties** MUST be **NonSharedImageDataProperties** when the parent record is **Style.NonSharedStyleProperties**.

2.2.36 UseSharedImage Data Properties

The **UseSharedImageDataProperties** record specifies the location of shared properties applicable to an [Image](#) record or [BackgroundImage](#) style property.

```
UseSharedImageDataProperties = useShared offset
```




useShared (1 byte): A byte that specifies the start of the **UseSharedImageDataProperties** record. The value of the **useShared** field MUST be 0x02.

offset (8 bytes): A signed integer that specifies the start of the [ImageDataProperties](#) record in the RPL stream; the **ImageDataProperties** record MUST have the [InlineSharedImageDataProperties](#) record.

2.2.37 InlineSharedImageDataProperties

The **InlineSharedImageDataProperties** record specifies the properties that can be shared by multiple [ImageDataProperties](#) records.

`InlineSharedImageDataProperties = shared [itemProperties] delimiter`



shared (1 byte): A byte that specifies the start of the **InlineSharedImageDataProperties** record. The value of the **shared** field MUST be 0x00.

itemProperties (variable): A collection of structures. The order of the elements in the collection is arbitrary. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
ImageMimeType
ImageName
ImageData
Width


Property
Height
HorizontalResolution
VerticalResolution
RawFormat

delimiter (1 byte): A byte that specifies the end of the **InlineSharedImageDataProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.38 NonSharedImageDataProperties

The **NonSharedImageDataProperties** record specifies the properties that are specific to a record. These properties are not shared by multiple [ImageDataProperties](#) records.

NonSharedImageDataProperties = nonShared [itemProperties] delimiter



nonShared (1 byte): A byte that specifies the start of the **NonSharedImageDataProperties** record. The value of the **nonShared** field MUST be 0x01.

itemProperties (variable): A collection of structures. The order of the elements in the collection is arbitrary. Each structure contained in the **itemProperties** field MUST be one of the following.

Property
ImageMimeType
ImageName
ImageData
Width
Height
HorizontalResolution
VerticalResolution

Property
RawFormat
ImageConsolidationOffsets

delimiter (1 byte): A byte that specifies the end of the **NonSharedImageDataProperties** record. The value of the **delimiter** field MUST be 0xFF.

2.2.39 ImageData

The **ImageData** property specifies a structure that defines the content for an image. If this property is specified, it MUST be part of one of the following records:

- [ImageDataProperties.InlineSharedImageDataProperties](#)
- [ImageDataProperties.NonSharedImageDataProperties](#)

ImageData = imageDataStart count imageDataContent

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31						
imageDataStart										count																											
...										imageDataContents (variable)																											
...																																					

imageDataStart (1 byte): A byte that specifies the start of the **ImageData** record. The value of the **imageDataStart** field MUST be 0x02.

count (4 bytes): A signed integer that specifies the number of bytes that comprise the image content.

imageDataContents (variable): An array of bytes that comprise the image. The number of bytes in the array MUST be equal to the value of the **count** field.

2.2.40 ImageMapAreas

The **ImageMapAreas** record specifies an array of **image map areas**.

ImageMapAreas = imageMapAreasStart count imageMapAreas

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
imageMapAreasStart										count																										

...	imageMapAreas (variable)
...	

imageMapAreasStart (1 byte): A byte that specifies the start of the **ImageMapAreas** record. The value of the **imageMapAreasStart** field MUST be 0x0A.

count (4 bytes): A signed integer that specifies the number of [ImageMapArea](#) record elements in the array.

imageMapAreas (variable): An array of **ImageMapArea** records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.41 ImageMapArea

The **ImageMapArea** record specifies an area in an **image map**.

ImageMapArea = shapeType count coordinates (ToolTip / delimiter)

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
shapeType										count																					
...										coordinates (variable)																					
...																															
toolTip (variable)																															
...																															
delimiter																															

shapeType (1 byte): A byte that specifies the shape of the area. The value of the **shapeType** field MUST be specified by the [ShapeType](#) enumeration.

count (4 bytes): A signed integer that specifies the number of coordinates record elements in the array.

coordinates (variable): An array of floating point values that specifies the coordinates of the shape, as a percentage of the image size. The number of elements in the array MUST be equal to the value of the **count** field. [<12>](#)

For a polygon shape, the **coordinates** array MUST have an even length and consist of X, Y coordinate pairs. Every even array element is a horizontal X coordinate and every odd array element is a vertical Y coordinate.

For a circle shape, there are exactly three elements in the **coordinates** array; these elements MUST occur in this order: the first two are the X and Y coordinates of the center of the circle, and the third element is the radius of the circle.

For a rectangle shape, there are four elements in the **coordinates** array; these elements MUST occur in this order: left, top, width, and height.

toolTip (variable): A [ToolTip](#) property that specifies the textual label for the image map area. This is an optional field that MUST be present only if the **delimiter** field is not specified.

delimiter (1 byte): A byte that specifies the end of an **ImageMapArea** record. The value of the **delimiter** field MUST be 0xFF. This is an optional field that MUST be present only if the **tooltip** field is not specified.

2.2.42 Chart

The **Chart** record specifies the properties applicable to a **chart** within a [Report](#).

Chart = chartToken chartProperties ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
chartToken										chartProperties (variable)																					
...																															
reportElementEnd																															
...																															
...																															

chartToken (1 byte): A byte that specifies the start of the **Chart** record. The value of the **chartToken** field MUST be 0x0B.

chartProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Chart** record. Each structure contained in this field MUST be one of the following.

Property
ActionImageMapAreas
DynamicImageData
StreamName
UniqueName

Property
Label
Bookmark
Tooltip
Style
ID
Name
ToggleItem
ImageConsolidationOffsets

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Chart** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **chartToken** field of the **Chart** record in the RPL stream.

2.2.43 GaugePanel

The **GaugePanel** record specifies the properties applicable to a **gauge panel** within a [Report](#).

GaugePanel = gaugePanelToken gaugePanelProperties ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
gaugePanelToken										gaugePanelProperties (variable)																										
...																																				
reportElementEnd																																				
...																																				
...																																				

gaugePanelToken (1 byte): A byte that specifies the start of the **GaugePanel** record. The value of the **gaugePanelToken** field MUST be 0x0E.

gaugePanelProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **GaugePanel** record. Each structure contained in this field MUST be one of the following.

Property
ActionImageMapAreas
DynamicImageData
StreamName
UniqueName
Label
Bookmark
Tooltip
Style
ID
Name
ToggleItem
ImageConsolidationOffsets


reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **GuagePanel** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of a **gaugePanelToken** field of the **GuagePanel** record in the RPL stream.

2.2.44 Map

Applies to RPL version 10.5 and later

The **Map** record specifies the properties applicable to a map within a [Report](#).

Map = mapToken mapProperties ReportElementEnd



mapToken (1 byte): A byte that specifies the start of the **Map** record. The value of the **mapToken** field MUST be 0x15.

mapProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Map** record. Each structure contained in this field MUST be one of the following.

Property
ActionImageMapAreas
DynamicImageData
StreamName
UniqueName
Label
Bookmark
Tooltip
Style
ID
Name
ToggleItem
ImageConsolidationOffsets

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Map** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **mapToken** field of the **ReportElementEnd** record in the RPL stream.

2.2.45 Rectangle

The **Rectangle** record specifies the properties applicable to a rectangle within a [Report](#) record.

Rectangle = rectangleToken rectangleProperties *ReportItem Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
rectangleToken										rectangleProperties (variable)																										
...																																				
reportItems (variable)																																				

...
measurements (variable)
...
reportElementEnd
...
...

rectangleToken (1 byte): A byte that specifies the start of the **Rectangle** record. The value of the **rectangleToken** field MUST be 0x0A.

rectangleProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Rectangle** record. Each structure contained in this field MUST be one of the following.

Property
LinkToChild
ID
Name
Tooltip
Bookmark
Label
ToggleItem
Style
UniqueName

reportItems (variable): An array of [ReportItem](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified in the **measurements** field.

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **reportItems** field array. The order of elements in the array MUST match the order of the **ReportItem** records in the **reportItems** field array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Rectangle** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **Rectangle** record in the RPL stream.

2.2.46 SubReport

The **SubReport** record specifies the properties applicable to a subreport within a [Report](#).

SubReport = subReportToken subReportProperties *ReportItem Measurements ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
subReportToken										subReportProperties (variable)																										
...																																				
reportItems (variable)																																				
...																																				
measurements (variable)																																				
...																																				
reportElementEnd																																				
...																																				
...																																				

subReportToken (1 byte): A byte that specifies the start of the **SubReport** record. The value of the **subReportToken** field MUST be 0x0C.

subReportProperties (variable): An [ElementProperties](#) record that specifies the properties applicable to **Report** records. Each structure contained in this field MUST be one of the following.

Property
Language
UniqueName
Label
Bookmark
Tooltip
Style

Property
ReportName
ID
Name
ToggleItem

reportItems (variable): An array of [ReportItem](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [Measurements](#) record specified in the **measurements** field.

measurements (variable): A **Measurements** record that specifies the size, location, and state properties for every element of the **reportItems** field array. The order of elements in the array MUST match the order of **ReportItem** records in the **reportItems** field array.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **SubReport** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of the **measurements** field of the **SubReport** record in the RPL stream.

2.2.47 RichTextBox

The **RichTextBox** record specifies the properties applicable to a **rich text box** within a [Report](#) record.

```
RichTextBox = richTextBoxToken richTextBoxProperties *ParagraphContent RichTextBoxStructure
ReportElementEnd
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
richTextBoxToken										richTextBoxProperties (variable)																							
...																																	
paragraphs (variable)																																	
...																																	
richTextBoxStructure (variable)																																	
...																																	
reportElementEnd																																	
...																																	

...

richTextBoxToken (1 byte): A byte that specifies the start of the **RichTextBox** record. The value of the **richTextBoxToken** field MUST be 0x07.

richTextBoxProperties (variable): A [ElementProperties](#) record that specifies the properties applicable to the **RichTextBox** record. If the [OriginalValue](#) property and the [TypeCode](#) property are both present, the **OriginalValue** property MUST appear in the array after the **TypeCode** property. The structure contained in the **richTextBoxProperties** field MUST be one of the following.

Property
ActionInfo
Value
ToggleState
SortState
IsToggleParent
ContentHeight
ContentOffset
ProcessedWithError
TypeCode
OriginalValue
CanGrow
CanShrink
CanSort
Formula
IsSimple
FormattedValueExpressionBased
UniqueName
Label
Bookmark
Tooltip
Style
ID
Name

Property
ToggleItem

paragraphs (variable): An array of [ParagraphContent](#) records. The number of elements in the array MUST be equal to the value of the **count** field of the [RichTextBoxStructure](#) record defined by the **richTextBoxStructure** field.

richTextBoxStructure (variable): A **RichTextBoxStructure** record.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **RichTextBox** record. The **offset** field for the **ReportElementEnd** record specifies the position of a **richTextBoxStructure** field in the RPL stream.

2.2.48 ParagraphContent

The **ParagraphContent** record specifies a paragraph of text and properties applicable to the entire paragraph. The text is specified through a contiguous collection of [TextRun](#) records.

```
ParagraphContent = *TextRun Paragraph
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
textRun (variable)																															
...																															
paragraph (variable)																															
...																															

textRun (variable): An array of **TextRun** records. The number of elements in the array MUST be equal to the value of the **count** field of a [Paragraph](#) record defined by the **paragraph** field.

paragraph (variable): A **Paragraph** record.

2.2.49 TextRun

The **TextRun** record specifies information about a span of text that is part of a [ParagraphContent](#) record.

```
TextRun = textRunStart textRunProperties delimiter
```


0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
textRunStart										textRunProperties (variable)																					
...																															
delimiter																															

textRunStart (1 byte): A byte that specifies the start of the **TextRun** record. The value of the **textRunStart** field MUST be 0x14.

textRunProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **TextRun** record. The structure contained in the **textRunProperties** field MUST be one of the following.

Property
UniqueName
ID
Style
Markup
Label
Tooltip
Value
ActionInfo
Formula
ProcessedWithError
ContentTop
ContentLeft
ContentWidth
ContentHeight

delimiter (1 byte): A byte that specifies the end of the **TextRun** record. The value of the **delimiter** field MUST be 0xFF.

2.2.50 Paragraph

The **Paragraph** record specifies a paragraph element of a [ParagraphContent](#) record.

Paragraph = paragraphStart paragraphProperties count offsetsTextRun delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
paragraphStart										paragraphProperties (variable)																										
...																																				
count																																				
offsetsTextRun (variable)																																				
...																																				
delimiter																																				

paragraphStart (1 byte): A byte that specifies the start of the **Paragraph** record. The value of the **paragraphStart** field MUST be 0x13.

paragraphProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Paragraph** record. The structure contained in the **paragraphProperties** field MUST be one of the following.

Property
UniqueName
ID
Style
ListStyle
ListLevel
LeftIndent
RightIndent
HangingIndent
SpaceBefore
SpaceAfter
ParagraphNumber
FirstLine
ContentTop

Property
ContentLeft
ContentWidth
ContentHeight

count (4 bytes): A signed integer that MUST be equal to the number of [TextRun](#) records present in the **textRuns** field array of the parent [ParagraphContent](#) record.

offsetsTextRun (variable): An array of 8-byte signed integers. The number of elements in the array MUST be equal to the value of the **count** field. Every element of the array specifies the position of a **TextRun** record in the RPL stream. The order of elements in the array MUST match the order of **TextRun** records in the **textRuns** field array of the parent **ParagraphContent** record.

delimiter (1 byte): A byte that specifies the end of the **Paragraph** record. The value of the **delimiter** field MUST be 0xFF.

2.2.51 RichTextBoxStructure

The **RichTextBoxStructure** record specifies the structure of a [RichTextBox](#) record.

```
RichTextBoxStructure = richTextBoxStructureStart offset count offsetsParagraphContent
delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
richTextBoxStructureStart										offset																										
...																																				
...										count																										
...										offsetsParagraphContent (variable)																										
...																																				
delimiter																																				

richTextBoxStructureStart (1 byte): A byte that specifies the start of the [RichTextBoxStructure](#) record. The value of the **richTextBoxStructureStart** field MUST be 0x12.

offset (8 bytes): A signed integer that specifies the position of the **richTextBoxToken** field of the parent record of type **RichTextBox** in the RPL stream.

count (4 bytes): A signed integer value that MUST be equal to the number of [ParagraphContent](#) records present in the parent [RichTextBox](#) record.

offsetsParagraphContent (variable): An array of 8-byte signed integers. The number of elements in the array MUST be equal to the value of the **count** field. Every element of the array specifies the position of a **Paragraph** as specified by the **paragraph** field of the **ParagraphContent** record in the RPL stream. The order of elements in the array MUST match the order of the **ParagraphContent** records in a **paragraphs** field array of the parent **RichTextBox** record.

delimiter (1 byte): A byte that specifies the end of the **RichTextBox** record. The value of the **delimiter** field MUST be 0xFF.

2.2.52 Tablix

The **Tablix** record specifies the properties, structures, and layout information applicable to a **tablix** within a [Report](#). The **Tablix** is a flexible grid layout that consists of cells that are organized in rows. A tablix layout is comprised of four areas: corner, **column headers**, **row headers**, and body.

Tablix = tablixToken tablixProperties [TablixContent] TablixStructure ReportElementEnd

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
tablixToken										tablixProperties (variable)																					
...																															
tablixContent (variable)																															
...																															
tablixStructure (variable)																															
...																															
reportElementEnd																															
...																															
...																															

tablixToken (1 byte): A byte that specifies the start of the **Tablix** record. The value of the **tablixToken** field MUST be 0x0D.

tablixProperties (variable): A record of type [ElementProperties](#) that specifies the properties applicable to the **Tablix** record. Each structure contained in the **tablixProperties** field MUST be one of the following.

Property
UniqueName
ID
Name
Tooltip
Bookmark
Label
ToggleItem
Style

tablixContent (variable): A [TablixContent](#) record that specifies the content of grid cells and layout information for the cells of a **tablix body area**.

tablixStructure (variable): A [TablixStructure](#) record.

reportElementEnd (10 bytes): A [ReportElementEnd](#) record that marks the end of the **Tablix** record. The **offset** field of the **ReportElementEnd** record MUST specify the position of a **tablixStructure** field of the **Tablix** record in the RPL stream.

2.2.53 TablixContent

The **TablixContent** record specifies the content of a [Tablix](#) record. The child records MUST be of type [ReportItem](#) or [TablixBodyRow](#).

```
TablixContent = *(ReportItem / TablixBodyRow)
```

2.2.54 TablixStructure

The **TablixStructure** record specifies information about the layout of a [Tablix](#) record and the position of the **Tablix** record in the RPL stream.

```
TablixStructure = tablixStructureStart offset TablixMeasurements delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
tablixStructureStart										offset																							
...																																	

...	tablixMeasurements (variable)
...	
delimiter	

tablixStructureStart (1 byte): A byte that specifies the start of the **TablixStructure** record. The value of the **tablixStructureStart** field MUST be 0x11.

offset (8 bytes): A signed integer that specifies the position of the **tablixStart** field of the parent record of type **Tablix** in the RPL stream.

tablixMeasurements (variable): A record of type [TablixMeasurements](#).

delimiter (1 byte): A byte that specifies the end of the **TablixStructure** record. The value of the **delimiter** field MUST be 0xFF.

2.2.55 TablixMeasurements

The **TablixMeasurements** record specifies the layout information of a [Tablix](#) record.

```
TablixMeasurements = tablixMeasurementsProperties *TablixRow
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
tablixMeasurementsProperties (variable)																															
...																															
tablixRows (variable)																															
...																															

tablixMeasurementsProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.

Property
ColumnHeaderRows
RowHeaderColumns
ColsBeforeRowHeader
LayoutDirection

Property
ColumnsWidths
RowHeights
ContentTop
ContentLeft
TablixRowMembersDef
TablixColMembersDef

tablixRows (variable): An array of [TablixRow](#) records.

2.2.56 ColumnsWidths

The **ColumnsWidths** record specifies the number of columns a [Tablix](#) record contains and the properties associated to each of these columns. The columns MUST be ordered according to the [LayoutDirection](#) and [ColsBeforeRowHeader](#) properties.

ColumnsWidths = columnsWidthsStart count *ColumnsInfo

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
columnsWidthsStart										count																							
...										columns (variable)																							
...																																	

columnsWidthsStart (1 byte): A byte that specifies the start of the **ColumnsWidths** record. The value of the **columnsWidthsStart** field MUST be 0x04.

count (4 bytes): A signed integer that specifies the number of columns contained in the corresponding **Tablix** record. The value of this field MUST be greater than or equal to the value of the [RowHeaderColumns](#) property of the **Tablix**.

columns (variable): An array of [ColumnInfo](#) records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.57 ColumnInfo

The **ColumnInfo** record specifies the properties applicable to a column of a [Tablix](#) record.

ColumnInfo = width fixed

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
width																															
fixed																															

width (4 bytes): A floating point value that specifies the width of the column in millimeters. The value of the **width** field MUST be greater than or equal to zero. <13>

fixed (1 byte): A **Boolean** value that indicates if the column should be displayed on the page when the user scrolls part of the tablix off the page. The value of the **fixed** field MUST be one of the following.

Value	Meaning
0x00	False, column is not displayed.
0x01	True, column is displayed.

2.2.58 RowHeights

The **RowHeights** record specifies the number of rows a [Tablix](#) record contains and the properties associated to each of these rows.

```
RowHeights = rowHeightsStart count *RowInfo
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rowHeightsStart										count																					
...										rows (variable)																					
...																															

rowHeightsStart (1 byte): A byte that specifies the start of the **RowHeights** record. The value of the **rowHeightsStart** field MUST be 0x05.

count (4 bytes): A signed integer that specifies the number of rows contained in the corresponding **Tablix** record. The value of this field MUST be greater than or equal to the value of the [ColumnHeaderRows](#) property of the **Tablix**.

rows (variable): An array of [RowInfo](#) records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.59 RowInfo

The **RowInfo** record specifies the properties applicable to a row of a [Tablix](#) record.

RowInfo = height byte

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
height																															
A - FixedRows	B - SharedLayoutRow	C - UseSharedLayoutRow	reserved																												

height (4 bytes): A floating point value that specifies the height of the row in millimeters. This MUST be a value greater than or equal to zero. [<14>](#)

A - FixedRows (1 bit): A bit field that specifies whether the row should be displayed on the page when the user scrolls part of the tablix off the page.

The value of the **FixedRows** bit field MUST be one of the following.

Value	Meaning
0x0	False
0x1	True

B - SharedLayoutRow (1 bit): A bit field that specifies whether the tablix row has a layout that can be shared by other rows that follow this one. The rows that share the same layout MUST be consecutive entries in the **tablixRows** field array of [TablixMeasurements](#) record. The **UseSharedLayoutRow** and **SharedLayoutRow** fields MUST NOT be set at the same time. [<15>](#) The value of this bit field MUST be one of the following.

Value	Meaning
0x0	False
0x1	True

C - UseSharedLayoutRow (1 bit): A bit that specifies whether the tablix row uses the same layout as a previous row in the **tablixRows** field array of **TablixMeasurements** record. The **UseSharedLayoutRow** and **SharedLayoutRow** MUST NOT be set at the same time. [<16>](#) The value of the **UseSharedLayoutRow** bit field MUST be one of the following.

Value	Meaning
0x0	False
0x1	True

reserved (5 bits): The value of the **reserved** field MUST be zero and MUST be ignored.

2.2.60 TablixRow

The **TablixRow** record specifies a row of a [Tablix](#) record.

```
TablixRow = tablixRowStart *TablixRowCell delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
tablixRowStart										tablixRowCells (variable)																										
...																																				
delimiter																																				

tablixRowStart (1 byte): A byte that specifies the start of the **TablixRow** record. The value of the **tablixRowStart** byte field MUST be 0x08.

tablixRowCells (variable): An array of [TablixRowCell](#) records. The elements MUST be ordered according to the [LayoutDirection](#) property of the **Tablix**. A [TablixCorner](#) or a [TablixColumnHeader](#) structure MUST NOT be part of a row that contains a [TablixRowHeader](#) or [TablixBodyRowCells](#) structure.

delimiter (1 byte): A byte that specifies the end of the **TablixRow** record. The value of the **delimiter** field MUST be 0xFF.

2.2.61 TablixRowCell

The **TablixRowCell** record specifies the content of a cell in a [Tablix](#) record.

```
TablixRowCell = TablixCorner / TablixColumnHeader / TablixRowHeader / TablixBodyRowCells
```

2.2.62 TablixCorner

The **TablixCorner** record specifies a cell of the corner area of a [Tablix](#) record.

```
TablixCorner = tablixCornerStart [tablixCellProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
tablixCornerStart										tablixCellProperties (variable)																										
...																																				

delimiter

tablixCornerStart (1 byte): A byte that specifies the start of the **TablixCorner** record. The value of the **tablixCornerStart** field MUST be 0x0A.

tablixCellProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.

Property
CellItemOffset
ColSpan
RowSpan
ColumnIndex
RowIndex
CellItemState
ContentTop
ContentLeft
ContentWidth
ContentHeight

delimiter (1 byte): A byte that specifies the end of the **TablixCorner** record. The value of the **delimiter** field MUST be 0xFF.

2.2.63 TablixColumnHeader

The **TablixColumnHeader** record specifies a cell of the column headers area of a [Tablix](#) record.

TablixColumnHeader = tablixColumnHeaderStart [tablixCellProperties] delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
tablixColumnHeaderStart										tablixCellProperties (variable)																					
...																															
delimiter																															

tablixColumnHeaderStart (1 byte): A byte that specifies the start of the **TablixColumnHeader** record. The value of the **tablixColumnHeaderStart** field MUST be 0x0B.

tablixCellProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.


Property
CellItemOffset
ColSpan
RowSpan
DefIndex
ColumnIndex
RowIndex
GroupLabel
UniqueName
State
CellItemState
RecursiveToggleLevel
ContentTop
ContentLeft
ContentWidth
ContentHeight

delimiter (1 byte): A byte that specifies the end of the **TablixColumnHeader** record. The value of the **delimiter** field MUST be 0xFF.

2.2.64 TablixRowHeader

The **TablixRowHeader** record specifies a cell of the row headers area of a [Tablix](#) record.

```
TablixRowHeader = tablixRowHeaderStart [tablixCellProperties] delimiter
```



tablixRowHeaderStart (1 byte): A byte that specifies the start of the **TablixRowHeader** record. The value of the **tablixRowHeaderStart** field MUST be 0x0C.

tablixCellProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.


Property
CellItemOffset
ColSpan
RowSpan
DefIndex
ColumnIndex
RowIndex
GroupLabel
UniqueName
State
CellItemState
RecursiveToggleLevel
ContentTop
ContentLeft
ContentWidth
ContentHeight

delimiter (1 byte): A byte that specifies the end of the **TablixRowHeader** record. The value of the **delimiter** field MUST be 0xFF.

2.2.65 TablixBodyRowCells

The **TablixBodyRowCells** record specifies the position in the RPL stream of the [TablixBodyRow](#) record that is part of the parent [TablixRow](#) record.

TablixBodyRowCells = tablixBodyRowCellsStart offset



...

tablixBodyRowCellsStart (1 byte): A byte that specifies the start of the **TablixBodyRowCells** record. The value of the **tablixBodyRowCellsStart** field MUST be 0x09.

offset (8 bytes): A signed integer that specifies the position of the **TablixBodyRow** record in the RPL stream.

2.2.66 TablixBodyRow

The **TablixBodyRow** record specifies the content of a row in the body area of a [Tablix](#) record.

```
TablixBodyRow = tablixBodyRowStart rowIndex *TablixBodyCell delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
tablixBodyRowStart										rowIndex																							
...										tablixBodyCells (variable)																							
...																																	
delimiter																																	

tablixBodyRowStart (1 byte): A byte that specifies the start of the **TablixBodyRow** record. The value of the **tablixBodyRowStart** field MUST be 0x12.

rowIndex (4 bytes): A signed integer that specifies the index of the row. The value of this field identifies the corresponding [RowInfo](#) structure in a **rows** field array of a [TablixMeasurements.RowHeights](#) record.

tablixBodyCells (variable): An array of [TablixBodyCell](#) records. The elements in the array MUST be ordered according to the **TablixLayout** property of a tablix.

delimiter (1 byte): A byte that specifies the end of the **TablixBodyRow** record. The value of the **delimiter** field MUST be 0xFF.

2.2.67 TablixBodyCell

The **TablixBodyCell** record specifies a cell of a body area of a [Tablix](#) record.

```
TablixBodyCell = tablixBodyCellStart [tablixCellProperties] delimiter
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
tablixBodyCellStart										tablixCellProperties (variable)																							
...																																	
delimiter																																	

tablixBodyCellStart (1 byte): A byte that specifies the start of the **TablixBodyCell** record. The value of the **tablixBodyCellStart** field MUST be 0x0D.

tablixCellProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.

Property
CellItemOffset
ColSpan
RowSpan
ColumnIndex
CellItemState
ContentTop
ContentLeft
ContentWidth
ContentHeight

delimiter (1 byte): A byte that specifies the end of the **TablixBodyCell** record. The value of the **delimiter** byte field MUST be 0xFF.

2.2.68 TablixRowMembersDef

The **TablixRowMembersDef** record specifies a list of [TablixMemberDef](#) records that are referenced by [TablixRowHeader](#) records.

`TablixRowMembersDef = tablixRowMembersDefStart count *TablixMemberDef`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1						
tablixRowMembersDefStart										count																											

...	tablixMembersDefContents (variable)
...	

tablixRowMembersDefStart (1 byte): A byte that specifies the start of the **TablixRowMemberDef** record. The value of the **tablixRowMembersDefStart** field MUST be 0x0E.

count (4 bytes): A signed integer that specifies the number of **TablixMemberDef** records associated with elements of the row headers area of the [Tablix](#) record.

tablixMembersDefContents (variable): An array of **TablixMemberDef** records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.69 TablixColMembersDef

The **TablixColMembersDef** record specifies a list of [TablixMemberDef](#) records that are referenced by [TablixColumnHeader](#) records.

`TablixColMembersDef = tablixColMembersDefStart count *TablixMemberDef`

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
tablixColMembersDefStart										count																					
...										tablixMembersDefContents (variable)																					
...																															

tablixColMembersDefStart (1 byte): A byte that specifies the start of the **TablixColMembersDef** record. The value of the **tablixColMembersDefStart** field MUST be 0x0F.

count (4 bytes): A signed integer that specifies the number of **TablixMemberDef** records associated with elements of associated with elements of the column headers area of the [Tablix](#) record.

tablixMembersDefContents (variable): An array of **TablixMemberDef** records. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.70 TablixMemberDef

The **TablixMemberDef** record specifies the definition of the **column members** and **row members** of a [Tablix](#) record.

`TablixMemberDef = tablixMemberDefStart [tablixMemberDefProperties] delimiter`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
tablixMemberDefStart										tablixMemberDefProperties (variable)																							
...																																	
delimiter																																	

tablixMemberDefStart (1 byte): A byte that specifies the start of the **TablixMemberDef** record. The value of the **tablixMemberDefStart** field MUST be 0x10.

tablixMemberDefProperties (variable): A collection of structures. The order of the structures in the collection is arbitrary. The structures in the collection MUST be one of the following.

Property
DefinitionPath
Level
MemberCellIndex
MemberDefState

delimiter (1 byte): A byte that specifies the end of **TablixMemberDef** record. The value of the **delimiter** field MUST be 0xFF.

2.2.71 Measurements

The **Measurements** record specifies the properties of an element in the parent record.

Measurements = measurementsStart offset count measurementsContent

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
measurementsStart										offset																							
...																																	
...										count																							
...										measurementsContent (variable)																							
...																																	

measurementsStart (1 byte): A byte that specifies the start of the **Measurements** record. The value of the **measurementsStart** field MUST be 0x10.

offset (8 bytes): A signed integer that MUST specify the position of the parent record in the RPL stream. The parent record MUST be one of the following.

Parent record
PageContent
SimpleSection
MixedSection
BodyAreaElement
PageHeaderElement
PageFooterElement
BodyElement
Rectangle
SubReport

count (4 bytes): A signed integer that specifies the number of elements the parent record contains.

measurementsContent (variable): An array of [Measurement](#) structures. The number of elements in the array MUST be equal to the value of the **count** field.

2.2.72 Measurement

The **Measurement** record specifies the properties of an element in the grandparent record.

Measurement = left top width height zIndex state reportElementEndOffset

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31																		
left										top										width										height										zIndex									

state	reportElementEndOffset
...	
...	

left (4 bytes): A field that specifies the left position, expressed in millimeters, of the element relative to its parent record.

top (4 bytes): A field that specifies the top position, expressed in millimeters, of the element relative to its parent record.

width (4 bytes): A field that specifies the width, expressed in millimeters, of the element.

height (4 bytes): A field that specifies the height, expressed in millimeters, of the element.

zIndex (4 bytes): A field that specifies the **zIndex** property. The **zIndex** is the drawing order of the items within the panel.

state (1 byte): A field of type byte that specifies information for the element. The meaning of this field value is derived from the [StateValues](#) enumeration.

reportElementEndOffset (8 bytes): A signed integer that specifies the position of the [ReportElementEnd](#) record in the RPL stream for an element in the grandparent record. The **offset** MUST point to a corresponding item (identified by the same index in the collection) in the grandparent record.

Record	Corresponding element type
PageContent	Section
SimpleSection	BodyAreaElement PageHeaderElement PageFooterElement
MixedSection	BodyAreaElement PageHeaderElement PageFooterElement
BodyAreaElement	BodyElement
PageHeaderElement	ReportItems
PageFooterElement	ReportItems
BodyElement	ReportItems
Rectangle	ReportItems
SubReport	ReportItems

2.2.73 ReportElementEnd

The **ReportElementEnd** record specifies the end of a variable size record.

ReportElementEnd = elementEnd offset delimiter

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
elementEnd										offset																					
...																															
...										delimiter																					

elementEnd (1 byte): A byte that specifies the start of the **ReportElementEnd** record. The value of this byte field **MUST** be 0xFE.

offset (8 bytes): A signed integer that points to the start of a record in the RPL stream. The record identified by the **offset** field depends on the record type that the **ReportElementEnd** record ends. The variable size records **MUST** be one of the following.

Record type	Offset points to BodyAreaElement
Report	offsetsArrayElement
PageContent	measurements
SimpleSection	measurements
MixedSection	measurements
BodyAreaElement	measurements
PageHeaderElement	measurements
PageFooterElement	measurements
BodyElement	measurements
Line	lineToken
Image	imageToken
Chart	chartToken
GaugePanel	gaugePanelToken
Map	mapToken
Rectangle	measurements
SubReport	measurements

Record type	Offset points toBodyAreaElement
RichTextBox	richTextBoxStructureStart
Tablix	tablixStructureStart

delimiter (1 byte): A byte that specifies the end of **ReportElementEnd** record. The value of the **delimiter** field MUST be 0xFF.


2.3 Properties

This section specifies the properties that can be used in an RPL stream.

2.3.1 ID

The **ID** property specifies a value that uniquely identifies the parent record of this property. If this property is specified, it MUST be part of a [SectionProperties](#), [PageProperties](#), or [ElementProperties.InlineSharedElementProperties](#) record.

ID = idStart idValue



idStart (1 byte): A byte that specifies the start of the **ID** property. The value of the **idStart** field MUST be one of the following values.

Value	Parent
0x00	SectionProperties
0x01	PageProperties ElementProperties.InlineSharedElementProperties for ReportItem ElementProperties.InlineSharedElementProperties for PageHeaderElement ElementProperties.InlineSharedElementProperties for PageFooterElement ElementProperties.InlineSharedElementProperties for BodyElement
0x05	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.InlineSharedElementProperties for TextRun

idValue (variable): A **String** variable that specifies the unique identifier of a structure specified in the table above.

2.3.2 ColumnCount

The **ColumnCount** property specifies the number of columns in a [Section](#) record. If this property is specified, it MUST be part of a [SectionProperties](#) record. If the **ColumnCount** property is not present, the default value is used.

ColumnCount = columnCountStart columnCountValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
columnCountStart										columnCountValue																					
...																															

columnCountStart (1 byte): A byte that specifies the start of the **ColumnCount** property. The value of the **columnCountStart** field MUST be the following value.

Value	Parent
0x01	SectionProperties

columnCountValue (4 bytes): An **integer** that specifies the number of columns in a section. The default value is 0x00000000.

2.3.3 ColumnSpacing

The **ColumnSpacing** property specifies the spacing between each column within a single section in multicolumn renderings. If this property is specified, it MUST be part of a [SectionProperties](#) or [PageProperties](#) record. If the **ColumnSpacing** property is not specified, the default value is used.

ColumnSpacing = columnSpacingStart columnSpacingValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
columnSpacingStart										columnSpacingValue																					
...																															

columnSpacingStart (1 byte): A byte that specifies the start of the **ColumnSpacing** property. The value of **columnSpacingStart** field MUST be one of the following values.


Value	Parent
0x02	SectionProperties
0x16	PageProperties

columnSpacingValue (4 bytes): A floating point value that specifies the spacing between each column in a section. The default value is 0x00000000.

2.3.4 UniqueName

The **UniqueName** property specifies a value that uniquely identifies a record. If this property is specified, it MUST be part of an [ElementProperties.NonSharedElementProperties](#), [TablixRowHeader](#), or [TablixColumnHeader](#) record.

UniqueName = uniqueNameStart uniqueNameValue



uniqueNameStart (1 byte): A byte that specifies the start of the **UniqueName** property. The value of the **uniqueNameStart** field MUST be one of the following values.


Value	Parent
0x00	ElementProperties.NonSharedElementProperties for ReportItem ElementProperties.NonSharedElementProperties for PageHeaderElement ElementProperties.NonSharedElementProperties for PageFooterElement ElementProperties.NonSharedElementProperties for BodyElement PageProperties
0x04	ElementProperties.NonSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for TextRun
0x0B	TablixColumnHeader TablixRowHeader

uniqueValue (variable): A **String** variable that specifies the unique identifier of a structure specified in the preceding table.

2.3.5 Name

The **Name** property specifies the name of a [ReportItem](#) record. If the **Name** property is specified, it MUST be part of a [ReportItem.ElementProperties.InlineSharedElementProperties](#) record.

Name = nameStart nameValue



nameStart (1 byte): A byte that specifies the start of the **Name** property. The value of the **nameStart** field MUST be the following value.


Value	Parent
0x02	ElementProperties.InlineSharedElementProperties for ReportItem

nameValue (variable): A **String** variable that specifies the name of a **ReportItem**.

2.3.6 Label

The **Label** property specifies a label for a [ReportItem](#), [TextRun](#), or [Action](#) record. If the **Label** property is specified, it MUST be part of a [ReportItem.ElementProperties](#), **TextRun.ElementProperties**, or **Action** record.

Label = labelStart labelValue



labelStart (1 byte): A byte that specifies the start of the **Label** property. The value of the **labelStart** field MUST be one of the following values.

Value	Parent
0x03	ElementProperties.InlineSharedElementProperties for ReportItem ElementProperties.NonSharedElementProperties for ReportItem
0x04	Action
0x08	ElementProperties.InlineSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for TextRun

labelValue (variable): A **String** variable that specifies a user-friendly label for the record.

2.3.7 Bookmark

The **Bookmark** property specifies a **bookmark** that can be linked to via a bookmark action in a report. If this property is specified, it **MUST** be part of a [ReportItem.ElementProperties](#) record.

Bookmark = bookmarkStart bookmarkValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
bookmarkStart										bookmarkValue (variable)																							
...																																	

bookmarkStart (1 byte): A byte that specifies the start of the **Bookmark** property. The value of the **bookmarkStart** field **MUST** be one of the following values.

Value	Parent
0x04	ElementProperties.InlineSharedElementProperties for ReportItem ElementProperties.NonSharedElementProperties for ReportItem

bookmarkValue (variable): A **String** variable that specifies a bookmark that can be linked to via a bookmark action.

2.3.8 ToolTip

The **ToolTip** property specifies a textual label that provides a description for a record. If the **ToolTip** property is specified, it **MUST** be part of a [ReportItem.ElementProperties](#), **TextRun.ElementProperties**, or [ImageMapArea](#) record.

ToolTip = toolTipStart toolTipValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
toolTipStart										toolTipValue (variable)																							
...																																	

toolTipStart (1 byte): A byte that specifies the start of the **ToolTip** property. The value of the **toolTipStart** field **MUST** be one of the following values.

Value	Parent
0x05	ElementProperties.InlineSharedElementProperties for ReportItem ElementProperties.NonSharedElementProperties for ReportItem ImageMapArea
0x09	ElementProperties.InlineSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for TextRun

toolTipValue (variable): A **String** variable that specifies a textual label for a report item or **text run**.

2.3.9 ToggleItem

The **ToggleItem** property specifies a text box that users click to show or hide the current item. The **ToggleItem** property MUST be part of a [ReportItem.ElementProperties.InlineSharedElementProperties](#) record.

If the **ToggleItem** property is not specified, the current item does not toggle. **ToggleItem** MUST NOT be used in [PageHeaderElement](#) or [PageFooterElement](#) records, nor can it refer to items within them.<17>

```
ToggleItem = toggleItemStart toggleItemValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
toggleItemStart										toggleItemValue (variable)																							
...																																	

toggleItemStart (1 byte): A byte that specifies the start of the **ToggleItem** property. The value of **toggleItemStart** field MUST be the following value.

Value	Parent
0x08	ElementProperties.InlineSharedElementProperties for ReportItem

toggleItemValue (variable): A **String** variable that specifies the corresponding text box with the matching [Name](#) property that a user clicks to set the visibility of the current item.

2.3.10 Description

The **Description** property specifies the description of a [Report](#) record. If this property is specified, it MUST be part of a [ReportProperties](#) record.

```
Description = descriptionStart descriptionValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
descriptionStart										descriptionValue																							
...																																	

descriptionStart (1 byte): A byte that specifies the start of the **Description** property. The value of the **descriptionStart** field MUST be the following value.

Value	Parent
0x09	ReportProperties

descriptionValue (variable): A variable **String** that specifies the description of the report.

2.3.11 Location

The **Location** property specifies the location of a [Report](#) record as an **absolute URL**. If the **Location** property is specified, it MUST be part of a [ReportProperties](#) record.

Location = locationStart locationValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
locationStart										locationValue (variable)																							
...																																	

locationStart (1 byte): A byte that specifies the start of the **Location** property. The value of the **locationStart** field MUST be the following value.

Value	Parent
0x0A	ReportProperties

locationValue (variable): A variable **String** that specifies the location of the report.

2.3.12 ConsumeContainerWhiteSpace (RPL 10.6)

Applies to RPL 10.6 and later

The **ConsumeContainerWhiteSpace** property specifies the growth behavior for items within containers that have trailing white space after the last item in the container. The **ConsumeContainerWhiteSpace** property controls whether the trailing white space is preserved as

the items grow or whether the trailing white space is consumed by the growth of the items. If the **ConsumeContainerWhiteSpace** is specified, it MUST be part of a [ReportProperties](#) record. If the **ConsumeContainerWhiteSpace** property is not specified, the default value is used.

ConsumeContainerWhiteSpace = consumeContainerWhiteSpaceStart consumeContainerWhiteSpaceValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
consumeContainerWhiteSpaceStart										consumeContainerWhiteSpaceValue																					

consumeContainerWhiteSpaceStart (1 byte): A byte that specifies the start of the **ConsumeContainerWhiteSpace** property. The value of the **ConsumeContainerWhiteSpaceStart** field MUST be the following value.

Value	Parent
0x32	ReportProperties

consumeContainerWhiteSpaceValue (1 byte): A byte that specifies the trailing white space item growth behavior of the **ReportProperties** record. The default value is 0x00. The value of the **consumeContainerWhiteSpaceValue** field MUST be one of the following values.

Value	Meaning
0x00	False. The space is preserved.
0x01	True. The space is consumed.

:

2.3.13 Language

The **Language** property specifies the primary **language** of the text in a record. If this property is specified, it MUST be part of a [ReportProperties](#), [SubReport.ElementProperties.NonSharedElementProperties](#), or [Style](#) record. If the **Language** property of the [SubReport](#) record is not specified, the **Language** property MUST default to the **Language** property of a [Report](#) record that contains the current item. If the **Language** property of the **Style** record is not specified, the **Language** property MUST default to the **Language** property of the **Report** or **SubReport** record that contains the current item.

Language = languageStart languageValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
languageStart										languageValue (variable)																					

...

languageStart (1 byte): A byte that specifies the start of the **Language** property. The value of the **languageStart** field MUST be one of the following values.


Value	Parent
0x0B	ReportProperties
0x0B	ElementProperties.NonSharedElementProperties for SubReport
0x20	Style.SharedStyleProperties
0x20	Style.NonSharedStyleProperties

languageValue (variable): A **String** variable that MUST be a valid language code, which is a combination of an ISO 639 two-letter lowercase culture code associated with a language, and an ISO 3166 (see [\[ISO-3166\]](#)) two-letter uppercase subculture code associated with a country or region.

2.3.14 ExecutionTime

The **ExecutionTime** property specifies the date and time that a report was generated for transmission. If this property is specified, it MUST be part of a [ReportProperties](#) record.

ExecutionTime = executionTimeStart executionTimeValue



executionTimeStart (1 byte): A byte that specifies the start of the **ExecutionTime** property. The value of **executionTimeStart** field MUST be the following value.

Value	Parent
0x0C	ReportProperties

executionTimeValue (8 bytes): A signed integer that specifies the date and time as the number of 100 non-second intervals since 12:00 AM January 1, year 1 A.D. in the proleptic Gregorian Calendar, and indicates the date and time that the [Report](#) record was executed.

2.3.15 Author

The **Author** property specifies the name of the author of a report. If this property is specified, it MUST be part of a [ReportProperties](#) record.

Author = authorStart authorValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
authorStart										authorValue (variable)																							
...																																	

authorStart (1 byte): A byte that specifies the start of the **Author** property. The value of the **authorStart** field MUST be the following value.

Value	Parent
0x0D	ReportProperties

authorValue (variable): A variable **String** containing the name of the author of the [Report](#) record.

2.3.16 AutoRefresh

The **AutoRefresh** property specifies, in seconds, how often to refresh a report. If this property is specified, it MUST be part of [ReportProperties](#) record. If the **AutoRefresh** property is not specified, the default value is used.

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
autoRefreshStart										autoRefreshValue																							
...																																	

autoRefreshStart (1 byte): A byte that specifies the start of the **AutoRefresh** property. The value of **autoRefreshStart** field MUST be the following value.

Value	Parent
0x0E	ReportProperties

autoRefreshValue (4 bytes): A signed integer that specifies the number of seconds to wait before the [Report](#) record refreshes. The default value is 0x00000000.

2.3.17 ReportName

The **ReportName** property specifies the name of a report. If this property is specified, it MUST be part of a [ReportProperties](#) or [SubReport.ElementProperties.InlineSharedElementProperties](#) record.

ReportName = reportNameStart reportNameValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
reportNameStart										reportNameValue (variable)																							
...																																	

reportNameStart (1 byte): A byte that specifies the start of the **ReportName** property. The value of the **reportNameStart** field MUST be one of the following values.

Value	Parent
0x0F	ReportProperties ElementProperties.InlineSharedElementProperties for SubReport

reportNameValue (variable): A variable **String** containing the name of a [Report](#) record.

2.3.18 PageHeight

The **PageHeight** property specifies the default height for rendering a report in a **physical-page oriented renderer**. If this property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **PageHeight** property is not specified, the default value is used.

PageHeight = pageHeightStart pageHeightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
pageHeightStart										pageHeightValue																							
...																																	

pageHeightStart (1 byte): A byte that specifies the start of the **PageHeight** property. The value of the **pageHeightStart** field MUST be one of the following values.

Value	Parent
0x10	PageLayout PageProperties

pageHeightValue (4 bytes): A floating point value that specifies the default height, in millimeters, for rendering the [Report](#) record in a physical-page oriented renderer. The default value is 0x00000000 millimeters.

2.3.19 PageWidth

The **PageWidth** property specifies the default width for rendering a report in a physical-page oriented renderer. If the **PageWidth** property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **PageWidth** property is not specified, the default value is used.

`PageWidth = pageWidthStart pageWidthValue`

0									1									2									3				
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
pageWidthStart									pageWidthValue																						
...																															

pageWidthStart (1 byte): A byte that specifies the start of the **PageWidth** property. The value of the **pageWidthStart** field MUST be one of the following values.

Value	Parent
0x11	PageLayout

pageWidthValue (4 bytes): A floating point value that specifies the default width, in millimeters, for rendering a [Report](#) record in a physical-page oriented renderer. The default value is 0x00000000 millimeters.

2.3.20 MarginTop

The **MarginTop** property specifies the size of the top margin of a page. If this property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **MarginTop** property is not specified, the default value is used.

`MarginTop = marginTopStart marginTopValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
marginTopStart										marginTopValue																					
...																															

marginTopStart (1 byte): A byte that specifies the start of the **MarginTop** property. The value of the **marginTopStart** field MUST be one of the following values.

Value	Parent
0x12	PageLayout PageProperties

marginTopValue (4 bytes): A floating point value that specifies the size, in millimeters, of the top margin of the page. The default value is 0x00000000 millimeters.

2.3.21 MarginLeft

The **MarginLeft** property specifies the size of the left margin of a page. If this property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **MarginLeft** property is not specified, the default value is used.

MarginLeft = marginLeftStart marginLeftValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
marginLeftStart										marginLeftValue																					
...																															

marginLeftStart (1 byte): A byte that specifies the start of the **MarginLeft** property. The value of the **marginLeftStart** field MUST be one of the following values.

Value	Parent
0x13	PageLayout PageProperties

marginLeftValue (4 bytes): A floating point value that specifies the size, in millimeters, of the left margin of the page. The default value is 0x00000000 millimeters.

2.3.22 MarginRight

The **MarginRight** property specifies the size of the right margin of a page. If this property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **MarginRight** property is not specified, the default value is used.

MarginRight = marginRightStart marginRightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
marginRightStart										marginRightValue																					
...																															

marginRightStart (1 byte): A byte that specifies the start of the **MarginRight** property. The value of **marginRightStart** field MUST be one of the following values.

Value	Parent
0x15	PageLayout PageProperties

marginRightValue (4 bytes): A floating point value that specifies the size, in millimeters, of the right margin of the page. The default value is 0x00000000 millimeters.

2.3.23 MarginBottom

The **MarginBottom** property specifies the size of the bottom margin of a page. If this property is specified, it MUST be part of a [PageLayout](#) or [PageProperties](#) record. If the **MarginBottom** property is not specified, the default value is used.

MarginBottom = marginBottomStart marginBottomValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
marginBottomStart										marginBottomValue																					
...																															

marginBottomStart (1 byte): A byte that specifies the start of the **MarginBottom** property. The value of the **marginBottomStart** field MUST be one of the following values.

Value	Parent
0x14	PageLayout PageProperties

marginBottomValue (4 bytes): A floating point value that specifies the size, in millimeters, of the bottom margin of the page. The default value is 0x00000000 millimeters.

2.3.24 Columns

The **Columns** property specifies the number of columns a page contains. If this property is specified, it MUST be part of a [PageProperties](#) record. If the **Columns** property is not specified, the default value is used.

Columns = columnsStart columnsValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
columnsStart										columnsValue																					
...																															

columnsStart (1 byte): A byte that specifies the start of the **Columns** property. The value of the **columnStart** field MUST be the following value.

Value	Parent
0x17	PageProperties

columnsValue (4 bytes): A signed integer that specifies the number of columns a page contains. The default value is 0x00000000.

2.3.25 PageName (RPL 10.6)

Applies to RPL version 10.6 and later

The **PageName** property specifies the name of a page. If this property is specified, it MUST be part of a **PageLayout** record.

PageName = pageNameStart pageNameValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
pageNameStart										pageNameValue (variable)																					

...

pageNameStart (1 byte): A byte that specifies the start of the **PageName** property. The value of the **pageNameStart** field MUST be the following value.

Value	Parent
0x30	PageLayout

pageNameValue (variable): A String variable that specifies the name of a page.

2.3.26 Slant

The **Slant** property specifies the direction in which a [Line](#) record is drawn. If the **Slant** property is specified, it MUST be part of a **Line.ElementProperties.InlineSharedElementProperties** record. If the **Slant** property is not specified, the default value is used.

Slant = slantStart slantValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
slantStart										slantValue																					

slantStart (1 byte): A byte that specifies the start of the **Slant** property. The value of the **slantStart** field MUST be the following value.

Value	Parent
0x18	ElementProperties.InlineSharedElementProperties for Line

slantValue (1 byte): A byte that specifies how the line should be drawn. The default value of this field is 0x00. The value of the **slantValue** field MUST be one of the following values.

Value	Meaning
0x00	Draw from (left, bottom) to (right, top)
0x01	Draw from (left, top) to (right, bottom)

2.3.27 CanGrow

The **CanGrow** property specifies if the height of a [RichTextBox](#) record can increase to accommodate its contents. If the **CanGrow** property is specified, it MUST be part of a [RichTextBox.ElementProperties.InlineSharedElementProperties](#) record. If the **CanGrow** property is not specified, the default value is used.

CanGrow = canGrowStart canGrowValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
canGrowStart										canGrowValue																					

canGrowStart (1 byte): A byte that specifies the start of the **CanGrow** property. The value of the **canGrowStart** field **MUST** be the following value.

Value	Parent
0x19	ElementProperties.InlineSharedElementProperties for RichTextBox

canGrowValue (1 byte): A byte that specifies if the **RichTextBox** record height can increase. The default value of this field is 0x00. The value of the **canGrowValue** field **MUST** be one of the following values.

Value	Meaning
0x00	False. The height cannot grow.
0x01	True. The height can grow.

2.3.28 CanShrink

The **CanShrink** property specifies if the height of a [RichTextBox](#) record can decrease to accommodate its contents. If the **CanShrink** property is specified, it **MUST** be part of a [RichTextBox.ElementProperties.InlineSharedElementProperties](#) record. If the **CanShrink** property is not specified, the default value is used.

CanShrink = canShrinkStart canShrinkValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
canShrinkStart										canShrinkValue																					

canShrinkStart (1 byte): A byte that specifies the start of the **CanShrink** property. The value of the **canShrinkStart** field **MUST** be the following value.

Value	Parent
0x1A	ElementProperties.InlineSharedElementProperties for RichTextBox


canShrinkValue (1 byte): A byte that specifies if the **RichTextBox** record height can decrease. The default value of the **canShrinkValue** field is 0x00. The value of the **canShrinkValue** field MUST be one of the following values.

Value	Meaning
0x00	False. The height cannot shrink.
0x01	True. The height can shrink.

2.3.29 Value

The **Value** property specifies the value of a [RichTextBox](#) or [TextRun](#) record that is returned as a formatted **String**. If this property is specified, it MUST be part of a [RichTextBox.ElementProperties](#) or **TextRun.ElementProperties** record.

Value = valueStart valueValue



valueStart (1 byte): A byte that specifies the start of the **Value** property. The value of the **valueStart** field MUST be one of the following values. [<18>](#)

Value	Parent
0x1B	ElementProperties.InlineSharedElementProperties for RichTextBox ElementProperties.NonSharedElementProperties for RichTextBox
0x0A	ElementProperties.InlineSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for TextRun

valueValue (variable): A **String** variable that specifies the formatted value of the **RichTextBox** or **TextRun**.

2.3.30 ToggleState

The **ToggleState** property specifies the current state of the toggle of a [RichTextBox](#) record. If the **ToggleState** is specified, it MUST be part of a [RichTextBox.ElementProperties.NonSharedElementProperties](#) record. If the **ToggleState** property is not specified, the default value is used.

ToggleState = toggleStateStart toggleStateValue

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	3	0	1
toggleStateStart										toggleStateValue																								

toggleStateStart (1 byte): A byte that specifies the start of the **ToggleState** property. The value of the **toggleStateStart** field MUST be the following value.

Value	Parent
0x1C	ElementProperties.NonSharedElementProperties for RichTextBox

toggleStateValue (1 byte): A byte that specifies the **toggle state** of the **RichTextBox** record. The default value is 0x00. The value of the **toggleStateValue** field MUST be one of the following values.

Value	Meaning
0x00	False. Toggle state off.
0x01	True. Toggle state on.

2.3.31 CanSort

The **CanSort** property specifies if a [RichTextBox](#) record supports sorting. If the **CanSort** property is specified, it MUST be part of a [RichTextBox.ElementProperties.InlineSharedElementProperties](#) record. If the **CanSort** property is not specified, the default value is used.

`CanSort = canSortStart canSortValue`

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	3	0	1
canSortStart										canSortValue																								

canSortStart (1 byte): A byte that specifies the start of **CanSort** property. The value of the **canSortStart** field MUST be the following value.

Value	Parent
0x1D	ElementProperties.InlineSharedElementProperties for RichTextBox


canSortValue (1 byte): A byte that specifies if the **RichTextBox** supports sorting. The default value is 0x00. The value of the **canSortValue** field MUST be one of the following values.

Value	Meaning
0x00	False. Cannot sort.
0x01	True. Can sort.

2.3.32 SortState

The **SortState** property specifies the **sort state** of a **RichTextBox** record. If the **SortState** property is specified, it MUST be part of a **RichTextBox.ElementProperties.NonSharedElementProperties** record. If the **SortState** property is not specified, the default value is used.

```
SortState = sortStateStart sortStateValue
```



sortStateStart (1 byte): A byte that specifies the start of **SortState** property. The value of **sortStateStart** field MUST be the following value.


Value	Parent
0x1E	ElementProperties.NonSharedElementProperties for RichTextBox

sortStateValue (1 byte): A byte that specifies sort state of the **RichTextBox**. The default value of the **sortStateValue** field is 0x00. The list of acceptable values MUST be defined by the **SortOptions** enumeration.

2.3.33 Formula

The **Formula** property returns the formula used to generate a value for a **RichTextBox** or **TextRun** record. If the **Formula** property is specified, it MUST be part of a **RichTextBox.ElementProperties.InlineSharedElementProperties** or **TextRun.ElementProperties.InlineSharedElementProperties** record.

```
Formula = formulaStart formulaValue
```



formulaStart (1 byte): A byte that specifies the start of the **Formula** property. The value of **formulaStart** field MUST be one of the following values.

Value	Parent
0x1F	ElementProperties.InlineSharedElementProperties for RichTextBox
0X0C	ElementProperties.InlineSharedElementProperties for TextRun

formulaValue (variable): A **String** value containing the formula that is used to generate the value for the **RichTextBox** or **TextRun**.

2.3.34 IsToggleParent

The **IsToggleParent** property specifies if a [RichTextBox](#) report item is used to toggle other items on a report. If this property is specified, it MUST be part of the [RichTextBox.ElementProperties](#) record. If the **IsToggleParent** property is not specified, the default value is used.

```
IsToggleParent = isToggleParentStart isToggleParentValue
```

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31
isToggleParentStart										isToggleParentValue																					

isToggleParentStart (1 byte): A byte that specifies the start of the **IsToggleParent** property. [19](#) The value of the **isToggleParentStart** field MUST be one of the following values.

Value	Parent
0x20	ElementProperties.InlineSharedElementProperties for RichTextBox ElementProperties.NonSharedElementProperties for RichTextBox

isToggleParentValue (1 byte): A byte that specifies if the **RichTextBox** is used as a toggle to control the visibility of another item on the report. The default value is 0x00. The value MUST be one of the following values.

Value	Meaning
0x00	False. The Textbox does not control the visibility of another item.
0x01	True. The Textbox controls the visibility of another item.

2.3.35 TypeCode

The **TypeCode** property specifies the type of value for a [RichTextBox](#). If this property is specified, it MUST be part of the [RichTextBox.ElementProperties](#) record. If the **TypeCode** property is not specified, the default value is used.

TypeCode = typeCodeStart typeCodeValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
typeCodeStart										typeCodeValue																					

typeCodeStart (1 byte): A byte that specifies the start of the **TypeCode** property. [<20>](#) The value of the **typeCodeStart** field MUST be one of the following values.

Value	Parent
0x21	ElementProperties.InlineSharedElementProperties for RichTextBox . ElementProperties.NonSharedElementProperties for RichTextBox .

typeCodeValue (1 byte): A byte that specifies the type of value for the **RichTextBox**. The default value is 0x11. The list of valid values MUST be obtained from the [TypeCode](#) enumeration. If a value that is not included in the enumeration is used, the value of the **TypeCode** enumeration is a **String**.

2.3.36 OriginalValue

The **OriginalValue** property specifies the unformatted value of a [RichTextBox](#) record. If the **OriginalValue** property is specified, it MUST be part of the [RichTextBox.ElementProperties.NonSharedElementProperties](#) record.

OriginalValue = originalValueStart originalValueValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
originalValueStart										originalValueValue (variable)																							
...																																	

originalValueStart (1 byte): A byte that specifies the start of the **OriginalValue** property. The value of **originalValueStart** field MUST be the following value.

Value	Parent
0x22	ElementProperties.NonSharedElementProperties for RichTextBox

originalValueValue (variable): A variable size field that specifies the unformatted value of the **RichTextBox**. The size and type of the **originalValueValue** field is dictated by the [TypeCode](#) property.

2.3.37 IsSimple

The **IsSimple** property specifies if a [RichTextBox](#) record has one or multiple [Paragraph](#) and [TextRun](#) records. <21> If the **IsSimple** property is specified, it MUST be part of the [RichTextBox.ElementProperties.InlineSharedElementProperties](#) record. If the **IsSimple** property is not specified, the default value is used.

IsSimple = isSimpleStart isSimpleValue

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	3	0	1
isSimpleStart									isSimpleValue																									

isSimpleStart (1 byte): A byte that specifies the start of **IsSimple** property. The value of **isSimpleStart** field MUST be the following value.

Value	Parent
0x23	ElementProperties.InlineSharedElementProperties for RichTextBox

isSimpleValue (1 byte): A byte that specifies whether the text box is simple. The default value is 0x01. The value MUST be one of the following values.

Value	Meaning
0x00	False. Multiple Paragraph records or one Paragraph with multiple TextRun records.
0x01	True. One Paragraph with only one TextRun record.

2.3.38 ContentOffset

The **ContentOffset** property specifies the offset for the first paragraph in a [RichTextBox](#) record. The offset is relative to the top-left corner of the **RichTextBox** when the paragraphs are rendered top to bottom. The offset is relative to the top-right corner of the **RichTextBox** when paragraphs are rendered right to left.

If the **ContentOffset** property is specified, it MUST be part of the [RichTextBox.ElementProperties.NonSharedElementProperties](#) record. If the **ContentOffset** property is not specified, the default value is used.

ContentOffset = contentOffsetStart contentOffsetValue

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	3	0	1
contentOffsetStart										contentOffsetValue																								
...																																		

contentOffsetStart (1 byte): A byte that specifies the start of the **ContentOffset** property. The value of **contentOffsetStart** field MUST be the following value.

Value	Parent
0x25	ElementProperties.NonSharedElementProperties for RichTextBox

contentOffsetValue (4 bytes): A floating point value that specifies the offset for the first paragraph. The default value is 0x00000000.

2.3.39 StreamName

The **StreamName** property specifies the name of a stream for a [Chart](#), [Map](#), or [GaugePanel](#) record. If this property is specified, it MUST be part of a [Chart.ElementProperties.NonSharedElementProperties](#) or **Map.ElementProperties.NonSharedElementProperties** or **GaugePanel.ElementProperties.NonSharedElementProperties** record.

StreamName = streamNameStart streamNameValue

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	3	0	1
streamNameStart										streamNameValue (variable)																								
...																																		

streamNameStart (1 byte): A byte that specifies the start of the **StreamName** property. The value of **streamNameStart** field MUST be one of the following values.

Value	Parent
0x28	ElementProperties.NonSharedElementProperties for Chart . ElementProperties.NonSharedElementProperties for Map . ElementProperties.NonSharedElementProperties for GaugePanel .

streamNameValue (variable): A **String** variable that specifies the **stream name** of the **Chart**, **Map**, and **GaugePanel** report items. <22>

2.3.40 Sizing

The **Sizing** property specifies the behavior of an image if the actual image does not fit within the specified size of an [Image](#) record. If this property is specified, it MUST be part of the [Image.ElementProperties.InlineSharedElementProperties](#) record. If this property is not specified, the default value is used.

Sizing = sizingStart sizingValue

										1									2										3		
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
sizingStart										sizingValue																					

sizingStart (1 byte): A byte that specifies the start of the **Sizing** property. The value of **sizingStart** field MUST be the following value.

Value	Parent
0x29	ElementProperties.InlineSharedElementProperties for Image

sizingValue (1 byte): A byte that specifies the behavior if the actual image does not fit in the specified size. The list of valid values MUST be obtained from the [Sizings](#) enumeration. The default value is 0x00.

2.3.41 LinkToChild

The **LinkToChild** property specifies the **ID** of a report item contained directly within a rectangle. If the **LinkToChild** property is specified, it MUST be part of the [Rectangle.ElementProperties.InlineSharedElementProperties](#) record.

LinkToChild = linkToChildStart linkToChildValue

										1									2										3				
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
linkToChildStart										linkToChildValue (variable)																							
...																																	

linkToChildStart (1 byte): A byte that specifies the start of the **LinkToChild** property. The value of **linkToChildStart** field MUST be the following value.

Value	Parent
0x2B	ElementProperties.InlineSharedElementProperties of Rectangle

linkToChildValue (variable): A **String** variable that specifies the **ID** of a child report item contained directly within a **Rectangle** that is the target location for the **document map** label (if any).

2.3.42 PrintOnFirstPage

The **PrintOnFirstPage** property specifies if the content of a header or footer should be printed on the first page of a report. If this property is specified, it MUST be part of the [PageHeader.ElementProperties.InlineSharedElementProperties](#) or **PageFooter.ElementProperties.InlineSharedElementProperties** record. If the **PrintOnFirstPage** property is not specified, the default value is used.

```
PrintOnFirstPage = printOnFirstPageStart printOnFirstPageValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
printOnFirstPageStart										printOnFirstPageValue																					

printOnFirstPageStart (1 byte): A byte that specifies the start of **PrintOnFirstPage** property. The value of the **printOnFirstPageStart** field MUST be one of the following values.

Value	Parent
0x2C	ElementProperties.InlineSharedElementProperties for PageHeaderElement ElementProperties.InlineSharedElementProperties for PageFooterElement

printOnFirstPageValue (1 byte): A byte that specifies whether the content should be printed on the first page of the [Report](#) record. The default value is 0x00. The value of the **printOnFirstPageValue** field MUST be one of the following values.

Value	Meaning
0x00	False. Do not print on first page.
0x01	True. Print on first page.

2.3.43 PrintBetweenSections (RPL 10.4)

Applies to RPL 10.4 and later

The **PrintBetweenSections** property specifies if the content of a header or footer should be printed between sections of a report. If the **PrintBetweenSections** property is specified, it MUST be part of a [PageHeaderElement.ElementProperties.InlineSharedElementProperties](#) or

PageFooterElement.ElementProperties.InlineSharedElementProperties record. If the **PrintBetweenSections** property is not specified, the default value is used.

PrintBetweenSections = printBetweenSectionsStart printBetweenSectionsValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
printBetweenSectionsStart										printBetweenSectionsValue																					

printBetweenSectionsStart (1 byte): A byte that specifies the start of the **PrintBetweenSections** property. The value of the **printBetweenSectionsStart** field MUST be one of the following values.

Value	Parent
0x2F	ElementProperties.InlineSharedElementProperties for PageHeaderElement ElementProperties.InlineSharedElementProperties for PageFooterElement

printBetweenSectionsValue (1 byte): A byte that specifies whether the content should be printed between sections of the [Report](#) record. The default value is 0x00. The value of the **printBetweenSectionsValue** field MUST be one of the following values.

Value	Meaning
0x00	False. Do not print between sections.
0x01	True. Print between sections.

2.3.44 FormattedValueExpressionBased

The **FormattedValueExpressionBased** property specifies that the [Value](#) property of a [RichTextBox](#) record was generated from expression-based properties (that is, either the value or one of the formatting style properties was an expression). The formatting style properties are: [Format](#), [Language](#), [Calendar](#), [NumeralLanguage](#), and [NumeralVariant](#).

If the **FormattedValueExpressionBased** property is specified, it MUST be part of the [RichTextBox.ElementProperties.InlineSharedElementProperties](#) record. If the **FormattedValueExpressionBased** property is not specified, the default value is used.

FormattedValueExpressionBased = formattedValueExpressionBasedStart
formattedValueExpressionBasedValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
formattedValueExpressionBasedStart										formattedValueExpressionBasedValue																					

formattedValueExpressionBasedStart (1 byte): A byte that specifies the start of the **FormattedValueExpressionBased** property. The value of the **formattedValueExpressionBasedStart** field MUST be the following value.

Value	Parent
0x2D	ElementProperties.InlineSharedElementProperties for RichTextBox .

formattedValueExpressionBasedValue (1 byte): A byte that specifies that the **Value** property of the **RichTextBox** record was generated from expression-based properties. The default value is 0x00. The value of the **formattedValueExpressionBasedValue** field MUST be one of the following values.

Value	Meaning
0x00	False.
0x01	True.

2.3.45 ProcessedWithError

The **ProcessedWithError** property specifies if an error was encountered during generation of the **Value** property for a text box or text run. If the **ProcessedWithError** property is specified, it MUST be part of a [RichTextBox.ElementProperties.NonSharedElementProperties](#) or **TextRun.ElementProperties.NonSharedElementProperties** record. If the **ProcessedWithError** property is not specified, the default value is used.

`ProcessedWithError = processedWithErrorStart processedWithErrorValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
processedWithErrorStart										processedWithErrorValue																					

processedWithErrorStart (1 byte): A byte that specifies the start of **ProcessedWithError** property. The value of the **processedWithErrorStart** field MUST be one of the following values.

Value	Parent
0x2E	ElementProperties.NonSharedElementProperties for RichTextBox .

Value	Parent
0x0D	ElementProperties.NonSharedElementProperties for TextRun .

processedWithErrorValue (1 byte): A byte that specifies if an error was encountered during generation of the **Value** property. The default value is 0x00. The value of the **processedWithErrorValue** field MUST be one of the following values.

Value	Meaning
0x00	False. Value property was processed without error.
0x01	True. Value property was processed with error and its valueValue field should be String "#Error".

2.3.46 ImageMIMETYPE

The **ImageMIMETYPE** property specifies the **MIME type** for an image. If the **ImageMIMETYPE** property is specified, it MUST be part of [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

ImageMIMETYPE = imageMIMETYPEStart imageMIMETYPEValue



imageMIMETYPEStart (1 byte): A byte that specifies the start of the **ImageMIMETYPE** property. [<23>](#) The value of the **imageMIMETYPEStart** field MUST be one of the following values.

Value	Parent
0x00	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

imageMIMETYPEValue (variable): A variable **String** that specifies the content type of an image object. The valid values are: image/bmp, image/jpeg, image/gif, image/png, image/x-png. [<24>](#)

2.3.47 ImageName

The **ImageName** property specifies the name of an image. If this property is specified, it MUST be part of the [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

ImageName = imageNameStart imageNameValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
imageNameStart										imageNameValue (variable)																					
...																															

imageNameStart (1 byte): A byte that specifies the start of **ImageName** property. <25> The value of the **imageNameStart** field MUST be one of the following values.

Value	Parent
0x01	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

imageNameValue (variable): A variable **String** that specifies the name of an image.

2.3.48 Width

The **Width** property specifies the width of an image in pixels. If this property is specified, it MUST be part of the [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

Width = widthStart widthValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
widthStart										widthValue																					
...																															

widthStart (1 byte): A byte that specifies the start of **Width** property. <26> The value of the **widthStart** field MUST be one of the following values.

Value	Parent
0x03	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

widthValue (4 bytes): A signed integer that specifies the width of an image in pixels. If this property is present, the [Height](#), [HorizontalResolution](#), [VerticalResolution](#), and [RawFormat](#) properties MUST be present in the same parent record. <27>

2.3.49 Height

The **Height** property specifies the height of an image in pixels. If this property is specified, it MUST be part of an [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

Height = heightStart heightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
heightStart										heightValue																					
...																															

heightStart (1 byte): A byte that specifies the start of the **Height** property. [<28>](#) The value of the **heightStart** field MUST be one of the following values.

Value	Parent
0x04	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

heightValue (4 bytes): A signed integer that specifies the height of an image in pixels. If this property is present, the [Width](#), [HorizontalResolution](#), [VerticalResolution](#), and [RawFormat](#) properties MUST be present in the same parent record. [<29>](#)

2.3.50 HorizontalResolution

The **HorizontalResolution** property specifies the **horizontal resolution**, in pixels per inch, of an image. If this property is specified, it MUST be part of the [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

HorizontalResolution = horizontalResolutionStart horizontalResolutionValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
horizontalResolutionStart										horizontalResolutionValue																					
...																															

horizontalResolutionStart (1 byte): A byte that specifies the start of the **HorizontalResolution** property. <30> The value of the **horizontalResolutionStart** field MUST be one of the following values.

Value	Parent
0x05	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

horizontalResolutionValue (4 bytes): A floating point value that specifies the horizontal resolution of an image. If this property is present, the [Width](#), [Height](#), [VerticalResolution](#), and [RawFormat](#) properties MUST be present in the same parent record. <31>

2.3.51 VerticalResolution

The **VerticalResolution** property specifies the **vertical resolution**, in pixels per inch, of an image. If this property is specified, it MUST be part of an [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

VerticalResolution = verticalResolutionStart verticalResolutionValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
verticalResolutionStart										verticalResolutionValue																					
...																															

verticalResolutionStart (1 byte): A byte that specifies the start of the **VerticalResolution** property. <32> The value of the **verticalResolutionStart** field MUST be one of the following values.

Value	Parent
0x06	ImageDataProperties.InlineSharedImageDataProperties

verticalResolutionValue (4 bytes): A floating point value that specifies the vertical resolution of an image. If this property is present, the [Width](#), [Height](#), [HorizontalResolution](#), and [RawFormat](#) properties MUST be present in the same parent record. <33>

2.3.52 RawFormat

The **RawFormat** property specifies the stream format of an image. If this property is specified, it MUST be part of the [ImageDataProperties.InlineSharedImageDataProperties](#) or [ImageDataProperties.NonSharedImageDataProperties](#) record.

RawFormat = rawFormatStart rawFormatValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rawFormatStart										rawFormatValue																					

rawFormatStart (1 byte): A byte that specifies the start of **RawFormat** property. <34> The value of the **rawFormatStart** field MUST be one of the following values.

Value	Parent
0x07	ImageDataProperties.InlineSharedImageDataProperties ImageDataProperties.NonSharedImageDataProperties

rawFormatValue (1 byte): A byte that specifies the stream format of the image. If this property is present, the [Width](#), [Height](#), [HorizontalResolution](#), and [VerticalResolution](#) properties MUST be present in the same parent record. <35> The value of the **rawFormatValue** field MUST be a value from the [ImageRawFormat](#) enumeration.

2.3.53 Hyperlink

The **Hyperlink** property specifies the URL of a hyperlink. If this property is specified, it MUST be part of an [Action](#) record.

Hyperlink = hyperlinkStart hyperlinkValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
hyperlinkStart										hyperlinkValue (variable)																							
...																																	

hyperlinkStart (1 byte): A byte that specifies the start of the **Hyperlink** property. The value of the **hyperlinkStart** field MUST be the following value.

Value	Parent
0x06	Action

hyperlinkValue (variable): A **String** variable that specifies the URL of a hyperlink.

2.3.54 BookmarkLink

The **BookmarkLink** property specifies the [ID](#) property of a bookmark located within a report that is the target of this action. If the **BookmarkLink** property is specified, it MUST be part of an [Action](#) record.

2.3.56 DrillthroughUrl

The **DrillthroughUrl** property specifies the URL of the drillthrough report to be executed and viewed as the target of an action specified by the [Action](#) record. If the **DrillthroughUrl** property is specified, it MUST be part of an **Action** record.

DrillthroughUrl = drillthroughUrlStart drillthroughUrlValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
drillthroughUrlStart										drillthroughUrlValue (variable)																					
...																															

drillthroughUrlStart (1 byte): A byte that specifies the start of **DrillthroughUrl** property. The value of **drillthroughStart** field MUST be the following value.

Value	Parent
0x09	Action

drillthroughUrlValue (variable): A **String** variable that specifies the URL of the drillthrough report to be executed and viewed as the target of this action.

2.3.57 BorderColor

The **BorderColor** property specifies the color of a border. If this property is specified, it MUST be part of the [Style](#) record. The value of the **BorderColor** property is overridden by the value of the [BorderColorLeft](#), [BorderColorRight](#), [BorderColorTop](#), or [BorderColorBottom](#) property for individual edges. If the **BorderColor** property is not specified, the default value is used.

BorderColor = borderColorStart borderColorValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
borderColorStart										borderColorValue (variable)																					
...																															

borderColorStart (1 byte): A byte that specifies the start of the **BorderColor** property. The value of the **borderColorStart** field MUST be one of the following values.


Value	Parent
0x00	SharedStyleProperties NonSharedStyleProperties

borderColorValue (variable): A **String** variable that specifies the border color. A color value can be a color name (user-defined system colors are not supported), a Red Green Blue (RGB) color **String** of the form #HHHHHH, or an Alpha Red Green Blue (ARGB) color **String** of the form #HHHHHHHH. The default value is "Black".

2.3.58 BorderColorLeft

The **BorderColorLeft** property specifies the color of the left border. If this property is specified, it **MUST** be part of a [Style](#) record. The value of the **BorderColorLeft** property overrides the [BorderColor](#) property for the left border. If the **BorderColorLeft** property is not defined, the value of **BorderColor** is used.

```
BorderColorLeft = borderColorLeftStart borderColorLeftValue
```



borderColorLeftStart (1 byte): A byte that specifies the start of the **BorderColorLeft** property. The value of the **borderColorLeftStart** field **MUST** be one of the following values.

Value	Parent
0x01	SharedStyleProperties NonSharedStyleProperties

borderColorLeftValue (variable): A **String** variable that specifies the left border color. A color value can be a color name (user-defined system colors are not supported), an RGB color **String** of the form #HHHHHH, or an ARGB color **String** of the form #HHHHHHHH.

2.3.59 BorderColorRight

The **BorderColorRight** property specifies the color of the right border. If this property is specified, it **MUST** be part of a [Style](#) record. The value of the **BorderColorRight** property overrides the [BorderColor](#) property for the right border. If the **BorderColorRight** property is not defined, the value of **BorderColor** is used.

```
BorderColorRight = borderColorRightStart borderColorRightValue
```


0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderColorRightStart										borderColorRightValue (variable)																							
...																																	

borderColorRightStart (1 byte): A byte that specifies the start of the **BorderColorRight** property. The value of **borderColorRightStart** field MUST be one of the following values.

Value	Parent
0x02	SharedStyleProperties NonSharedStyleProperties

borderColorRightValue (variable): A **String** variable that specifies the color of the right border. A color value can be a color name (user defined system colors are not supported), an RGB color **String** of the form #HHHHHH, or an ARGB color **String** of the form #HHHHHHHH.

2.3.60 BorderColorTop

The **BorderColorTop** property specifies the color of the top border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderColorTop** property overrides the [BorderColor](#) property for the top border. If the **BorderColorTop** property is not defined, the value of **BorderColor** is used.

```
BorderColorTop = borderColorTopStart borderColorTopValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderColorTopStart										borderColorTopValue (variable)																							
...																																	

borderColorTopStart (1 byte): A byte that specifies the start of the **BorderColorTop** property. The value of the **borderColorTopStart** field MUST be one of the following values.

Value	Parent
0x03	SharedStyleProperties NonSharedStyleProperties

borderColorTopValue (variable): A **String** variable that specifies the color of the top border. A color value can be a color name (user-defined system colors are not supported), an RGB color **String** of the form #HHHHHH, or an ARGB color **String** of the form #HHHHHHHH.

2.3.61 BorderColorBottom

The **BorderColorBottom** property specifies the color of the bottom border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderColorBottom** property overrides the [BorderColor](#) property for the bottom border. If the **BorderColorBottom** property is not defined, the value of **BorderColor** is used.

`BorderColorBottom = borderColorBottomStart borderColorBottomValue`

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31					
borderColorBottomStart										borderColorBottomValue (variable)																										
...																																				

borderColorBottomStart (1 byte): A byte that specifies the start of the **BorderColorBottom** property. The value of the **borderColorBottomStart** field MUST be one of the following values.

Value	Parent
0x04	SharedStyleProperties NonSharedStyleProperties

borderColorBottomValue (variable): A **String** variable that specifies the color of the bottom border. A color value can be a color name (user-defined system colors are not supported), an RGB color **String** of the form #HHHHHH, or an ARGB color **String** of the form #HHHHHHHH.

2.3.62 BorderStyle

The **BorderStyle** property specifies the style of a border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderStyle** property is overridden by the value of the [BorderStyleLeft](#), [BorderStyleRight](#), [BorderStyleTop](#), or [BorderStyleBottom](#) property for individual edges. If the **BorderStyle** property is not specified, the default value is used.

`BorderStyle = borderStyleStart borderStyleValue`

0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31		
borderStyleStart										borderStyleValue																							

borderStyleStart (1 byte): A byte that specifies the start of the **BorderStyle** property. The value of the **borderStyleStart** field MUST be one of the following values.

Value	Parent
0x05	SharedStyleProperties NonSharedStyleProperties

borderStyleValue (1 byte): A byte that specifies the border style. The value of the **borderStyleValue** field is of type [BorderStyles](#) and it MUST be contained in the **BorderStyles** enumeration. <36> The default value is 0x00.

2.3.63 BorderStyleLeft

The **BorderStyleLeft** property specifies the style of the left border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderStyleLeft** property overrides the [BorderStyle](#) property for the left border. If the **BorderStyleLeft** property is not defined then the value of **BorderStyle** is used.

```
BorderStyleLeft = borderStyleLeftStart borderStyleLeftValue
```

										1										2																						3	
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1												
borderStyleLeftStart										borderStyleLeftValue																																	

borderStyleLeftStart (1 byte): A byte that specifies the start of the **BorderStyleLeft** property. The value of **borderStyleLeftStart** field MUST be one of the following values.

Value	Parent
0x06	SharedStyleProperties NonSharedStyleProperties

borderStyleLeftValue (1 byte): A byte that specifies the style of the left border. The value of this field is of type [BorderStyles](#) and it MUST be contained in the **BorderStyles** enumeration. <37>

2.3.64 BorderStyleRight

The **BorderStyleRight** property specifies the style of the right border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderStyleRight** property overrides the [BorderStyle](#) property for the right border. If the **BorderStyleRight** property is not defined, the value of **BorderStyle** is used.

```
BorderStyleRight = borderStyleRightStart borderStyleRightValue
```

										1										2																	3	
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1							
borderStyleRightStart										borderStyleRightValue																												

borderStyleRightStart (1 byte): A byte that specifies the start of the **BorderStyleRight** property. The value of the **borderStyleRightStart** field MUST be one of the following values.

Value	Parent
0x07	SharedStyleProperties NonSharedStyleProperties

borderStyleRightValue (1 byte): A byte that specifies the style of the right border. The value of this field is of type [BorderStyle](#) and it MUST be contained in the **BorderStyles** enumeration. <38>

2.3.65 BorderStyleTop

The **BorderStyleTop** property specifies the style of the top border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderStyleTop** property overrides the [BorderStyle](#) property for the top border. If the **BorderStyleTop** property is not defined, the value of **BorderStyle** is used.

`BorderStyleTop = borderStyleTopStart borderStyleTopValue`

										1											2														3	
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1					
borderStyleTopStart										borderStyleTopValue																										

borderStyleTopStart (1 byte): A byte that specifies the start of the **BorderStyleTop** property. The value of **borderStyleTopStart** field MUST be one of the following values.

Value	Parent
0x08	SharedStyleProperties NonSharedStyleProperties

borderStyleTopValue (1 byte): A byte that specifies the style of the top border. The value of the **borderStyleTopValue** field is of type [BorderStyle](#) and it MUST be contained in the **BorderStyles** enumeration. <39>

2.3.66 BorderStyleBottom

The **BorderStyleBottom** property specifies the style of the bottom border. If this property is specified, it MUST be part of a [Style](#) record. The value of this property overrides the [BorderStyle](#)

property for the bottom border. If the **BorderStyleBottom** property is not defined, the value of **BorderStyle** is used.

BorderStyleBottom = borderStyleBottomStart borderStyleBottomValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
borderStyleBottomStart										borderStyleBottomValue																					

borderStyleBottomStart (1 byte): A byte that specifies the start of the **BorderStyleBottom** property. The value of the **borderStyleBottomStart** field MUST be one of the following values.

Value	Parent
0x09	SharedStyleProperties NonSharedStyleProperties

borderStyleBottomValue (1 byte): A byte that specifies the style of the bottom border. The value of this field is of type [BorderStyles](#) and it MUST be contained in the enumeration. <40>

2.3.67 BorderWidth

The **BorderWidth** property specifies the width of a border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderWidth** property is overridden by the value of the [BorderWidthLeft](#) for the left border, [BorderWidthRight](#) for the right border, [BorderWidthTop](#) for the top border, or [BorderWidthBottom](#) for the bottom border. If the **BorderWidth** property is not specified, the default value is used.

BorderWidth = borderWidthStart borderWidthValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderWidthStart										borderWidthValue (variable)																							
...																																	

borderWidthStart (1 byte): A byte that specifies the start of the **BorderWidth** property. The value of the **borderWidthStart** field MUST be one of the following values.

Value	Parent
0x0A	SharedStyleProperties NonSharedStyleProperties

borderWidthValue (variable): An [RPLSize](#) variable that specifies the border width. The default value is "Opt".

2.3.68 BorderWidthLeft

The **BorderWidthLeft** property specifies the width of the left border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderWidthLeft** property overrides the [BorderWidth](#) property for the left border. If the **BorderWidthLeft** property is not defined, the value of **BorderWidth** is used.

```
BorderWidthLeft = borderWidthLeftStart borderWidthLeftValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderWidthLeftStart										borderWidthLeftValue (variable)																							
...																																	

borderWidthLeftStart (1 byte): A byte that specifies the start of the **BorderWidthLeft** property. The value of the **borderWidthLeftStart** field MUST be one of the following values.

Value	Parent
0x0B	SharedStyleProperties NonSharedStyleProperties

borderWidthLeftValue (variable): An [RPLSize](#) variable that specifies the width of the left border.

2.3.69 BorderWidthRight

The **BorderWidthRight** property specifies the width of the right border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderWidthRight** property overrides the [BorderWidth](#) property for the right border. If the **BorderWidthRight** property is not defined, the value of **BorderWidth** is used.

```
BorderWidthRight = borderWidthRightStart borderWidthRightValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderWidthRightStart										borderWidthRightValue (variable)																							
...																																	

borderWidthRightStart (1 byte): A byte that specifies the start of the **BorderWidthRight** property. The value of the **borderWidthRightStart** field MUST be one of the following values.

Value	Parent
0x0C	SharedStyleProperties NonSharedStyleProperties

borderWidthRightValue (variable): An [RPLSize](#) variable that specifies the width of the right border.

2.3.70 BorderWidthTop

The **BorderWidthTop** property specifies the width of the top border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderWidthTop** property overrides the [BorderWidth](#) property for the top border. If the **BorderWidthTop** property is not defined, the value of **BorderWidth** is used.

`BorderWidthTop = borderWidthTopStart borderWidthTopValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
borderWidthTopStart										borderWidthTopValue (variable)																							
...																																	

borderWidthTopStart (1 byte): A byte that specifies the start of the **BorderWidthTop** property. The value of the **borderWidthTopStart** field MUST be one of the following values.

Value	Parent
0x0D	SharedStyleProperties NonSharedStyleProperties

borderWidthTopValue (variable): An [RPLSize](#) variable that specifies the width of the top border.

2.3.71 BorderWidthBottom

The **BorderWidthBottom** property specifies the width of the bottom border. If this property is specified, it MUST be part of a [Style](#) record. The value of the **BorderWidthBottom** property overrides the [BorderWidth](#) property for the bottom border. If the **BorderWidthBottom** property is not defined, the value of **BorderWidth** is used.

`BorderWidthBottom = borderWidthBottomStart borderWidthBottomValue`

2.3.73 PaddingRight

The **PaddingRight** property specifies the size of the padding to apply to the right of the contents. If this property is specified, it MUST be part of a [Style](#) record. If the **PaddingRight** property is not specified, the default value is used.

PaddingRight = paddingRightStart paddingRightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
paddingRightStart										paddingRightValue (variable)																							
...																																	

paddingRightStart (1 byte): A byte that specifies the start of the **PaddingRight** property. The value of the **paddingRightStart** field MUST be one of the following values.

Value	Parent
0x10	SharedStyleProperties NonSharedStyleProperties

paddingRightValue (variable): An [RPLSize](#) variable that specifies the padding between the right edge and its contents. The default value is "0pt".

2.3.74 PaddingTop

The **PaddingTop** property specifies the size of the padding to apply to the top of the contents. If this property is specified, it MUST be part of a [Style](#) record. If the **PaddingTop** property is not specified, the default value is used.

PaddingTop = paddingTopStart paddingTopValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
paddingTopStart										paddingTopValue (variable)																							
...																																	

paddingTopStart (1 byte): A byte that specifies the start of the **PaddingTop** property. The value of the **paddingTopStart** field MUST be one of the following values.

Value	Parent
0x11	SharedStyleProperties NonSharedStyleProperties

paddingTopValue (variable): An [RPLSize](#) variable that specifies the padding between the top edge and its contents. The default value is "0pt".

2.3.75 PaddingBottom

The **PaddingBottom** property specifies the size of the padding to apply to the bottom of the contents. If this property is specified, it MUST be part of a [Style](#) record. If the **PaddingBottom** property is not specified, the default value is used.

PaddingBottom = paddingBottomStart paddingBottomValue

										1											2										3		
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
paddingBottomStart										paddingBottomValue (variable)																							
...																																	

paddingBottomStart (1 byte): A byte that specifies the start of the **PaddingBottom** property. The value of the **paddingBottomStart** field MUST be one of the following values.

Value	Parent
0x12	SharedStyleProperties NonSharedStyleProperties

paddingBottomValue (variable): An [RPLSize](#) variable that specifies the padding between the bottom edge and its contents. The default value is "0pt".

2.3.76 FontStyle

The **FontStyle** property specifies the style of the font for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record. If the **FontStyle** property is not specified, the default value is used.

FontStyle = fontStyleStart fontStyleValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
fontStyleStart										fontStyleValue																					

fontStyleStart (1 byte): A byte that specifies the start of the **FontStyle** property. The value of the **fontStyleStart** field MUST be one of the following values.

Value	Parent
0x13	SharedStyleProperties NonSharedStyleProperties

fontStyleValue (1 byte): A byte that specifies the font style. The value of the **fontStyleValue** field is of type [FontStyles](#) and it MUST be contained in the **FontStyles** enumeration. <41> The default value is 0x00.

2.3.77 FontFamily

The **FontFamily** property specifies the name of the font family for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record. If the **FontFamily** property is not specified, the default value is used.

FontFamily = fontFamilyStart fontFamilyValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
fontFamilyStart										fontFamilyValue (variable)																							
...																																	

fontFamilyStart (1 byte): A byte that specifies the start of the **FontFamily** property. The value of the **fontFamilyStart** field MUST be one of the following values.

Value	Parent
0x14	SharedStyleProperties NonSharedStyleProperties

fontFamilyValue (variable): A **String** variable that specifies the font family. The default value is "Arial".

2.3.78 FontSize

The **FontSize** property specifies the size of the font for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record.

FontSize = fontSizeStart fontSizeValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
fontSizeStart										fontSizeValue (variable)																							
...																																	

fontSizeStart (1 byte): A byte that specifies the start of the **FontSize** property. The value of the **fontSizeStart** field MUST be one of the following values.

Value	Parent
0x15	SharedStyleProperties NonSharedStyleProperties

fontSizeValue (variable): An [RPLSize](#) variable that specifies the font family.

2.3.79 FontWeight

The **FontWeight** property specifies the thickness of the font for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record. If the **FontWeight** property is not specified, the default value is used.

FontWeight = fontWeightStart fontWeightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
fontWeightStart										fontWeightValue																							

fontWeightStart (1 byte): A byte that specifies the start of the **FontWeight** property. The value of the **fontWeightStart** field MUST be one of the following values.

Value	Parent
0x16	SharedStyleProperties NonSharedStyleProperties

fontWeightValue (1 byte): A byte that specifies the font weight. The value of this field is of type [FontWeights](#) and it MUST be contained in the **FontWeights** enumeration. [<42>](#) The default value is 0x00.

2.3.80 Format

The **Format** property specifies a formatting **String** for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record.

```
Format = formatStart formatValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
formatStart										formatValue (variable)																							
...																																	

formatStart (1 byte): A byte that specifies the start of the **Format** property. The value of the **formatStart** field MUST be one of the following values.

Value	Parent
0x17	SharedStyleProperties NonSharedStyleProperties

formatValue (variable): A **String** variable that specifies the formatting **String**.

2.3.81 TextDecoration

The **TextDecoration** property specifies the special formatting for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record. If the **TextDecoration** property is not specified, the default value is used.

```
TextDecoration = textDecorationStart textDecorationValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
textDecorationStart										textDecorationValue																							

textDecorationStart (1 byte): A byte that specifies the start of the **TextDecoration** property. The value of the **textDecorationStart** field MUST be one of the following values.


Value	Parent
0x18	SharedStyleProperties NonSharedStyleProperties

textDecorationValue (1 byte): A byte that specifies the **text decoration**. The value of the **textDecorationValue** field is of type [TextDecorations](#) and it MUST be contained in the **TextDecorations** enumeration.<43> The default value is 0x00.

2.3.82 TextAlign

The **TextAlign** property specifies the horizontal alignment for a contiguous set of characters. If this property is specified, it MUST be part of the [Style](#) record. If the **TextAlign** property is not specified, the default value is used.

```
TextAlign = textAlignStart textAlignValue
```



textAlignStart (1 byte): A byte that specifies the start of the **TextAlign** property. The value of the **textAlignStart** field MUST be one of the following values.

Value	Parent
0x19	SharedStyleProperties NonSharedStyleProperties

textAlignValue (1 byte): A byte that specifies the horizontal alignment of text. The value of the **textAlignValue** field is of type [TextAlignments](#) and it MUST be contained in the **TextAlignments** enumeration.<44> The default value is 0x00.

2.3.83 VerticalAlign

The **VerticalAlign** property specifies the vertical alignment for a contiguous set of characters. If this property is specified, it MUST be part of a [Style](#) record. If the **VerticalAlign** property is not specified, the default value is used.

```
VerticalAlign = verticalAlignStart verticalAlignValue
```


LineHeight = lineHeightStart lineHeightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
lineHeightStart										lineHeightValue (variable)																					
...																															

lineHeightStart (1 byte): A byte that specifies the start of the **LineHeight** property. The value of the **lineHeightStart** field MUST be one of the following values.

Value	Parent
0x1C	SharedStyleProperties NonSharedStyleProperties

lineHeightValue (variable): An [RPLSize](#) variable that specifies the height of a line of text.

2.3.86 Direction

The **Direction** property specifies the direction in which a contiguous set of characters is written. If this property is specified, it MUST be part of a [Style](#) record. If the **Direction** property is not specified, the default value is used.

Direction = directionStart directionValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
directionStart										directionValue																					

directionStart (1 byte): A byte that specifies the start of the **Direction** property. The value of the **directionStart** field MUST be one of the following values.

Value	Parent
0x1D	SharedStyleProperties NonSharedStyleProperties

directionValue (1 byte): A byte that specifies the direction the text is written. The value of this field is of type [Directions](#) and it MUST be contained in the **Directions** enumeration. [<47>](#) The default value is 0x00.

2.3.87 WritingMode

The **WritingMode** property specifies whether a contiguous set of characters is written horizontally or vertically. If this property is specified, it MUST be part of a [Style](#) record. If the **WritingMode** property is not specified, the default value is used.

WritingMode = writingModeStart writingModeValue

									1																				2										3			
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1											
writingModeStart									writingModeValue																																	

writingModeStart (1 byte): A byte that specifies the start of the **WritingMode** property. The value of the **writingModeStart** field MUST be one of the following values.

Value	Parent
0x1E	SharedStyleProperties NonSharedStyleProperties

writingModeValue (1 byte): A byte that specifies whether text is written horizontally or vertically. The value of this field is of type [WritingModes](#) and it MUST be contained in the **WritingModes** enumeration. [<48>](#) The default value is 0x00.

2.3.88 UnicodeBiDi

The **UnicodeBiDi** property specifies the level of embedding with respect to the bidirectional algorithm. If this property is specified, it MUST be part of a [Style](#) record. If the **UnicodeBiDi** property is not specified, the default value is used.

UnicodeBiDi = unicodeBiDiStart unicodeBiDiValue

										1																				2											3			
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1													
unicodeBiDiStart									unicodeBiDiValue																																			

unicodeBiDiStart (1 byte): A byte that specifies the start of the **UnicodeBiDi** property. The value of the **unicodeBiDiStart** field MUST be one of the following values.

Value	Parent
0x1F	SharedStyleProperties NonSharedStyleProperties

unicodeBiDiValue (1 byte): A byte that specifies the level of embedding with respect to the bidirectional algorithm. The value of this field is of type [UnicodeBiDiTypes](#) and it MUST be contained in the **UnicodeBiDiTypes** enumeration. [<49>](#) The default value is 0x00.

2.3.89 BackgroundImage

The **BackgroundImage** property specifies the image to use as a background. If this property is specified, it MUST be part of a [Style](#) record.

BackgroundImage = backgroundImageStart backgroundImageValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
backgroundImageStart										backgroundImageValue (variable)																							
...																																	

backgroundImageStart (1 byte): A byte that specifies the start of the **BackgroundImage** property. The value of the **backgroundImageStart** field MUST be one of the following values.

Value	Parent
0x21	SharedStyleProperties NonSharedStyleProperties

backgroundImageValue (variable): An [ImageDataProperties](#) record that specifies the background image of a structure.

2.3.90 BackgroundColor

The **BackgroundColor** property specifies the color to use for the background. If this property is specified, it MUST be part of a [Style](#) record. If the **BackgroundColor** property is not specified, the background color MUST be interpreted as being transparent.

BackgroundColor = backgroundColorStart backgroundColorValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
backgroundColorStart										backgroundColorValue (variable)																							
...																																	

backgroundColorStart (1 byte): A byte that specifies the start of the **BackgroundColor** property. The value of **backgroundColorStart** field MUST be one of the following values.

Value	Parent
0x22	SharedStyleProperties NonSharedStyleProperties

backgroundColorValue (variable): A **String** variable that specifies the background color. A background color value can be a color name (user-defined system colors are not supported), an RGB color **String** of the form #HHHHHH, or an ARGB color **String** of the form #HHHHHHHH.[<50>](#)

2.3.91 BackgroundRepeat

The **BackgroundRepeat** property specifies how a background image should occupy the available space within its parent container. If this property is specified, it MUST be part of a [Style](#) record. If the **BackgroundRepeat** property is not specified, the default value is used.

`BackgroundRepeat = backgroundRepeatStart backgroundRepeatValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
backgroundRepeatStart										backgroundRepeatValue																					

backgroundRepeatStart (1 byte): A byte that specifies the start of **BackgroundRepeat** property. The value of the **backgroundRepeatStart** field MUST be one of the following values.

Value	Parent
0x23	SharedStyleProperties NonSharedStyleProperties

backgroundRepeatValue (1 byte): A byte that specifies how the background image should occupy the available space. The value of this field is of type [BackgroundRepeatTypes](#) and it MUST be contained in the **BackgroundRepeatTypes** enumeration.[<51>](#) The default value is 0x00.

2.3.92 NumeralLanguage

The **NumeralLanguage** property specifies the digit format to use as determined by a language. If this property is specified, it MUST be part of a [Style](#) record. If the **NumeralLanguage** property is not specified, its value MUST be the same as the peer [Language](#) style property.

`NumeralLanguage = numeralLanguageStart numeralLanguageValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
numeralLanguageStart										numeralLanguageValue (variable)																							
...																																	

numeralLanguageStart (1 byte): A byte that specifies the start of the **NumeralLanguage** property. The value of **numeralLanguageStart** field MUST be one of the following values.

Value	Parent
0x24	SharedStyleProperties NonSharedStyleProperties

numeralLanguageValue (variable): A **String** variable that specifies the digit format to use as determined by a language. The value MUST be a valid language code, which is a combination of an ISO 639 two-letter lowercase culture code associated with a language, and an ISO 3166 (see [ISO-3166](#)) two-letter uppercase subculture code associated with a country or region.

2.3.93 NumeralVariant

The **NumeralVariant** property specifies the variant of the digit format to use. If this property is specified, it MUST be part of a [Style](#) record.

NumeralVariant = numeralVariantStart numeralVariantValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1		
numeralVariantStart										numeralVariantValue																							
...																																	

numeralVariantStart (1 byte): A byte that specifies the start of the **NumeralVariant** property. The value of the **numeralVariantStart** field value MUST be one of the following values.

Value	Parent
0x25	SharedStyleProperties NonSharedStyleProperties

numeralVariantValue (4 bytes): An integer variable value that specifies the variant of the digit format to use. [52](#) The default value is 0x00000001. The value of the **numeralVariantValue** field MUST be one of the following values.

Value	Meaning
0x00000001	Default, follow Unicode context rules.
0x00000002	0123456789
0x00000003	Traditional digits for the script as defined in GDI+. Applicable only to numeral languages with the following cultures: ar, bn, bo, fa, gu, hi, kn, kok, lo, mr, ms, or, pa, sa, ta, te, th, ur
0x00000004	Applicable only to numeral languages with the following cultures: ko, ja, zh-CHS, zh-CHT
0x00000005	Applicable only to numeral languages with the following cultures: ko, ja, zh-CHS, zh-CHT
0x00000006	Applicable only to numeral languages with the following cultures: ko, ja, zh-CHS, zh-CHT [Wide versions of regular digits]
0x00000007	Applicable only to numeral languages with the following cultures: ko

2.3.94 Calendar

The **Calendar** property specifies the **calendar** to use for formatting dates. If the **Calendar** property is specified, its value MUST be compatible with the .NET Framework Language setting. The property MUST be part of a [Style](#) record. If the **Calendar** property is not specified, the default value is used.

Calendar = calendarStart calendarValue

											1									2									3		
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
calendarStart											calendarValue																				

calendarStart (1 byte): A byte that specifies the start of the **Calendar** property. The value of the **calendarStart** field MUST be one of the following values.

Value	Parent
0x26	SharedStyleProperties NonSharedStyleProperties

calendarValue (1 byte): A byte that specifies the calendar to use for formatting dates. The value of the **calendarValue** field is of type [Calendars](#) and it MUST be contained in the **Calendars** enumeration. [<53>](#) The default value is defined by default calendar of the [Language](#) peer style property.

2.3.95 ColumnHeaderRows

The **ColumnHeaderRows** property specifies the number of visible rows in a [Tablix](#) column headers area. If the **ColumnHeaderRows** property is specified, it MUST be part of the [TablixMeasurements](#) record. If the **ColumnHeaderRows** property is not specified, the default value is used.

ColumnHeaderRows = columnHeaderRowsStart columnHeaderRowsValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
columnHeaderRowsStart										columnHeaderRowsValue																					
...																															

columnHeaderRowsStart (1 byte): A byte that specifies the start of **ColumnHeaderRows** property. The value of **columnHeaderRowsStart** field MUST be the following value.

Value	Parent
0x00	TablixMeasurements

columnHeaderRowsValue (4 bytes): A signed **integer** that MUST be greater than or equal to zero. [54](#) The default value of this field is 0x00000000.

2.3.96 RowHeaderColumns

The **RowHeaderColumns** property specifies the number of visible columns in the [Tablix](#) row headers area. If the **RowHeaderColumns** property is specified, it MUST be part of the [TablixMeasurements](#) record. If the **RowHeaderColumns** property is not specified, the default value is used.

RowHeaderColumns = rowHeaderColumnsStart rowHeaderColumnsValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rowHeaderColumnsStart										rowHeaderColumnsValue																					
...																															

rowHeaderColumnsStart (1 byte): A byte that specifies the start of the **RowHeaderColumns** property. The value of the **rowHeaderColumnsStart** field MUST be the following value.

Value	Parent
0x01	TablixMeasurements

rowHeaderColumnsValue (4 bytes): A signed **integer** that MUST be greater than or equal to zero. [55](#) The default value of this field is 0x00000000.

2.3.97 ColsBeforeRowHeader

The **ColsBeforeRowHeader** property specifies the number of [Tablix](#) body area columns, which are displayed in order specified by the [LayoutDirection](#) property. The **LayoutDirection** property MUST be rendered before the row headers area. If the **ColsBeforeRowHeader** property is specified, it MUST be part of the [TablixMeasurements](#) record. If this property is not specified, the default value is used.

ColsBeforeRowHeader = colsBeforeRowHeaderStart colsBeforeRowHeaderValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
colsBeforeRowHeaderStart										colsBeforeRowHeaderValue																					
...																															

colsBeforeRowHeaderStart (1 byte): A byte that specifies the start of the **ColsBeforeRowHeader** property. The value of the **colsBeforeRowHeaderStart** field MUST be the following value.

Value	Parent
0x02	TablixMeasurements

colsBeforeRowHeaderValue (4 bytes): A signed **integer** that MUST be greater than or equal to zero. [<56>](#) The default value of this field is 0x00000000.

2.3.98 LayoutDirection

The **LayoutDirection** property specifies the direction of the layout of [Tablix](#) columns. If this property is specified, it MUST be part of the [TablixMeasurements](#) record. If this property is not specified, the default value is used.

LayoutDirection = layoutDirectionStart layoutDirectionValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
layoutDirectionStart										layoutDirectionValue																					

layoutDirectionStart (1 byte): A byte that specifies the start of the **LayoutDirection** property. The value of the **layoutDirectionStart** field MUST be the following value.

Value	Parent
0x03	TablixMeasurements

layoutDirectionValue (1 byte): A byte that specifies the layout direction of tablix columns. The value of the **layoutDirectionValue** field MUST be defined by the [Directions](#) enumeration. The default value is 0x00.

2.3.99 DefinitionPath

The **DefinitionPath** property specifies a unique identifier for a [TablixMemberDef](#) record. If this property is specified, it MUST be part of the **TablixMemberDef** record.

DefinitionPath = definitionPathStart definitionPathValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1													
										1																	2																	3
definitionPathStart										definitionPathValue (variable)																																		
...																																												

definitionPathStart (1 byte): A byte that specifies the start of a **DefinitionPath** property. The value of the **definitionPathStart** field MUST be the following value.

Value	Parent
0x00	TablixMemberDef

definitionPathValue (variable): A **String** variable that specifies a unique identifier for a **tablix member**.

2.3.100 Level

The **Level** property specifies the level of a [TablixMemberDef](#) record in the row or column hierarchy of a [Tablix](#) record. If the **Level** property is specified, it MUST be part of a **TablixMemberDef** record. If the **Level** property is not specified, the default value is used.

Level = levelStart levelValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1													
										1																	2																	3
levelStart										levelValue																																		

...	
-----	--

levelStart (1 byte): A byte that specifies the start of the **Level** property. The value of the **levelStart** field MUST be the following value.

Value	Parent
0x01	TablixMemberDef

levelValue (4 bytes): A signed **integer** that specifies the level of a tablix member definition. The default value is 0x00000000.

2.3.101 MemberCellIndex

The **MemberCellIndex** property specifies the index of a tablix body cell in the report definition. In the report definition, tablix body cells are organized in a double-indexed array. The first index specifies the row index. The second index specifies the column index.

If the **MemberCellIndex** property is specified, it MUST be part of a [TablixMemberDef](#) record. If the ancestor of the **MemberCellIndex** is [TablixRowHeader](#), the **MemberCellIndex** property MUST be a row index in the tablix body cells in report definition. If the ancestor of the **MemberCellIndex** property is [TablixColumnHeader](#), the **MemberCellIndex** property MUST be a column index in the tablix body cells in report definition. If this property is not specified, the default value is used.

`MemberCellIndex = memberCellIndexStart memberCellIndexValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
memberCellIndexStart										memberCellIndexValue																					
...																															

memberCellIndexStart (1 byte): A byte that specifies the start of a **MemberCellIndex** property. The value of **memberCellIndexStart** field MUST be the following value.

Value	Parent
0x02	TablixMemberDef


memberCellIndexValue (4 bytes): A signed **integer** value that specifies the index of a tablix body cell in the report definition. The default value is 0x00000000.

2.3.102 CellItemOffset

The **CellItemOffset** property specifies the position of a [ReportElementEnd](#) record in an RPL stream. The value of the **CellItemOffset** property MUST correspond to the top-level report item of a tablix cell.

If the **CellItemOffset** property is specified, it MUST be part of a [TablixCorner](#), [TablixRowHeader](#), [TablixColumnHeader](#), or [TablixBodyCell](#) record.

CellItemOffset = cellItemOffsetStart cellItemOffset



cellItemOffsetStart (1 byte): A byte that specifies the start of the **CellItemOffset** property. The value of the **cellItemOffsetStart** field MUST be one of the following values.

Value	Parent
0x04	TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell

cellItemOffsetValue (8 bytes): A signed integer that specifies the position of a **ReportElementEnd** record in the RPL stream, and that MUST correspond to the top-level [ReportItem](#) record of the parent tablix cell.

2.3.103 ColSpan

The **ColSpan** property specifies the number of columns a cell spans in a [Tablix](#) record. If this property is specified, it MUST be part of a [TablixCorner](#), [TablixRowHeader](#), [TablixColumnHeader](#), or [TablixBodyCell](#) record. If the **ColSpan** property is not specified, the default value is used.

ColSpan = colSpanStart colSpanValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
colSpanStart										colSpanValue																					
...																															

colSpanStart (1 byte): A byte that specifies the start of the **ColSpan** property. The value of the **colSpanStart** field MUST be one of the following values.

Value	Parent
0x05	TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell

colSpanValue (4 bytes): A signed integer that specifies the number of columns the parent cell spans. The default value is 0x00000001.

2.3.104 RowSpan

The **RowSpan** property specifies the number of rows a cell spans in a [Tablix](#) record. If the **RowSpan** property is specified, it MUST be part of a [TablixCorner](#), [TablixRowHeader](#), [TablixColumnHeader](#), or [TablixBodyCell](#) record. If the **RowSpan** property is not specified, the default value is used.

RowSpan = rowSpanStart rowSpanValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rowSpanStart										rowSpanValue																					
...																															

rowSpanStart (1 byte): A byte that specifies the start of the **RowSpan** property. The value of the **rowSpanStart** field MUST be one of the following values.

Value	Parent
0x06	TablixCorner TablixColumnHeader TablixRowHeader

Value	Parent
	TablixBodyCell

rowSpanValue (4 bytes): A signed integer that specifies the number of rows the parent cell spans. The default value is 0x00000001.

2.3.105 DefIndex

The **DefIndex** property specifies the zero-based index of a [TablixMemberDef](#) record. The index is stored in the **tablixMembersDefContents** array field of a [TablixColMembersDef](#) or [TablixRowMembersDef](#) record that corresponds to a column or row header in a [Tablix](#) record. If the **DefIndex** property is specified, it MUST be part of a [TablixColumnHeader](#) or [TablixRowHeader](#) record.

DefIndex = defIndexStart defIndexValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
defIndexStart										defIndexValue																					
...																															

defIndexStart (1 byte): A byte that specifies the start of the **DefIndex** property. The value of **defIndexStart** field MUST be one of the following values.

Value	Parent
0x07	TablixColumnHeader TablixRowHeader

defIndexValue (4 bytes): A signed integer that MUST specify the index of a **TablixMemberDef** record. The index is stored into the **tablixMembersDefContents** array field of a **TablixColMembersDef** or **TablixRowMembersDef** record. If the parent is a **TablixColumnHeader**, the value of the **defIndexValue** field MUST be greater than or equal to zero and MUST be less than the **count** field of the **TablixColMembersDef** record of the parent **Tablix** record. If the parent is a **TablixRowHeader**, the value of the **defIndexValue** field MUST be greater than or equal to zero and MUST be less than the **count** field of the **TablixRowMembersDef** record of the parent **Tablix** record.

2.3.106 ColumnIndex

The **ColumnIndex** property specifies the zero-based index of the first column for a tablix cell. If the **ColumnIndex** property is specified, it MUST be part of [TablixCorner](#), [TablixRowHeader](#), [TablixColumnHeader](#), or [TablixBodyCell](#) record. If the **ColumnIndex** property is not specified, the default value is used.

ColumnIndex = columnIndexStart columnIndexValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
columnIndexStart										columnIndexValue																					
...																															

columnIndexStart (1 byte): A byte that specifies the start of the **ColumnIndex** property. The value of the **columnIndexStart** field MUST be one of the following values.

Value	Parent
0x08	TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell

columnIndexValue (4 bytes): A signed integer that specifies the zero-based index of the first column for a tablix cell. The value of this field MUST greater or equal to zero. The addition of the **ColSpan** property to the **columnIndexValue** field MUST result in a value that is less than the **count** field of **ColumnsWidths** record of the [Tablix](#) record. <57> The default value is 0xFFFFFFFF.

2.3.107 RowIndex

The **RowIndex** property specifies the zero-based index of the starting row for a tablix cell. If this property is specified, it MUST be part of [TablixCorner](#), [TablixRowHeader](#), [TablixColumnHeader](#), or [TablixBodyCell](#) record. If the **RowIndex** property is not specified, the default value is used.

RowIndex = rowIndexStart rowIndexValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rowIndexStart										rowIndexValue																					
...																															

rowIndexStart (1 byte): A byte that specifies the start of the **RowIndex** property. The value of the **rowIndexStart** field MUST be one of the following values.

Value	Parent
0x09	TablixCorner TablixColumnHeader TablixRowHeader

rowIndexValue (4 bytes): A signed integer that specifies the zero-based index of the first row for a tablix cell. The value of this field MUST be greater than or equal to zero. The addition of the [RowSpan](#) property to this field MUST result in a value that is less than the **count** field of the [RowHeights](#) record of the [Tablix](#) record. <58> The default value is 0xFFFFFFFF.

2.3.108 GroupLabel

The **GroupLabel** property specifies the label for a row header or column header of a [Tablix](#) record. If this property is specified, it MUST be part of a [TablixRowHeader](#) or [TablixColumnHeader](#).

```
GroupLabel = groupLabelStart groupLabelValue
```

									1											2															3		
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1						
groupLabelStart										groupLabelValue (variable)																											
...																																					

groupLabelStart (1 byte): A byte that specifies the start of the **GroupLabel** structure. The value of the **groupLabelStart** field MUST be one of the following values.

Value	Parent
0x0A	TablixColumnHeader TablixRowHeader

groupLabelValue (variable): A **String** that specifies the label for a row header or column header of the **Tablix** record.

2.3.109 RecursiveToggleLevel

The **RecursiveToggleLevel** property specifies the **recursive toggling** state of a row header or column header of a [Tablix](#) record. If the **RecursiveToggleLevel** property is specified, it MUST be part of a [TablixRowHeader](#) or [TablixColumnHeader](#). If the **RecursiveToggleLevel** property is not specified, the default value is used.

```
RecursiveToggleLevel = recursiveToggleLevelStart recursiveToggleLevelValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
recursiveToggleLevelStart										recursiveToggleLevelValue																					
...																															

recursiveToggleLevelStart (1 byte): A byte that specifies the start of the **RecursiveToggleLevel** property. The value of the **recursiveToggleLevelStart** field MUST be one of the following values.

Value	Parent
0x0E	TablixColumnHeader TablixRowHeader

recursiveToggleLevelValue (4 bytes): A signed integer that specifies the recursive toggling state of a row header or column header of the **Tablix** record. The default value is 0xFFFFFFFF. The value of the **recursiveToggleLevelValue** field MUST be one of the following.

Value	Parent
<0	The group of parent header is not recursive, the parent header is not toggleable, or the toggle is not recursive.
0	This parent header is a root of a toggleable recursive forest.
>0	This parent header is a child in the toggleable recursive hierarchy. The value specifies the depth of the item in the recursive hierarchy.

2.3.110 ListStyle

The **ListStyle** property specifies if a [Paragraph](#) record is part of a list and identifies the numbering type. If the **ListStyle** property is specified, it MUST be part of a [Paragraph.ElementProperties](#) record. If the **ListStyle** property is not specified, the default value is used.

ListStyle = listStyleStart listStyleValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
listStyleStart										listStyleValue																					

listStyleStart (1 byte): A byte that specifies the start of the **ListStyle** property. The value of the **listStyleStart** field MUST be one of the following.

Value	Parent
0x07	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for Paragraph

listStyleValue (1 byte): A byte that specifies whether the paragraph is part of a list, and that identifies the numbering type. The value of the **listStyleValue** field is of type [ListStyles](#) and it MUST be contained in the **ListStyles** enumeration. The default value is 0x00.

2.3.111 ListLevel

The **ListLevel** property specifies the numbering style and/or indentation level of a [Paragraph](#) record. If the **ListLevel** property is specified, it MUST be part of a [Paragraph.ElementProperties](#) record. If the **ListLevel** property is not specified, the default value is used.

```
ListLevel = listLevelStart listLevelValue
```

1										2										3											
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
listLevelStart										listLevelValue																					
...																															

listLevelStart (1 byte): A byte that specifies the start of the **ListLevel** property. The value of the **listLevelStart** field MUST be one of the following.

Value	Parent
0x08	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for Paragraph

listLevelValue (4 bytes): A signed integer that specifies the numbering style and/or indentation level of the **Paragraph** record. The default value is 0x00000000.

2.3.112 ParagraphNumber

The **ParagraphNumber** property specifies the one-based index of a [Paragraph](#) record, which is a member of list of paragraphs that have the same value for a [ListLevel](#) property and MUST have the [ListStyle](#) property set to 0x01. If the **ParagraphNumber** property is specified, it MUST be part of a [ElementProperties.NonSharedElementProperties](#) record for a **Paragraph** record. If the **ParagraphNumber** property is not specified, the default value is used.

```
ParagraphNumber = paragraphNumberStart paragraphNumberValue
```


0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
paragraphNumberStart										paragraphNumberValue																					
...																															

paragraphNumberStart (1 byte): A byte that specifies the start of the **ParagraphNumber** property. The value of the **paragraphNumberStart** field MUST be one of the following.

Value	Parent
0x0E	ElementProperties.NonSharedElementProperties for Paragraph

paragraphNumberValue (4 bytes): A signed integer that specifies the number of the paragraph, which is a member of a list of paragraphs that have the same value for the **ListLevel** property and MUST have the **ListStyle** property set to 0x01. [<59>](#) The default value is 0x00000000.

2.3.113 RightIndent

The **RightIndent** property specifies the indentation for all text within a paragraph from the right edge of the text box containing the [Paragraph](#). If this property is specified, it MUST be part of [Paragraph.ElementProperties](#) record.

```
RightIndent = rightIndentStart rightIndentValue
```

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
rightIndentStart										rightIndentValue (variable)																					
...																															

rightIndentStart (1 byte): A byte that specifies the start of the **RightIndent** property. The value of the **rightIndentStart** field MUST be one of the following.

Value	Parent
0x0A	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for Paragraph

rightIndentValue (variable): An [RPLSize](#) variable that specifies the indentation for all text within a paragraph from the right edge of the text box containing the paragraph.

2.3.114 LeftIndent

The **LeftIndent** property specifies the indentation for all text within a paragraph from the left edge of the text box containing the [Paragraph](#) record. If this property is specified, it MUST be part of a [Paragraph.ElementProperties](#) record.

LeftIndent = leftIndentStart leftIndentValue

0	1	2	3	4	5	6	7	8	9	1				0	1	2	3	4	5	6	7	8	9	2				0	1	2	3	4	5	6	7	8	9	3			0	1
leftIndentStart										leftIndentValue (variable)																																
...																																										

leftIndentStart (1 byte): A byte that specifies the start of the **LeftIndent** property. The value of the **leftIndentStart** field MUST be one of the following.

Value	Parent
0x09	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for Paragraph

leftIndentValue (variable): An [RPLSize](#) variable that specifies the indentation for all text within a paragraph from the left edge of the text box containing the paragraph.

2.3.115 HangingIndent

The **HangingIndent** property specifies the indent of the first line of text within a paragraph relative to the [LeftIndent](#) property of the same paragraph. If this property is specified, it MUST be part of a [Paragraph.ElementProperties](#) record.

HangingIndent = hangingIndentStart hangingIndentValue

0	1	2	3	4	5	6	7	8	9	1				0	1	2	3	4	5	6	7	8	9	2				0	1	2	3	4	5	6	7	8	9	3			0	1
hangingIndentStart										hangingIndentValue (variable)																																
...																																										

hangingIndentStart (1 byte): A byte that specifies the start of the **HangingIndent** property. The value of the **hangingIndentStart** field MUST be one of the following.

...

spaceAfterStart (1 byte): A byte that specifies the start of the **SpaceAfter** property. The value of the **spaceAfterStart** field **MUST** be the following.

Value	Parent
0x0D	ElementProperties.InlineSharedElementProperties for Paragraph ElementProperties.NonSharedElementProperties for Paragraph

spaceAfterValue (variable): An [RPLSize](#) variable that specifies vertical spacing after a paragraph.

2.3.118 FirstLine

The **FirstLine** property specifies if the first line of text of a paragraph is part of the current report page. If this property is specified, it **MUST** be part of a [ElementProperties.NonSharedElementProperties](#) record of a [Paragraph](#) record. If the **FirstLine** property is not specified, the default value is used.

`FirstLine = firstLineStart firstLineValue`

										1																	2													3		
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	
firstLineStart											firstLineValue																															

firstLineStart (1 byte): A byte that specifies the start of the **FirstLine** structure. The value of the **firstLineStart** field **MUST** be one of the following.

Value	Parent
0x0F	ElementProperties.NonSharedElementProperties for Paragraph

firstLineValue (1 byte): A **Boolean** value that specifies whether the first line of text of a paragraph is part of the current report page. The default value is 0x01.

2.3.119 Markup

The **Markup** property specifies the markup style for a [TextRun](#) record. If this property is specified, it **MUST** be part of an [ElementProperties](#) record of a **TextRun**. If the **Markup** property is not specified, the default value is used.

`Markup = markupStart markupValue`

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
markupStart										markupValue																					

markupStart (1 byte): A byte that specifies the start of the **Markup** property. The value of the **markupStart** field MUST be one of the following.

Value	Parent
0x07	ElementProperties.InlineSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for TextRun

markupValue (1 byte): A byte that specifies the markup style for a **TextRun** record. The value of the **markupValue** field is of type [MarkupStyles](#) and it MUST be contained in the **MarkupStyles** enumeration. The default value is 0x00.

2.3.120 ContentTop

The **ContentTop** property specifies the top position of the content relative to the container top. If this property is specified, it MUST be part of a [TextRun](#), [Paragraph](#), [TablixMeasurements](#), [TablixCorner](#), [TablixColumnHeader](#), [TablixRowHeader](#), or [TablixBodyCell](#) record. If the **ContentTop** property is not specified, the default value is used.

ContentTop = contentTopStart contentTopValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
contentTopStart										contentTopValue																					
...																															

contentTopStart (1 byte): A byte that specifies the start of the **ContentTop** property. The value of the **contentTopStart** field MUST be one of the following.

Value	Parent
0x00	ElementProperties.NonSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for Paragraph TablixCorner TablixColumnHeader TablixRowHeader TablixBody Cell

Value	Parent
0x06	TablixMeasurements

contentTopValue (4 bytes): A floating point value that specifies the top position of the content relative to the container start. The default value is 0x00000000.

2.3.121 ContentLeft

The **ContentLeft** property specifies the size of the left position relative to the container top. The **ContentLeft** property MUST be part of a [TextRun](#), [Paragraph](#), [TablixMeasurements](#), [TablixCorner](#), [TablixColumnHeader](#), [TablixRowHeader](#), or [TablixBodyCell](#) record. If the **ContentLeft** property is not specified, the default value is used.

ContentLeft = contentLeftStart contentLeftValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
contentLeftStart										contentLeftValue																					
...																															

contentLeftStart (1 byte): A byte that specifies the start of the **ContentLeft** property. The value of the **contentLeftStart** field MUST be one of the following.

Value	Parent
0x01	ElementProperties.NonSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for Paragraph TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell
0x07	TablixMeasurements

contentLeftValue (4 bytes): A floating point value that specifies the left position relative to the container top. The default value is 0x00000000.

2.3.122 ContentWidth

The **ContentWidth** property specifies the width of the content of a container. If the **ContentWidth** property is specified, it MUST be part of a [TextRun](#), [Paragraph](#), [TablixCorner](#), [TablixColumnHeader](#), [TablixRowHeader](#), or [TablixBodyCell](#) record. If the **ContentWidth** property is not specified, the default value is used.

ContentWidth = contentWidthStart contentWidthValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
contentWidthStart										contentWidthValue																					
...																															

contentWidthStart (1 byte): A byte that specifies the start of the **ContentWidth** property. The value of the **contentWidthStart** field MUST be one of the following.

Value	Parent
0x02	ElementProperties.NonSharedElementProperties for TextRun ElementProperties.NonSharedElementProperties for Paragraph TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell

contentWidthValue (4 bytes): A floating point value that specifies the width of the content of a container. The default value is defined by the container width.

2.3.123 ContentHeight

The **ContentHeight** property specifies the height of the content of a container. If the **ContentHeight** property is specified, it MUST be part of a [TextRun](#), [Paragraph](#), [TablixCorner](#), [TablixColumnHeader](#), [TablixRowHeader](#), [TablixBodyCell](#), or [ElementProperties.NonSharedElementProperty](#) record. If the **ContentHeight** property is not specified, the default value is used.

ContentHeight = contentHeightStart contentHeightValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
contentHeightStart										contentHeightValue																					
...																															

contentHeightStart (1 byte): A byte that specifies the start of the **ContentHeight** property. The value of the **contentHeightStart** field MUST be one of the following.

Value	Parent
0x03	TextRun Paragraph TablixCorner TablixColumnHeader TablixRowHeader TablixBody Cell
0x24	ElementProperties.NonSharedElementProperty for RichTextBox

contentHeightValue (4 bytes): A floating point value that specifies the height of the content of a container. The default value is defined by the container height.

2.3.124 State

The **State** property specifies the state of a row header or column header of a [Tablix](#) record. If the **State** property is specified, it MUST be part of a [TablixRowHeader](#) or [TablixColumnHeader](#) record. If the **State** property is not specified, the default value is used.

```
State = stateStart stateValue
```

0	1	2	3	4	5	6	7	8	9	1	0	1	2	3	4	5	6	7	8	9	2	0	1	2	3	4	5	6	7	8	9	0	1	3	0	1
stateStart										stateValue																										

stateStart (1 byte): A byte that specifies the start of the **State** property. The value of the **stateStart** field MUST be one of the following.

Value	Parent
0X0C	TablixRowHeader TablixColumnHeader

stateValue (1 byte): A byte that specifies the state of a row header or column header of a **Tablix** record. The meaning of this field value is derived from the [TablixMemberStateValues](#) structure. The default value is 0x00.

2.3.125 CellItemState

The **CellItemState** property specifies the state of the top-level report item of a tablix cell. If the **CellItemState** property is specified, it MUST be part of a [TablixBodyCell](#), [TablixComer](#), [TablixRowHeader](#), or [TablixColumnHeader](#) record. If this property is not specified, the default value is used.

```
CellItemState = stateStart stateValue
```


0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
stateStart										stateValue																					

stateStart (1 byte): A byte that specifies the start of the **CellItemState** property. The value of the **stateStart** field MUST be one of the following.

Value	Parent
0x0D	TablixCorner TablixColumnHeader TablixRowHeader TablixBodyCell

stateValue (1 byte): A byte that specifies the state of the top-level report item of a tablix cell. The meaning of this field value is derived from the [StateValues](#) enumeration. The default value is 0x00.

2.3.126 MemberDefState

The **MemberDefState** property specifies the state of a row header or column header definition of a [Tablix](#) record. If the **MemberDefState** property is specified, it MUST be part of a [TablixMemberDef](#) record. If the **MemberDefState** property is not specified, the default value is used.

MemberDefState = stateStart stateValue

0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1
stateStart										stateValue																					

stateStart (1 byte): A byte that specifies the start of the **MemberDefState** property. The value of the **stateStart** field MUST be one of the following.

Value	Parent
0x03	TablixMemberDef

stateValue (1 byte): A byte that specifies the state of a row header or column header definition of a **Tablix** record. The meaning of this field value is derived from the [TablixMemberDefStateValues](#) enumeration. The default value is 0x00.

2.4 Enumerations

This section describes the enumerations that can be used in the RPL stream. Valid values are specified for each enumeration.

2.4.1 SortOptions

The **SortOptions** enumeration specifies the sort state of a [RichTextBox](#) record. This enumeration contains valid values for the [SortState](#) property. The value of the **SortOptions** enumeration MUST be one of the following.

Value	Meaning
0x00	None
0x01	Ascending
0x02	Descending

2.4.2 Sizings

The **Sizings** enumeration specifies the options for sizing an image when it does not fit within the specified size. This enumeration contains valid values for the [Sizing](#) property. The value of the **Sizings** enumeration MUST be one of the following.

Value	Meaning
0x00	AutoSize
0x01	Fit
0x02	FitProportional
0x03	Clip

2.4.3 ShapeType

The **ShapeType** enumeration specifies the type of shape that is used for an image map. This enumeration contains valid values for the [ImageMapArea](#) property. The value of the **ShapeType** enumeration MUST be one of the following.

Value	Meaning
0x00	Rectangle
0x01	Polygon
0x02	Circle

2.4.4 ImageRawFormat

The **ImageRawFormat** enumeration specifies the **raw format** for an image. This enumeration contains valid values for the [RawFormat](#) property. The value of the **ImageRawFormat** enumeration MUST be one of the following.

Value	Meaning
0x00	BMP
0x01	JPEG
0x02	GIF
0x03	PNG

2.4.5 FontStyles

The **FontStyles** enumeration specifies the style of font used for a contiguous set of characters. This enumeration contains valid values for the [FontStyle](#) property. The value of the **FontStyles** enumeration MUST be one of the following.

Value	Meaning
0x00	Normal
0x01	Italic

2.4.6 FontWeights

The **FontWeights** enumeration specifies the weight of the font used for a contiguous set of characters. This enumeration contains valid values for the [FontWeight](#) property. The value of the **FontWeights** enumeration MUST be one of the following.

Value	Meaning
0x00	Normal
0x01	Thin
0x02	ExtraLight
0x03	Light
0x04	Medium
0x05	SemiBold
0x06	Bold
0x07	ExtraBold
0x08	Heavy

2.4.7 TextDecorations

The **TextDecorations** enumeration specifies the decoration used for a contiguous set of characters. This enumeration contains valid values for the [TextDecoration](#) property. The value of the **TextDecorations** enumeration MUST be one of the following.

Value	Meaning
0x00	None
0x01	Underline
0x02	Overline
0x03	LineThrough

2.4.8 TextAlignments

The **TextAlignments** enumeration specifies the horizontal alignment of a contiguous set of characters. This enumeration contains valid values for the [TextAlign](#) property. The **General** value specifies that the text alignment is derived from the data type of the value for the span of text and the peer style [Direction](#) property. The value of the **TextAlignments** enumeration MUST be one of the following.

Value	Meaning
0x00	General
0x01	Left
0x02	Center
0x03	Right

2.4.9 VerticalAlignments

The **VerticalAlignments** enumeration specifies the vertical alignment of a contiguous set of characters. This enumeration contains valid values for the [VerticalAlign](#) property. The value of the **VerticalAlignments** enumeration MUST be one of the following.

Value	Meaning
0x00	Top
0x01	Middle
0x02	Bottom

2.4.10 Directions

The **Directions** enumeration specifies the direction in which a contiguous set of characters is written and the layout direction of tablix columns. This enumeration contains valid values for the style [Direction](#) and tablix [LayoutDirection](#) properties. The value of the **Directions** enumeration MUST be one of the following.

Value	Meaning
0x00	LTR
0x01	RTL

2.4.11 WritingModes

The **WritingModes** enumeration specifies the direction in which to write a contiguous set of characters. This enumeration contains valid values for the [WritingMode](#) property. The value of the **WritingModes** enumeration MUST be one of the following.

Value	Meaning
0x00	Horizontal
0x01	Vertical

2.4.12 UnicodeBiDiTypes

The **UnicodeBiDiTypes** enumeration specifies the level of embedding with respect to the bi-directional algorithm. This enumeration contains valid values for the [UnicodeBiDi](#) property. The value of the **UnicodeBiDiTypes** enumeration MUST be one of the following.

Value	Meaning
0x00	Normal
0x01	Embed
0x02	BiDiOverride

2.4.13 Calendars

The **Calendars** enumeration specifies the type of calendar to use for formatting dates. This enumeration contains valid values for the [Calendar](#) property. The value of the **Calendars** enumeration MUST be one of the following.

Value	Meaning
0x00	Gregorian
0x01	GregorianArabic
0x02	GregorianMiddleEastFrench
0x03	GregorianTransliteratedEnglish
0x04	GregorianTransliteratedFrench
0x05	GregorianUSEnglish
0x06	Hebrew
0x07	Hijri
0x08	Japanese
0x09	Korean
0x10	Julian
0x11	Taiwan

Value	Meaning
0x12	ThaiBuddist

2.4.14 BorderStyles

The **BorderStyles** enumeration specifies the style for a given border. This enumeration contains valid values for the following border style properties: [BorderStyle](#), [BorderStyleLeft](#), [BorderStyleRight](#), [BorderStyleTop](#), and [BorderStyleBottom](#). The value of the **BorderStyles** enumeration MUST be one of the following.

Value	Meaning
0x00	None
0x01	Dotted
0x02	Dashed
0x03	Solid
0x04	Double

2.4.15 BackgroundRepeatTypes

The **BackgroundRepeatTypes** enumeration specifies how a background image should fill the space available within its parent container. This enumeration contains valid values for the [BackgroundRepeat](#) property. The value of the **BackgroundRepeatTypes** enumeration MUST be one of following.

Value	Meaning
0x00	Repeat
0x01	Clip
0x02	RepeatX
0x03	RepeatY

2.4.16 ListStyles

The **ListStyles** enumeration specifies the style used for a list. This enumeration contains valid values for the [ListStyle](#) property. The value of the **ListStyles** enumeration MUST be one of the following.

Value	Meaning
0x00	None
0x01	Numbered
0x02	Bulleted

2.4.17 MarkupStyles

The **MarkupStyles** enumeration specifies the type of markup to use for a block of text. This enumeration contains valid values for the [Markup](#) property. The value of the **MarkupStyles** enumeration MUST be one of the following.

Value	Meaning
0x00	None
0x01	HTML
0x02	RTF

2.4.18 TypeCode

The **TypeCode** enumeration specifies the type of an object. This enumeration contains valid values for the [TypeCode](#) property. The value of the **TypeCode** enumeration MUST be one of the following.

Value	Meaning
0x03	Boolean
0x04	Char
0x06	Byte
0x07	Int16
0x09	Int32
0x0B	Int64
0x0C	Single
0x0D	Double
0x0E	Decimal
0x0F	DateTime
0x11	String

2.4.19 StateValues

The **StateValues** structure specifies state information for report items. The parent structure for this property MUST be [Measurement](#) or [CellItemState](#).

										1												2																3
0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1	2	3	4	5	6	7	8	9	0	1							
A	B	C	D	E	F	reserved																																

A - OmitTop (1 bit): A bit that specifies that the top border is not displayed.

Value	Meaning
0x0	False. The border is displayed
0x1	True. The border is not displayed

B - OmitBottom (1 bit): A bit that specifies that the bottom border is not displayed.

Value	Meaning
0x0	False. The border is displayed
0x1	True. The border is not displayed

C - OmitLeft (1 bit): A bit that specifies that the left border is not displayed.

Value	Meaning
0x0	False. The border is displayed
0x1	True. The border is not displayed

D - OmitRight (1 bit): A bit that specifies that the right border is not displayed.

Value	Meaning
0x0	False. The border is displayed
0x1	True. The border is not displayed

E - HasToggle (1 bit): A bit that specifies that the [ReportItem](#) record has the ability to toggle between visible and hidden state.

Value	Meaning
0x0	False. The ReportItem does not toggle visibility
0x1	True. The ReportItem toggles visibility

F - ToggleCollapse (1 bit): A bit that specifies the **ReportItem** has its toggle set to collapsed.

Value	Meaning
0x0	False. The ReportItem toggle is not set to collapsed
0x1	True. The ReportItem toggle is set to collapsed

reserved (2 bits): The value MUST be zero.

A - Column (1 bit): A bit that specifies whether the current header is a row or column.

Value	Meaning
0x0	Row
0x1	Column

B - Static (1 bit): A bit that specifies whether the row or column header is static or dynamic.

Value	Meaning
0x0	False. The row or column header is not static.
0x1	True. The row or column header is static.

C - StaticHeadersTree (1 bit): A bit that specifies whether the row or column header and all its children are static.


Value	Meaning
0x0	False. The row or column header tree is not static.
0x1	True. The row or column header tree is static.

reserved (5 bits): The value MUST be zero.

2.4.22 RPLSize

The **RPLSize** structure specifies size information for the properties [BorderWidth](#), [BorderWidthLeft](#), [BorderWidthRight](#), [BorderWidthTop](#), [BorderWidthBottom](#), [PaddingLeft](#), [PaddingRight](#), [PaddingTop](#), [PaddingBottom](#), [FontSize](#), [LineHeight](#), [NumeralLanguage](#), [RightIndent](#), [LeftIndent](#), [HangingIndent](#), [SpaceBefore](#), and [SpaceAfter](#).

RPLSize = sizeValue



sizeValue (variable): A **String** variable that MUST be in the following structure:

"<FormatValue><FormatType>"

The **FormatValue** property MUST have a numerical string value in the form of an integer with no thousand delimiters, optionally followed by a decimal point and a positive integer. Unless

otherwise specified, the value of the **FormatValue** property MUST NOT evaluate to a negative integer.

The **FormatType** property specifies the unit type that is used for the distance. This property MUST be set to one of the following:

Value	Meaning
pt	Specifies a size in units of points.
pc	Specifies a size in units of picas.
in	Specifies a size in units of inches.
mm	Specifies a size in units of millimeters.
cm	Specifies a size in units of centimeters.

3 Structure Examples

This section contains examples of some of the most commonly used data structures in the RPL stream. The examples are meant to be a starting point for an implementer who is learning the stream format. They do not cover all the records in the stream format.

The following conventions are followed for the examples, unless noted otherwise:

- The order of the records, structures, and fields within an example match their corresponding order in the stream format.
- The examples begin with the first record that is relevant to the example and end with the last record that is relevant to the example. With the exception of the Report example, none of the examples can be used as a complete and stand-alone MS-RPL file.
- The examples are self-contained and contiguous; no records or structures are omitted in the middle of an example.
- Undefined and ignored fields are not included in the field explanations.
- Offset values for the records are included in the leftmost column because they are heavily relied upon in the RPL stream. While the value of the **offset** is an 8-byte integer, only one byte is shown in the Offset column.

3.1 Line

The following example illustrates a [Line](#) record with a [Slant](#) property in an RPL stream.

Offset	Size	Structure	Value
	0011	Line	
0x01	0001	BYTE - lineToken	0x08
	0006	LineProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	0002	ItemProperties	
0x04	0001	BYTE - slantStart	0x18
0x05	0001	BYTE - slantValue	0x00
0x06	0001	BYTE - delimiter	0xFF
0x07	0001	BYTE - delimiter	0xFF
	000A	ReportElementEnd	
0x08	0001	BYTE - elementEnd	0xFE
0x09	0008	INT - offset	0x0000000000000001

Offset	Size	Structure	Value
0x11	0001	BYTE - delimiter	0xFF

Line: A Line record that specifies the **Line** report item.

lineToken: 0x08 specifies the start **token** of the **Line** record.

LineProperties: An [ElementProperties](#) record that specifies the properties for the **Line** report item.

elementPropertiesStart: 0x0F specifies the start of the **ElementProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record that specifies the [InlineSharedElementProperties](#) record of the **Line** record.

shared: 0x00 specifies the start token of the InlineSharedElementProperties record.

ItemProperties: An array of properties for the **Line** record.

slantStart: 0x18 specifies the start of the Slant property.

slantValue: 0x00 specifies that the line will be drawn from the lower left to the upper right.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **LineProperties** record.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of the **Line** report item.

elementEnd: 0xFE specifies the end of the **Line** record.

offset: 0x0000000000000001 specifies the position of the **lineToken** field in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.2 Image

The following example illustrates an [Image](#) record with a [Sizing](#) property in an RPL stream.

Offset	Size	Structure	Value
	0011	Image	
0x01	0001	BYTE - imageStart	0x09
	0006	ImageProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	0002	ItemProperties	
0x04	0001	BYTE - sizingStart	0x29
0x05	0001	BYTE - sizingValue	0x00

Offset	Size	Structure	Value
0x06	0001	BYTE - delimiter	0xFF
0x07	0001	BYTE - delimiter	0xFF
	000A	ReportElementEnd	
0x08	0001	BYTE - elementEnd	0xFE
0x09	0008	INT - offset	0x0000000000000001
0x11	0001	BYTE - delimiter	0xFF

Image: An Image record that specifies the **Image** report item.

imageStart: 0x09 specifies the start token of the **Image** record.

ImageProperties: An ImageProperties record specifies the properties of the **Image** report item.

elementPropertiesStart: 0x0F specifies the start of the **ImageProperties** record.

SharedElementProperties: A **SharedElementProperties** structure that specifies the [InlineSharedElementProperties](#) record of the **Image** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **Image** record.

sizingStart: 0x29 specifies the start token of the Sizing property.

sizingValue: 0x00 specifies the default **Sizing** value. The **Image** report item will be set to **AutoSize**.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ImageProperties** record.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of image.

elementEnd: 0xFE specifies the end of the **Image** record.

offset: 0x0000000000000001 specifies the position of the **imageToken** field in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.3 Chart

The following example illustrates a [Chart](#) record with [Label](#) and [StreamName](#) properties in an RPL stream.

Offset	Size	Structure	Value
	002F	Chart	
0x01	0001	BYTE - chartToken	0x0B
	0024	ChartProperties	

Offset	Size	Structure	Value
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0010	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	000E	ItemProperties	
0x04	0001	BYTE - labelStart	0x03
0x05	000D	STRING - labelValue	Chart1
0x12	0001	BYTE - delimiter	0xFF
	0012	NonSharedElementProperties	
0x13	0001	BYTE - nonShared	0x01
	0010	ItemProperties	
0x14	0001	BYTE - streamNameStart	0x28
0x15	000F	STRING - streamNameValue	Stream1
0x24	0001	BYTE - delimiter	0xFF
0x25	0001	BYTE - delimiter	0xFF
	000A	ReportElementEnd	
0x26	0001	BYTE - elementEnd	0xFE
0x27	0008	INT - offset	0x0000000000000001
0x2F	0001	BYTE - delimiter	0xFF

Chart: A [Chart](#) record that specifies the **Chart** report item.

chartToken: 0x0B specifies the start token of the **Chart** record.

ChartProperties: An [ElementProperties](#) record that specifies the properties of the **Chart** report item.

elementPropertiesStart: 0x0F specifies the start of the **ElementProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record that specifies the [InlineSharedElementProperties](#) record of the **Chart** record.

shared: 0x00 specifies the start token of the **InlineSharedElementProperties** record.

ItemProperties: An array of properties for the **Chart** record.

labelStart: 0x03 specifies the start of Label property.

labelValue: *Chart1* specifies the label of the **Chart** report item.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

NonSharedElementProperties: A [NonSharedElementProperties](#) record that specifies the properties of the **Chart** record.

nonShared: 0x01 specifies the token of the NonSharedElementProperties record.

ItemProperties: An array of properties for the **Chart** record.

streamNameStart: 0x28 specifies the start token of the StreamName property.

streamNameValue: *Stream1* specifies the stream name of the **Chart** report item.

delimiter: 0xFF specifies the end of the **NonSharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ChartProperties** record.

ReportElementEnd: A [ReportElementEnd](#) structure specifies the end of the **Chart** record.

elementEnd: 0xFE specifies the end of the **Chart** element.

offset: 0x0000000000000001 specifies the position of the **chartToken** field in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.4 GaugePanel

The following example illustrates a [GaugePanel](#) record with [Label](#) and [Tooltip](#) properties in an RPL stream.

Offset	Size	Structure	Value
	002D	GaugePanel	
0x01	0001	BYTE - gaugePanelToken	0x0E
	0024	GaugePanelProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0010	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	000E	ItemProperties	
0x04	0001	BYTE - labelStart	0x03
0x05	000D	STRING - labelValue	Panel1
0x12	0001	BYTE - delimiter	0xFF
	0010	NonSharedElementProperties	
0x13	0001	BYTE - nonShared	0x01
	000E	ItemProperties	
0x14	0001	BYTE - toolTipStart	0x05
0x15	000D	STRING - toolTipValue	Gauge1

Offset	Size	Structure	Value
0x22	0001	BYTE - delimiter	0xFF
0x23	0001	BYTE - delimiter	0xFF
	000A	ReportElementEnd	
0x24	0001	BYTE - elementEnd	0xFE
0x25	0008	INT - offset	0x0000000000000001
0x2D	0001	BYTE - delimiter	0xFF

GaugePanel: A GaugePanel record that specifies the **GaugePanel** report item.

gaugePanelToken: 0x0E specifies the start token of the **GaugePanel** record.

GaugePanelProperties: An [ElementProperties](#) record that specifies the properties of the **GaugePanel** report item.

elementPropertiesStart: 0x0F specifies the start token of the **GaugePanelProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record that specifies the [InlineSharedElementProperties](#) record of the **GaugePanel** record.

shared: 0x00 specifies the start token of the **InlineSharedElementProperties** record.

ItemProperties: An array of properties for the **GaugePanel** record.

labelStart: 0x03 specifies the start of the Label property.

labelValue: *Panel1* specifies the label of the **GaugePanel** report item.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

NonSharedElementProperties: A [NonSharedElementProperties](#) record specifies the properties of the **GaugePanel** record.

nonShared: 0x01 specifies the start token of the **NonSharedElementProperties** record.

ItemProperties: An array of properties for the **GaugePanel** record.

toolTipStart: 0x05 specifies the start token of the Tooltip property.

toolTipValue: *Gauge1* specifies the text that is shown in the tool tip for the **GaugePanel** report item.

delimiter: 0xFF specifies the end of the **NonSharedElementProperties** record.

delimiter: 0xFF specifies the end of the **GaugePanelProperties** record.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of the **GaugePanel** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** element.

offset: 0x0000000000000001 specifies the position of the **gaugePanelToken** field in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.5 SubReport

The following example illustrates a [SubReport](#) record with a [ReportName](#) property in an RPL stream.

Offset	Size	Structure	Value
	005A	SubReport	
0x01	0001	BYTE - subReportToken	0x0C
	0014	SubReportProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0012	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	0010	ItemProperties	
0x04	0001	BYTE - reportNameStart	0x0F
0x05	000F	STRING - reportNameValue	report1
0x14	0001	BYTE - delimiter	0xFF
0x15	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0x16	0011	Line	
	002A	Measurements	
0x27	0001	BYTE - measurementStart	0x10
0x28	0008	INT - offset	0x0000000000000001
0x30	0004	INT - count	0x00000001
	001D	MeasurementsContent	
0x34	0004	FLOAT - left	0x00000000
0x38	0004	FLOAT - top	0x00000000
0x3C	0004	FLOAT - width	0X00000098
0x40	0004	FLOAT - height	0x00000019
0x44	0004	INT - zIndex	0x00000000
0x48	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0

Offset	Size	Structure	Value
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x49	0008	INT - reportElementEndOffset	0X000000000000001D
	000A	ReportElementEnd	
0x51	0001	BYTE - elementEnd	0xFE
0x52	0008	INT - offset	0x0000000000000027
0x5A	0001	BYTE - delimiter	0xFF

SubReport: A SubReport record that specifies the **SubReport** report item.

subReportToken: 0x0C specifies the start token of the **SubReport** record.

subReportProperties: An [ElementProperties](#) record that specifies the properties for the **SubReport** report item.

elementPropertiesStart: 0x0F specifies the start of the **ElementProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record specifies the [InlineSharedElementProperties](#) record of the **SubReport** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **SubReport** record.

reportNameStart: 0x0F specifies the start of ReportName property.

reportNameValue: *report1* specifies the name of the **SubReport** report item.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **SubReportProperties** record.

ReportItems: A [ReportItem](#) record specifies an array of report items.

Line: A [Line](#) record specifies a **Line** report item in the **SubReport** report item. See the Line example (section [3.1](#)) for more details.

Measurements: A [Measurements](#) record specifies size, location, and state properties for the **ReportItems** record.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x0000000000000001 specifies the start of the **SubReport** record in the RPL stream.

count: 0x00000001 specifies one **Measurement** record.

measurementsContent (variable): A **MeasurementsContent** structure that specifies an array of [Measurement](#) structures.

left: 0x00000000 specifies that the left position of the line is 0 millimeters relative to its parent record.

top: 0x00000000 specifies that the top position of the line is 0 millimeters relative to its parent record.

width: 0x00000098 specifies that the line is 152 millimeters (6 inches) wide.

height: 0x00000019 specifies that the line is 25.5 millimeters (1 inch) tall.

zIndex: 0x00000001 specifies that the line is drawn first.

state: 0x0C specifies the start token of the [State](#) property.

reportElementEndOffset: 0x000000000000001D specifies the **offset** of the **ReportElementEnd** record for the **Line** record in the RPL stream.

ReportElementEnd: A [ReportElementEnd](#) structure specifies the end of the **SubReport** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x0000000000000027 specifies the position of the **Measurements** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.6 RichTextBox

The following example illustrates a [RichTextBox](#) record with a single paragraph and two text runs in an RPL stream.

Offset	Size	Structure	Value
	00C2	RichTextBox	
0x01	0001	BYTE - richTextBoxToken	0x07
	0006	RichTextBoxProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	0002	ItemProperties	
0x04	0001	BYTE - canGrowStart	0x19
0x05	0001	BYTE - canGrowValue	0x00
0x06	0001	BYTE - delimiter	0xFF
0x07	0001	BYTE - delimiter	0xFF

Offset	Size	Structure	Value
	009B	Paragraphs	
	0034	TextRun	
0x08	0001	BYTE - textRunStart	0x14
	0032	TextRunProperties	
0x09	0001	BYTE - elementPropertiesStart	0x0F
	0012	SharedElementProperties	
0x0A	0001	BYTE - shared	0x00
	0010	ItemProperties	
0x0B	0001	BYTE - labelStart	0x03
0x0C	000F	STRING - labelValue	txtRun1
0x1B	0001	BYTE - delimiter	0xFF
	001E	NonSharedElementProperties	
0x1C	0001	BYTE - nonShared	0x01
	001C	ItemProperties	
0x1D	0001	BYTE - valueStart	0x19
0x1E	001B	STRING - valueValue	first textrun
0x39	0001	BYTE - delimiter	0xFF
0x3A	0001	BYTE - delimiter	0xFF
0x3B	0001	BYTE - delimiter	0xFF
	0036	TextRun	
0x3C	0001	BYTE - textRunStart	0x14
	0034	TextRunProperties	
0x3D	0001	BYTE - elementPropertiesStart	0x0F
	0012	SharedElementProperties	
0x3E	0001	BYTE - shared	0x00
	0010	ItemProperties	
0x3F	0001	BYTE - labelStart	0x03
0x40	000F	STRING - labelValue	txtRun2
0x4F	0001	BYTE - delimiter	0xFF
	0020	NonSharedElementProperties	

Offset	Size	Structure	Value
0x50	0001	BYTE - nonShared	0x01
	001E	ItemProperties	
0x51	0001	BYTE - valueStart	0x19
0x52	001D	STRING - valueValue	second textrun
0x6F	0001	BYTE - delimiter	0xFF
0x70	0001	BYTE - delimiter	0xFF
0x71	0001	BYTE - delimiter	0xFF
	0031	Paragraph	
0x72	0001	BYTE - paragraphStart	0x13
	001B	ParagraphProperties	
0x73	0001	BYTE - elementPropertiesStart	0x0F
	0012	SharedElementProperties	
0x74	0001	BYTE - shared	0x00
	0010	ItemProperties	
0x75	0001	BYTE - labelStart	0x03
0x76	000F	STRING - labelValue	paragr1
0x85	0001	BYTE - delimiter	0xFF
	0007	NonSharedElementProperties	
0x86	0001	BYTE - nonShared	0x01
	0005	ItemProperties	
0x87	0001	BYTE - paragraphNumberStart	0x0E
0x88	0004	INT - paragraphNumberValue	0x00000001
0x8C	0001	BYTE - delimiter	0xFF
0x8D	0001	BYTE - delimiter	0xFF
0x8E	0004	INT - count	0x00000002
	0010	OffsetsTextRun	
0x92	0008	INT - offset1	0x0000000000000008
0x9A	0008	INT - offset2	0x000000000000003C
0xA2	0001	BYTE - delimiter	0xFF
	0016	RichTextBoxStructure	

Offset	Size	Structure	Value
0xA3	0001	BYTE - richTextBoxStructureStart	0x12
0xA4	0008	INT - offset	0x0000000000000001
0xAC	0004	INT - count	0x00000001
	0008	OffsetsParagraphContent	
0xB0	0008	INT - offset1	0x0000000000000072
0xB8	0001	BYTE - delimiter	0xFF
	000A	ReportElementEnd	
0xB9	0001	BYTE - elementEnd	0xFE
0xBA	0008	INT - offset	0x00000000000000A3
0xC2	0001	BYTE - delimiter	0xFF

RichTextBox: A **RichTextBox** record that specifies the text box report item.

richTextBoxToken: 0x07 specifies the start token of the **RichTextBox** record.

RichTextBoxProperties: An [ElementProperties](#) record that specifies the properties for the **RichTextBox** report item.

elementPropertiesStart: 0x0F specifies the start token of the **RichTextBoxProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record specifies the [InlineSharedElementProperties](#) record of the **RichTextBox** record.

shared: 0x00 specifies the start token for the **SharedElementProperties** record.

ItemProperties: An array of properties for the **RichTextBox** record.

canGrowStart: 0x19 specifies the start token of the [CanGrow](#) property.

canGrowValue: 0x00 specifies a false value, which indicates that the height of the **RichTextBox** cannot increase.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **RichTextBoxProperties** record.

delimiter: 0xFF specifies the end of the [TextRun](#) record.

Paragraphs: An array of [ParagraphContent](#) records specifies the contents of the **RichTextBox** record.

TextRun: A **TextRun** structure specifies the contents and properties of a span of text.

textRunStart: 0x14 specifies the start token of the **TextRun** record.

TextRunProperties: An **ElementProperties** record specifies the properties of the **TextRun** record.

elementPropertiesStart: 0x0F specifies the start token of the **TextRunProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the **InlineSharedElementProperties** record of the **TextRun** record.

shared: 0x00 specifies the start token of the **InlineSharedElementProperties** record.

ItemProperties: An array of properties for the **TextRun** record.

labelStart: 0x03 specifies the start of the **Label** property.

labelValue: *txtRun1* specifies the label of the **TextRun** record.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

NonSharedElementProperties: A [NonSharedElementProperties](#) record specifies the properties of the **TextRun** record.

nonShared: 0x01 specifies the start token of the **NonSharedElementProperties** record.

ItemProperties: An array of properties for the **TextRun** record.

valueStart: 0x0A specifies the start token of the [Value](#) property.

valueValue: *first textrun* specifies the text to show in the **RichTextBox** record.

delimiter: 0xFF specifies the end of the **NonSharedElementProperties** record.

delimiter: 0xFF specifies the end of the **TextRunProperties** record.

delimiter: 0xFF specifies the end of the **TextRun** record.

TextRun: A **TextRun** record specifies the contents and properties of a span of text.

textRunStart: 0x14 specifies the start token of the **TextRun** record.

TextRunProperties: An **ElementProperties** record specifies the properties of the **TextRun** record.

elementPropertiesStart: 0x0F specifies the start token of the **TextRunProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the **InlineSharedElementProperties** record of the **TextRun** record.

shared: 0x00 specifies the start token of the **InlineSharedElementProperties** record.

ItemProperties: An array of properties for the **TextRun** record.

labelStart: 0x03 specifies the start of the **Label** property.

labelValue: *txtRun2* specifies the label of the **TextRun** record.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

NonSharedElementProperties: A **NonSharedElementProperties** structure specifies the properties of the **TextRun** record.

nonShared: 0x01 specifies the start token of the **NonSharedElementProperties** record.

ItemProperties: An array of properties for the **TextRun** record.

valueStart: 0x0A specifies the start token of the **Value** property.

valueValue: *second textrun* specifies the text to be shown in the **RichTextBox** record.

delimiter: 0xFF specifies the end of the **NonSharedElementProperties** record.

delimiter: 0xFF specifies the end of the **TextRunProperties** record.

delimiter: 0xFF specifies the end of the **TextRun** record.

Paragraph: A [Paragraph](#) record specifies the properties and layout of a **RichTextBox** record.

paragraphStart: 0x13 specifies the start token of the **Paragraph** record.

ParagraphProperties: An **ElementProperties** record that specifies the properties for the **Paragraph** record.

elementPropertiesStart: 0x0F specifies the start token of the **ParagraphProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the **InlineSharedElementProperties** record of the **Paragraph** record.

shared: 0x00 specifies the start token of the **InlineSharedElementProperties** record.

ItemProperties: An array of properties for the **Paragraph** record.

labelStart: 0x03 specifies the start of the **Label** property.

labelValue: *paragr1* specifies the label of the **Paragraph** record.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

NonSharedElementProperties: A **NonSharedElementProperties** record specifies the properties of the **Paragraph** record.

NonShared: 0x01 specifies the start token of the **NonSharedElementProperties** record.

ItemProperties: An array of properties for the **Paragraph** record.

paragraphNumberStart: 0x0E specifies the start token of the [ParagraphNumber](#) property.

paragraphNumberValue: 0x00000001 specifies that 1 is the number of this paragraph.

delimiter: 0xFF specifies the end of the **NonSharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ParagraphProperties** record.

count: 0x00000002 specifies that there are two **TextRun** records present in the **ParagraphContent** record.

OffsetsTextRun: An array of offsets pointing to the beginning of each **TextRun** record in the RPL stream.

offset1: 0x0000000000000008 specifies the position of the beginning of the first **TextRun** record.

offset2: 0x000000000000003C specifies the position of the beginning of the second **TextRun** record.

delimiter: 0xFF specifies the end of the **Paragraph** record.

RichTextBoxStructure: A [RichTextBoxStructure](#) record specifies the structure of the text box.

richTextBoxStructureStart: 0x12 specifies the start token of the **RichTextBoxStructure** record.

offset: 0x0000000000000001 specifies the position of the **RichTextBox** record in the RPL stream.

count: 0x00000001 specifies that one **ParagraphContent** record is present in the **RichTextBox** record.

offsetsParagraphContent: An array of offsets pointing to the beginning of each **Paragraph** record in the RPL stream.

offset1: 0x0000000000000072 specifies the position of the first **Paragraph** record in the RPL stream.

delimiter: 0xFF specifies the end of the **RichTextBoxStructure** record.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of the **RichTextBox** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000000A3 specifies the position of the **RichTextBoxStructureStart** token in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.7 Tablix

The following example illustrates a [Tablix](#) record with two rows and three columns. The first row consists of a [TablixComer](#) record and two [TablixColumnHeader](#) records, and the second row consists of a [TablixRowHeader](#) record and two [TablixBodyCell](#) records, each containing a [Line](#) record and an [Image](#) record.

Offset	Size	Structure	Value
	0093	Tablix	
0x01	0001	BYTE - tablixToken	0x0D
	0014	tablixProperties	
0x02	0001	BYTE - elementPropertiesStart	0x0F
	0012	SharedElementProperties	
0x03	0001	BYTE - shared	0x00
	0010	ItemProperties	
0x04	0001	BYTE - nameStart	0x02
0x05	000F	BYTE - nameStart	0x02
0x14	0001	STRING - nameValue	tablix1
0x15	0001	BYTE - delimiter	0xFF

Offset	Size	Structure	Value
	00A1	BYTE - delimiter	
	0003E	TablixContent	
	0022	ReportItems	
0x16	0011	Line	
0x27	0011	Image	
	001C	BYTE - tablixBodyRowStart	0x12
00x39	0004	INT - rowIndex	0x00000001
	0016	TablixBodyCells	
0x3D	0001	BYTE - tablixBodyCellStart	0x0D
	0009	TablixCellProperties	
0x3E	0001	BYTE - cellItemOffsetStart	0x04
0x3F	0008	INT - cellItemOffsetValue	0x000000000000001D
0x47	0001	BYTE - delimiter	0xFF
0x48	0001	BYTE - tablixBodyCellStart	0x0D
	0009	TablixCellProperties	
0x49	0001	BYTE - cellItemOffsetStart	0x04
0x4A	0008	INT - cellItemOffsetValue	0x000000000000002E
0x52	0001	BYTE - delimiter	0xFF
0x53	0001	BYTE - delimiter	0xFF
	0036	TablixStructure	
00x54	0001	BYTE - tablixStructureStart	0x11
0x55	0008	INT - offset	0x0000000000000001
	002C	TablixMeasurements	
	0025	tablixMeasurementsProperties	
0x5D	0001	BYTE - layoutDirectionStart	0x03
0x5F	0001	BYTE - tablixRowStart	0x08
	0029	TablixRows	
0x5F	0001	BYTE - tablixRowStart	0x08
	0015	TablixRowCell	
	0007	TablixCorner	

Offset	Size	Structure	Value
0x60	0001	BYTE - tablixCornerStart	0x0A
	0005	tablixCellProperties	
0x61	0001	BYTE - colSpanStart	0x05
0x62	0004	INT - colSpanValue	0x00000001
0x66	0001	BYTE - delimiter	0xFF
	0007	TablixColumnHeader	
0x67	0001	BYTE - tablixColumnHeaderStart	0x0B
0x68	0001	BYTE - colSpanStart	0x05
0x69	0004	INT - colSpanValue	0x00000001
	0005	tablixCellProperties	
0x6D	0001	BYTE - delimiter	0xFF
	0001	BYTE - delimiter	0xFF
	0007	TablixColumnHeader	
0x6E	0001	BYTE - tablixColumnHeaderStart	0x0B
0x6E	0001	BYTE - tablixColumnHeaderStart	0x0B
	0005	tablixCellProperties	
0x6F	0001	BYTE - colSpanStart	0x05
0x70	0004	INT - colSpanValue	0x00000001
00x74	0001	BYTE - delimiter	0xFF
00x75	0001	BYTE - delimiter	0xFF
0x76	0001	BYTE - tablixRowStart	0x08
	0019	TablixRowCell	
	0007	TablixRowHeader	
00x77	0001	BYTE - tablixRowHeaderStart	0x0
	0005	tablixCellProperties	
0x78	0001	BYTE - defIndexStart	0x08
0x79	0004	INT - defIndexValue	0x00000000
0x7D	0001	BYTE - delimiter	0xFF
	0009	TablixBodyRowCells	
0x7E	0001	BYTE - tablixBodyRowCellsStart	0x09

Offset	Size	Structure	Value
0x7F	0008	INT -offset	0x0000000000000038
0x87	0001	BYTE -delimiter	0xFF
0x88	0001	BYTE -delimiter	0xFF
0x89	0001	BYTE -delimiter	0xFF
	000A	ReportElementEnd	
0x8A	0001	BYTE -elementEnd	0xFE
0x8B 0x9B	0008	INT -offset	0x000000000000005E
0x93	0001	BYTE -delimiter	0xFF

Tablix: A **Tablix** record specifies the **Tablix** report item.

tablixToken: 0x0D specifies the start token of the **Tablix** record.

TablixProperties: An [ElementProperties](#) record specifies the properties for the **Tablix** report item.

elementPropertiesStart: 0x0F specifies the start of the **TablixProperties** record.

SharedElementProperties: A [SharedElementProperties](#) structure that specifies the [InlineSharedElementProperties](#) record of the **Tablix** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **Tablix** record.

nameStart: 0x02 specifies the start of the [Name](#) property.

nameValue: *tablix1* specifies the name of the **Tablix** report item.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **TablixProperties** record.

TablixContent: A [TablixContent](#) record specifies the **ReportItems** and [TablixBodyRow](#) records of the **tablix**.

ReportItems: A **ReportItems** record specifies an array of report items containing one line and one image.

Line: A **Line** structure specifies a **Line** report item in the **Tablix** report item. See the **Line** example (section [3.1](#)) for additional details.

Image: An **Image** record specifies a **Line** report item in the **Tablix** report item. See the **Image** example (section [3.2](#)) for additional details.

TablixBodyRow: The **TablixBodyRow** record specifies the content of a row in the **Tablix** record.

tablixBodyRowStart: 0x12 specifies the start token of **TablixBodyRow**.

rowIndex: 0x00000001 specifies that 1 is the index of this row.

TablixBodyCells: The **TablixBodyCells** record specifies an array of **TablixBodyCell** records.

tablixBodyCellStart: 0x0D specifies the start token of **TablixBodyCell**.

tablixCellProperties: An array of properties for the **Tablix** cell.

cellItemOffsetStart: 0x04 specifies the start token of the [CellItemOffset](#) property.

cellItemOffsetValue: 0x000000000000001D specifies the offset pointing to the **ReportElementEnd** record of the **Line** report item.

columnIndexStart: 0x08 specifies the start token of the [ColumnIndex](#) property.

columnIndexValue: 0x00000001 specifies that this cell will appear in the second column.

delimiter: 0xFF specifies the end of the **TablixBodyCell** record.

tablixBodyCellStart: 0x0D specifies the start token of **TablixBodyCell**.

tablixCellProperties: An array of properties for the **Tablix** cell.

cellItemOffsetStart: 0x04 specifies the start token of the **CellItemOffset** property.

cellItemOffsetValue: 0x000000000000002E specifies the offset pointing to the **ReportElementEnd** of the image report item.

columnIndexStart: 0x08 specifies the start token of the **ColumnIndex** property.

columnIndexValue: 0x00000002 specifies that this cell will appear in the third column.

delimiter: 0xFF specifies the end of the **TablixBodyCell** record.

delimiter: 0xFF specifies the end of the **TablixBodyRow** record.

TablixStructure: A [TablixStructure](#) record specifies the measurements of the tablix.

tablixStructureStart: 0x11 specifies the start token of the **TablixStructure** record.

offset: 0x0000000000000001 specifies the position of the **Tablix** record in the RPL stream.

TablixMeasurements: A [TablixMeasurements](#) record specifies the measurements of the tablix.

TablixMeasurementsProperties: A collection of **ItemProperty** records specifies the properties for the tablix measurements.

layoutDirectionStart: 0x03 specifies the start token of the [LayoutDirection](#) property.

layoutDirectionValue: 0x00 specifies that the layout direction of the tablix is left to right.

ColumnsWidths: A **ColumnWidths** record specifies the width of each column.

columnsWidthsStart: 0x04 specifies the start token of the **ColumnsWidths** record.

count: 0x03 specifies there are three columns in this tablix.

Columns: A [Columns](#) record specifies an array of properties for each column.

width: 0x0000CC41 specifies that the first column is 25.5 millimeters wide.

fixed: 0x00 specifies a false value, which indicates that the columns will disappear when part of the tablix is scrolled off the screen.

width: 0x0000CC41 specifies that the second column is 25.5 millimeters wide.

fixed: 0x00 specifies a false value, which indicates that the columns will disappear when part of the tablix is scrolled off the screen.

width: 0x0000CC41 specifies that the third column is 25.5 millimeters wide.

fixed: 0x00 specifies a false value, which indicates that the columns will disappear when part of the tablix is scrolled off the screen.

RowHeights: A [RowHeights](#) record specifies the heights of each row.

RowHeightsStart: 0x05 specifies the start token of the **RowHeights** property.

count: 0x02 specifies that there are two rows in this tablix.

height: 0x0000CC41 specifies that the first row is 25.5 millimeters tall.

fixedRows: 0x0 specifies a false value, which indicates the row will disappear when part of the tablix is scrolled off the screen.

sharedLayoutRows: 0x0 specifies a false value, which indicates that the layout cannot be shared by another row.

useSharedLayoutRows: 0x0 specifies a false value, which indicates that this row is not using the same layout as a previous row.

reserved: 0x0 specifies the field is 0 and must be ignored.

height: 0x0000CC41 specifies that the second row is 25.5 millimeters tall.

fixedRows: 0x0 specifies a false value, which indicates that the row will disappear when part of the tablix is scrolled off the screen.

sharedLayoutRows: 0x0 specifies a false value, which indicates that the layout cannot be shared by another row.

useSharedLayoutRows: 0x0 specifies a false value, which indicates that this row does not use the same layout as a previous row.

reserved: 0x0 specifies the field is 0 and must be ignored.

TablixRows: A **TablixRows** structure specifies an array of the [TablixRow](#) record.

tablixRowStart: 0x08 specifies the start token of the tablix row.

TablixRowCells: A **TablixRowCells** record specifies an array of the [TablixRowCell](#) record.

TablixCorner: A **TablixCorner** record specifies the contents of the tablix corner.

tablixCornerStart: 0x0A specifies the start token of **TablixCorner**.

tablixCellProperties: An array of properties for the tablix corner cell.

columnIndexStart: 0x08 specifies the start token of the **columnIndex** property.

columnIndexValue: 0x00000000 specifies this cell will appear in the first column.

delimiter: 0xFF specifies the end of **TablixCorner**.

TablixColumnHeader: A **TablixColumnHeader** record specifies the contents of the tablix header.

tablixColumnHeaderStart: 0x0B specifies the start token of **TablixColumnHeader**.

tablixCellProperties: An array of properties for the tablix column header cell.

columnIndexStart: 0x08 specifies the start token of the **columnIndex** property.

columnIndexValue: 0x00000001 specifies that this cell will appear in the second column.

delimiter: 0xFF specifies the end of **TablixColumnHeader**.

TablixColumnHeader: A **TablixColumnHeader** record specifies the contents of the tablix header.

tablixColumnHeaderStart: 0x0B specifies the start token of **TablixColumnHeader**.

tablixCellProperties: A collection of **ItemProperty** records specifies the properties for the tablix column header cell.

columnIndexStart: 0x08 specifies the start token of the **columnIndex** property.

columnIndexValue: 0x00000002 specifies that this cell will appear in the third column.

delimiter: 0xFF specifies the end of the **TablixColumnHeader** record.

delimiter: 0xFF specifies the end of the **TablixRow** record.

tablixRowStart: 0x08 specifies the start token of **TablixRow**.

TablixRowCells: A **TablixRowCells** record specifies an array of **TablixRowCell**.

TablixRowHeader: A **TablixRowHeader** record specifies the contents of the tablix header.

tablixRowHeaderStart: 0x0C specifies the start token of **TablixRowHeader**.

tablixCellProperties: An array of properties for the tablix row header cell.

columnIndexStart: 0x08 specifies the start token of the **columnIndex** property.

columnIndexValue: 0x00000000 specifies that this cell will appear in the first column.

delimiter: 0xFF specifies the end of the **TablixRowHeader** record.

TablixBodyRowCells: A **TablixBodyRowCell** record specifies the contents of the tablix body row cells.

tablixBodyRowCellsStart: 0x09 specifies the start token of the **TablixBodyRowCells** record.

offset: 0x0000000000000038 specifies the position of the **TablixBodyRow** record in the RPL stream.

delimiter: 0xFF specifies the end of the **TablixRows** record.

delimiter: 0xFF specifies the end of the **TablixMeasurements** record.

delimiter: 0xFF specifies the end of the **TablixStructure** record.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of the tablix record.

elementEnd: 0xFE specifies the end of the **Tablix** record.

offset: 0x000000000000005E specifies the position of the **TablixStructureStart** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

3.8 Report

This example specifies the records that are required to produce a [Report](#) by using RPL.

Offset	Size	Structure	Value
	0240	Report	
0x1	000B	STRING- RPLStamp	RPLIF
	0006	Version	
0xC	0001	BYTE- majorVersion	0x0A
0xD	0001	BYTE- minorVersion	0x04
0xE	0004	INT- build	0x00000000
0x12	0001	BYTE- reportStart	0x00
	0017	ReportProperties	
0x13	0001	BYTE- reportPropertiesStart	0x02
	0015	ItemProperties	
0x14	0001	BYTE - reportNameStart	0x0F
0x15	000F	STRING - reportNameValue	Report1
0x24	0001	BYTE - autoRefreshStart	0x0E
0x25	0004	INT - autoRefreshValue	0x0000001E
0x29	0001	BYTE - delimiter	0xFF
	01F2	Pages	
0x2A	0001	BYTE- pageContentStart	0x13
	000C	PageLayout	
0x2B	0001	BYTE - pagePropertiesStart	0x03
	000A	ItemProperties	
0x2C	0001	BYTE - pageHeightStart	0x10
0x2D	0004	FLOAT - pageHeightValue	0X00808B43
0x31	0001	BYTE - pageWidthStart	0x11

Offset	Size	Structure	Value
0x32	0004	FLOAT - pageWidthValue	0X00005843
0x36	0001	BYTE - delimiter	0xFF
	01B1	Sections	
0x37	0001	BYTE - sectionStart	0x15
	0019	SectionProperties	
0x38	0001	BYTE - sectionPropertiesStart	0x16
	0017	ItemProperties	
0x39	0001	BYTE - idStart	0x00
0x3A	0011	STRING - idValue	Section1
0x4B	0001	BYTE - columnCountStart	0x01
0x4C	0004	INT - columnCountValue	0x00000001
0x50	0001	BYTE - delimiter	0xFF
	0091	BodyAreaElement	
0x51	0001	BYTE - columns	0x14
	005C	BodyArea	
0x52	0001	BYTE - body	0x06
	0016	ElementProperties	
0x53	0001	BYTE - elementPropertiesStart	0x0F
	0014	SharedElementProperties	
0x54	0001	BYTE - shared	0x00
	0012	ItemProperties	
0x55	0001	BYTE - idStart	0x00
0x56	0011	STRING - idValue	BodyArea
0x67	0001	BYTE - delimiter	0xFF
0x68	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0x69	0011	Image	
	002A	Measurements	
0x7A	0001	BYTE - measurementsStart	0x10
0x7B	0008	INT- offset	0x0000000000000052

Offset	Size	Structure	Value
0x83	0004	INT- count	0x00000001
	001D	measurementsContent	
0x87	0004	FLOAT - left	0x00000000
0x8B	0004	FLOAT - top	0x00000000
0x8F	0004	FLOAT - width	0x00001843
0x93	0004	FLOAT - height	0x00003243
0x97	0004	INT - zIndex	0x00000000
0x9B	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x9C	0008	INT - reportElementEndOffset	0x0000000000000070
	000A	ReportElementEnd	
0xA4	0001	BYTE - elementEnd	0xFE
0xA5	0008	INT- offset	0x000000000000007A
0xAD	0001	BYTE - delimiter	0xFF
	002A	Measurements	
0xAE	0001	BYTE - measurementsStart	0x10
0xAF	0008	INT- offset	0x0000000000000051
0xB7	0004	INT- count	0x00000001
	001D	measurementsContent	
0xBB	0004	FLOAT - left	0x00000000
0xBF	0004	FLOAT - top	0x0000CC41
0xC3	0004	FLOAT - width	0x00001843
0xC7	0004	FLOAT - height	0x00003243

Offset	Size	Structure	Value
0xCB	0004	INT - zIndex	0x00000000
0xCF	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0xD0	0008	INT - reportElementEndOffset	0x00000000000000A4
	000A	ReportElementEnd	
0xD8	0001	BYTE - elementEnd	0xFE
0xD9	0008	INT- offset	0x00000000000000AE
0xE1	0001	BYTE - delimiter	0xFF
	004C	PageFooterElement	
0xE2	0001	BYTE - pageFooter	0x05
	0006	ElementProperties	
0xE3	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0xE4	0001	BYTE - shared	0x00
	0002	ItemProperties	
0xE5	0001	BYTE - printOnFirstPageStart	0x2C
0xE6	0001	BYTE - printOnFirstPageValue	0x00
0xE7	0001	BYTE - delimiter	0xFF
0xE8	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0xE9	0011	Line	
	002A	Measurements	
0xFA	0001	BYTE - measurementsStart	0x10

Offset	Size	Structure	Value
0xFB	0008	INT- offset	0x00000000000000E2
0x103	0004	INT- count	0x00000001
	001D	measurementsContent	
0x107	0004	FLOAT - left	0x00000000
0x10B	0004	FLOAT - top	0x00000000
0x10F	0004	FLOAT - width	0X00001843
0x113	0004	FLOAT - height	0x0000CC41
0x117	0004	INT - zIndex	0x00000000
0x11B	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x11C	0008	INT - reportElementEndOffset	0x00000000000000F0
	000A	ReportElementEnd	
0x124	0001	BYTE - elementEnd	0xFE
0x125	0008	INT- offset	0x00000000000000FA
0x12D	0001	BYTE - delimiter	0xFF
	004C	PageHeaderElement	
0x12E	0001	BYTE - pageHeader	0x04
	0006	ElementProperties	
0x12F	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0x130	0001	BYTE - shared	0x00
	0002	ItemProperties	
0x131	0001	BYTE - printOnFirstPageStart	0x2C

Offset	Size	Structure	Value
0x132	0001	BYTE - printOnFirstPageValue	0x01
0x133	0001	BYTE - delimiter	0xFF
0x134	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0x135	0011	Line	
	002A	Measurements	
0x146	0001	BYTE - measurementsStart	0x10
0x147	0008	INT- offset	0x000000000000012E
0x14F	0004	INT- count	0x00000001
	001D	measurementsContent	
0x153	0004	FLOAT - left	0x00000000
0x157	0004	FLOAT - top	0x00000000
0x15B	0004	FLOAT - width	0x00001843
0x15F	0004	FLOAT - height	0x0000CC41
0x163	0004	INT - zIndex	0x00000000
0x167	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x168	0008	INT - reportElementEndOffset	0x000000000000013C
	000A	ReportElementEnd	
0x170	0001	BYTE - elementEnd	0xFE
0x171	0008	INT- offset	0x0000000000000146
0x179	0001	BYTE - delimiter	0xFF
	0064	Measurements	

Offset	Size	Structure	Value
0x17A	0001	BYTE - measurementsStart	0x10
0x17B	0008	INT- offset	0x0000000000000037
0x183	0004	INT- count	0x00000003
	0057	measurementsContent	
0x187	0004	FLOAT - left	0x00000000
0x18B	0004	FLOAT - top	0X0000CC41
0x18F	0004	FLOAT - width	0x00001843
0x193	0004	FLOAT - height	0x00003243
0x197	0004	INT - zIndex	0x00000000
0x19B	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x19C	0008	INT - reportElementEndOffset	0x00000000000000D8
0x1A4	0004	FLOAT - left	0x00000000
0x1A8	0004	FLOAT - top	0X00804B43
0x1AC	0004	FLOAT - width	0x00001843
0x1B0	0004	FLOAT - height	0x0000CC41
0x1B4	0004	INT - zIndex	0x00000001
0x1B8	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0

Offset	Size	Structure	Value
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x1B9	0008	INT - reportElementEndOffset	0x0000000000000124
0x1C1	0004	FLOAT - left	0x00000000
0x1C5	0004	FLOAT - top	0X00000000
0x1C9	0004	FLOAT - width	0x00001843
0x1CD	0004	FLOAT - height	0x0000CC41
0x1D1	0004	INT - zIndex	0x00000002
0x1D5	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x1D6	0008	INT - reportElementEndOffset	0x0000000000000170
	000A	ReportElementEnd	
0x1DE	0001	BYTE - elementEnd	0xFE
0x1DF	0008	INT- offset	0x000000000000017A
0x1E7	0001	BYTE - delimiter	0xFF
	002A	Measurements	
0x1E8	0001	BYTE - measurementsStart	0x10
0x1E9	0008	INT- offset	0x000000000000002A
0x1F1	0004	INT- count	0x00000001
	001D	measurementsContent	
0x1F5	0004	FLOAT - left	0x00000000
0x1F9	0004	FLOAT - top	0x00000000

Offset	Size	Structure	Value
0x1FD	0004	FLOAT - width	0x00001843
0x201	0004	FLOAT - height	0x00006543
0x205	0004	INT - zIndex	0x00000000
0x209	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x20A	0008	INT - reportElementEndOffset	0x000000000000001DE
	000A	ReportElementEnd	
0x212	0001	BYTE - elementEnd	0xFE
0x213	0008	INT- offset	0x000000000000001E8
0x21B	0001	BYTE - delimiter	0xFF
	0015	OffsetsArrayElement	
0x21C	0001	BYTE- offsetsArrayElementStart	0x12
0x21D	0008	INT- offset	0x00000000000000012
0x225	0004	INT- count	0x00000001
	0008	OffsetsPageContent	
0x229	0008	INT- offset	0x00000000000000212
	000A	ReportElementEnd	
0x231	0001	BYTE - elementEnd	0xFE
0x232	0008	INT- offset	0x0000000000000021C
0x23A	0001	BYTE - delimiter	0xFF
	0006	Version	
0x23B	0001	BYTE- majorVersion	0x0A
0x23C	0001	BYTE- minorVersion	0x04

Offset	Size	Structure	Value
0x23D	0004	INT- build	0x00000000

Report: A Report record specifies the contents of the report.

RPLStamp: *RPLIF* specifies the value for the stamp.

Version: A [Version](#) record specifies the RPL version.

majorVersion: 0x0A specifies that the major version is 10.

minorVersion: 0x04 specifies that the minor version is 4.

build: 0x00000000 specifies that the build is 0.

reportStart: 0x00 specifies the start token of the **Report** record.

ReportProperties: A [ReportProperties](#) record specifies properties of the report.

reportPropertiesStart: 0x02 specifies the start token of the **ReportProperties** record.

ItemProperties: An array of item properties for the **Report** record.

reportNameStart: 0x0F specifies the start token of the [ReportName](#) property.

reportNameValue: *Report1* specifies the name of the report.

autoRefreshStart: 0x0E specifies the start token of the [AutoRefresh](#) property.

autoRefreshValue: 0x0000001E specifies that the automatic refresh interval is 30 seconds.

delimiter: 0xFF specifies the end of the **ReportProperties** record.

Pages: A [PageContent](#) record specifies the pages of a report.

pageContentStart: 0x13 specifies the start token of the **PageContent** record.

PageLayout: A [PageLayout](#) record specifies the layout of a page.

pagePropertiesStart: 0x03 specifies the start token of the **PageLayout** record.

ItemProperties: An array of properties for the **Page** record.

pageHeightStart: 0x10 specifies the start token of the **PageHeight** property.

pageHeightValue: 0x00808B43 specifies that the height of the page is 279 millimeters.

pageWidthStart: 0x11 specifies the start token of the **PageWidth** property.

pageWidthValue: 0x00005843 specifies that the width of the page is 216 millimeters.

delimiter: 0xFF specifies the end of the **PageLayout** record.

Sections: A [Section](#) record specifies the sections of a page.

sectionStart: 0x15 specifies the start token of the **Sections** record.

SectionProperties: A [SectionProperties](#) record specifies the properties of a section.

sectionPropertiesStart: 0x16 specifies the start token of the **SectionProperties** structure.

ItemProperties: An array of properties for the **Sections** record.

idStart: 0x00 specifies the start token of the [ID](#) property.

idValue: *Section1* specifies the identifier for the section.

columnCountStart: 0x01 specifies the start token of the [ColumnCount](#) property.

columnCountValue: 0x00000001 specifies that there is one column in this section.

delimiter: 0xFF specifies the end of the **SectionProperties** record.

BodyAreaElement: A [BodyAreaElement](#) record specifies an area of the body of a section.

Columns: 0x14 specifies the start token of the **BodyAreaElement** record.

BodyArea: A [BodyElement](#) record specifies the content of the main area of a **BodyAreaElement**.

body: 0x06 specifies the start token of the **BodyArea** record.

ElementProperties: An [ElementProperties](#) record that specifies the properties for the **BodyArea** record.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record that specifies the [InlineSharedElementProperties](#) record of the **BodyArea** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **BodyAreaElement** record.

idStart: 0x00 specifies the start token of the ID property.

idValue: *BodyArea* specifies the **ID** property for the **BodyArea** record.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A [ReportItem](#) record specifies items in the report.

Image: An [Image](#) record specifies an **Image** report item in the **BodyArea** record. See the **Image** example (section [3.2](#)) for additional details.

Measurements: A [Measurements](#) record specifies the measurements of an image report item.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x00000000000000052 specifies the position of the body token in the RPL stream.

count: 0x00000001 specifies that there is one [Measurement](#) record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the image is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the image is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the image is 152 millimeters wide.

height: 0x00003243 specifies that the image is 178 millimeters tall.

zIndex: 0x00000000 specifies that the image is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

A: 0x0 specifies that the top border is not omitted.

B: 0x0 specifies that the bottom border is not omitted.

C: 0x0 specifies that the left border is not omitted.

D: 0x0 specifies that the right border is not omitted.

E: 0x0 specifies that the report item does not toggle visibility.

F: 0x0 specifies that the report item is not set to collapse.

Reserved: 0x0 specifies that the bit MUST be set to 0.

Reserved: 0x0 specifies that the bit MUST be set to 0.

reportElementEndOffset: 0x0000000000000070 specifies the position of the [ReportElementEnd](#) record for the **Image** report item structure in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **BodyArea** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x000000000000007A specifies the position of the **measurementsStart** token for the **BodyArea** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Measurements: A **Measurements** record specifies the measurements of the body areas.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x0000000000000051 specifies the position of the columns token in the RPL stream.

count: 0x00000001 specifies that there is one **Measurement** record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the body area is placed 0 millimeters to the left of the parent.

top: 0x0000CC41 specifies that the body area is placed 25.5 millimeters below the parent.

width: 0x00001843 specifies that the body area is 152 millimeters wide.

height: 0x00003243 specifies that the body area is 178 millimeters tall.

zIndex: 0x00000000 specifies that the body area is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x00000000000000A4 specifies the position of the **ReportElementEnd** record for the **BodyElement** recording the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of **BodyAreaElement** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000000AE specifies the position of the **measurementsStart** token for **BodyAreaElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

PageFooterElement: A [PageFooterElement](#) record specifies the footer of a page.

pageFooter: 0x05 specifies the start token of the **PageFooterElement** record.

ElementProperties: An **ElementProperties** record specifies the properties for **PageFooterElement**.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the shared properties of a **PageFooter** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **PageFooterElement** record.

printOnFirstPageStart: 0x2C specifies the start token of the [PrintOnFirstPage](#) property.

printOnFirstPageValue: 0x00 specifies a false value, which indicates that the page footer will not print on the first page.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A **ReportItem** record specifies items in the report.

Line: A [Line](#) record specifies a **Line** report item in the **PageFooter** record. See the **Line** example (section [3.1](#)) for additional details.

Measurements: A **Measurements** record specifies the measurements of the report items.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x00000000000000E2 specifies the position of the **pageFooter** token in the RPL stream.

count: 0x00000001 specifies that there is one **Measurement** record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the line is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the line is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the line is 152 millimeters wide.

height: 0x0000C41 specifies that the line is 25.5 millimeters tall.

zIndex: 0x00000000 specifies that the line is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x00000000000000F0 specifies the position of the **ReportElementEnd** record for the **Line** report item for the **PageFooterElement** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of **PageFooterElement**.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000000FA specifies the position of the **measurementsStart** token for the **PageFooterElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

PageHeaderElement: A [PageHeaderElement](#) record specifies the header of a page.

pageHeader: 0x04 specifies the start token of the **PageHeaderElement** record.

ElementProperties: An **ElementProperties** record specifies the properties for **PageHeaderElement**.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the shared properties of a **PageHeader** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **PageHeaderElement** record.

printOnFirstPageStart: 0x2C specifies the start token of the **PrintOnFirstPage** property.

printOnFirstPageValue: 0x01 specifies a true value, which indicates that the page header will print on the first page.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A **ReportItem** record that specifies the items in the report.

Line: A **Line** record specifies a **Line** report item in the **PageHeader** record. See the **Line** example (section [3.1](#)) for additional details.

Measurements: A **Measurements** record specifies the measurements of the report items.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x0000000000000012E specifies the position of the **pageHeader** token in the RPL stream.

count: 0x00000001 specifies that there is one **Measurement** record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the line is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the line is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the line is 152 millimeters wide.

height: 0x0000CC41 specifies that the line is 25.5 millimeters tall.

zIndex: 0x00000000 specifies that the line is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x000000000000013C specifies the position of the **ReportElementEnd** record for the **Line** report item for the **PageHeaderElement** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **PageHeaderElement**.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x0000000000000146 specifies the position of the **measurementsStart** token for the **PageHeaderElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Measurements: A **Measurements** record specifies the measurements of the body area element, page header footer, and page header element.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x0000000000000037 specifies the position of the **sectionStart** token in the RPL stream.

count: 0x00000003 specifies that there are three **Measurement** records.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the body area is placed 0 millimeters to the left of the parent.

top: 0x0000CC41 specifies that the body area is placed 25.5 millimeters below the parent.

width: 0x00001843 specifies that the body area is 152 millimeters wide.

height: 0x00003243 specifies that the body area is 178 millimeters tall.

zIndex: 0x00000000 specifies that the body area is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x00000000000000D8 specifies the position of the **ReportElementEnd** record for the **BodyAreaElement** record in the RPL stream.

left: 0x00000000 specifies that the page footer is placed 0 millimeters to the left of the parent.

top: 0x00804B43 specifies that the page footer is placed 203.5 millimeters below the parent.

width: 0x00001843 specifies that the page footer is 152 millimeters wide.

height: 0x0000CC41 specifies that the page footer is 25.5 millimeters tall.

zIndex: 0x00000001 specifies that the page footer is drawn second.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x0000000000000124 specifies the position of the **ReportElementEnd** record for the **PageFooterElement** record in the RPL stream.

left: 0x00000000 specifies that the page header is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the page header is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the page header is 152 millimeters wide.

height: 0x0000CC41 specifies that the page header is 25.5 millimeters tall.

zIndex: 0x00000002 specifies that the page header is drawn third.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x0000000000000170 specifies the position of the **ReportElementEnd** record for the **PageHeaderElement** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **SimpleSection** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x000000000000017A specifies the position of the **measurementsStart** token for **SimpleSection** in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Measurements: A **Measurements** record specifies the measurements of the sections.

measurementsStart: 0x10 specifies the start token of the **Measurements** structure.

offset: 0x000000000000002A specifies the position of the **pageContentStart** token in the RPL stream.

count: 0x00000001 specifies that there is one Measurement record.

MeasurementsContent: A **MeasurementsContent** structure specifies an array of **Measurement** records.

left: 0x00000000 specifies that the section is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the section is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the section is 152 millimeters wide.

height: 0x00006543 specifies that the section is 229 millimeters tall.

zIndex: 0x00000000 specifies that the section is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x00000000000001DE specifies the position of the **ReportElementEnd** record for the **PageContent** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **PageContent** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000001E8 specifies the position of the **measurementsStart** token for the **PageContent** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

OffsetsArrayElement: An [OffsetsArrayElement](#) record specifies the offset for each page.

offsetsArrayElementStart: 0x12 specifies the start token of the **OffsetsArrayElement** record.

offset: 0x0000000000000012 specifies the position of the **reportStart** token in the RPL stream.

count: 0x00000001 specifies that there is one **PageContent** record.

OffsetsPageContent: An **OffsetsPageContent** record specifies an array with offsets to each **reportElementEnd** field of a **PageContent** record in the RPL stream.

offset: 0x0000000000000212 specifies the position of the **ReportElementEnd** record for the **PageContent** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the Report.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** structure.

offset: 0x000000000000021C specifies the position of the **offsetsArrayElementStart** token in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Version: A **Version** record specifies the RPL version.

majorVersion: 0x0A specifies that the major version is 10.

minorVersion: 0x04 specifies that the minor version is 4.

build: 0x00000000 specifies that the build is 0.

3.9 Report 2008

This example specifies the records that are required to produce a [Report](#) by using RPL 10.3.

Offset	Size	Structure	Value
	0201	Report	

Offset	Size	Structure	Value
0x1	000B	STRING- RPLStamp	RPLIF
	0006	Version	
0xC	0001	BYTE- majorVersion	0x0A
0xD	0001	BYTE- minorVersion	0x03
0xE	0004	INT- build	0x00000000
0x12	0001	BYTE- reportStart	0x00
	0017	ReportProperties	
0x13	0001	BYTE- reportPropertiesStart	0x02
	0015	ItemProperties	
0x14	0001	BYTE - reportNameStart	0x0F
0x15	000F	STRING - reportNameValue	Report1
0x24	0001	BYTE - autoRefreshStart	0x0E
0x25	0004	INT - autoRefreshValue	0x0000001E
0x29	0001	BYTE - delimiter	0xFF
	01B3	PageContent	
0x2A	0001	BYTE- pageContentStart	0x13
	00CB	BodyAreaElement	
0x2B	0001	BYTE - columns	0x14
	005C	BodyArea	
0x2C	0001	BYTE - body	0x06
	0016	ElementProperties	
0x2D	0001	BYTE - elementPropertiesStart	0x0F
	0014	SharedElementProperties	
0x2E	0001	BYTE - shared	0x00
	0012	ItemProperties	
0x2F	0001	BYTE - idStart	0x00
0x30	0011	STRING - idValue	BodyArea
0x41	0001	BYTE - delimiter	0xFF
0x42	0001	BYTE - delimiter	0xFF
	0011	ReportItems	

Offset	Size	Structure	Value
0x43	0011	Image	
	002A	Measurements	
0x54	0001	BYTE - measurementsStart	0x10
0x55	0008	INT- offset	0x000000000000002C
0x5D	0004	INT- count	0x00000001
	001D	measurementsContent	
0x61	0004	FLOAT - left	0x00000000
0x65	0004	FLOAT - top	0x00000000
0x69	0004	FLOAT - width	0x00001843
0x6D	0004	FLOAT - height	0x00003243
0x71	0004	INT - zIndex	0x00000000
0x75	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x76	0008	INT - reportElementEndOffset	0x000000000000004A
	000A	ReportElementEnd	
0x7E	0001	BYTE - elementEnd	0xFE
0x7F	0008	INT- offset	0x0000000000000054
0x87	0001	BYTE - delimiter	0xFF
	002A	Measurements	
0x88	0001	BYTE - measurementsStart	0x10
0x89	0008	INT- offset	0x000000000000002B
0x91	0004	INT- count	0x00000001
	001D	measurementsContent	

Offset	Size	Structure	Value
0x95	0004	FLOAT - left	0x00000000
0x99	0004	FLOAT - top	0x0000CC41
0x9D	0004	FLOAT - width	0x00001843
0xA1	0004	FLOAT - height	0x00003243
0xA5	0004	INT - zIndex	0x00000000
0xA9	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0xAA	0008	INT - reportElementEndOffset	0x000000000000007E
	000A	ReportElementEnd	
0xB2	0001	BYTE - elementEnd	0xFE
0xB3	0008	INT- offset	0x0000000000000088
0xBB	0001	BYTE - delimiter	0xFF
	00B3	Page	
0xBC	0001	BYTE - pageStart	0x01
	0019	PageProperties	
0xBD	0001	BYTE - pagePropertiesStart	0x03
	0017	ItemProperties	
0xBE	0001	BYTE - idStart	0x00
0xBF	0011	STRING - idValue	PageID01
0xD0	0001	BYTE - columnsStart	0x17
0xD1	0004	INT - columnsValue	0x00000001
0xD5	0001	BYTE - delimiter	0xFF
	004C	PageHeaderElement	

Offset	Size	Structure	Value
0xD6	0001	BYTE - pageHeader	0x04
	0006	ElementProperties	
0xD7	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0xD8	0001	BYTE - shared	0x00
	0002	ItemProperties	
0xD9	0001	BYTE - printOnFirstPageStart	0x2C
0xDA	0001	BYTE - printOnFirstPageValue	0x01
0xDB	0001	BYTE - delimiter	0xFF
0xDC	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0xDD	0011	Line	
	002A	Measurements	
0xEE	0001	BYTE - measurementsStart	0x10
0xEF	0008	INT- offset	0x00000000000000D6
0xF7	0004	INT- count	0x00000001
	001D	measurementsContent	
0xFB	0004	FLOAT - left	0x00000000
0xFF	0004	FLOAT - top	0x00000000
0x103	0004	FLOAT - width	0x00001843
0x107	0004	FLOAT - height	0x0000CC42
0x10B	0004	INT - zIndex	0x00000000
0x10F	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0

Offset	Size	Structure	Value
	1 bit	BIT - reserved	0x0
0x110	0008	INT - reportElementEndOffset	0x00000000000000E4
	000A	ReportElementEnd	
0x118	0001	BYTE - elementEnd	0xFE
0x119	0008	INT- offset	0x00000000000000EE
0x121	0001	BYTE - delimiter	0xFF
	004C	PageFooterElement	
0x122	0001	BYTE - pageFooter	0x05
	0006	ElementProperties	
0x123	0001	BYTE - elementPropertiesStart	0x0F
	0004	SharedElementProperties	
0x124	0001	BYTE - shared	0x00
	0002	ItemProperties	
0x125	0001	BYTE - printOnFirstPageStart	0x2C
0x126	0001	BYTE - printOnFirstPageValue	0x00
0x127	0001	BYTE - delimiter	0xFF
0x128	0001	BYTE - delimiter	0xFF
	0011	ReportItems	
0x129	0011	Line	
	002A	Measurements	
0x13A	0001	BYTE - measurementsStart	0x10
0x13B	0008	INT- offset	0x0000000000000122
0x143	0004	INT- count	0x00000001
	001D	measurementsContent	
0x147	0004	FLOAT - left	0x00000000
0x14B	0004	FLOAT - top	0x00000000
0x14F	0004	FLOAT - width	0X00001843
0x153	0004	FLOAT - height	0x0000CC41
0x157	0004	INT - zIndex	0x00000000
0x15B	0001	BYTE - state	

Offset	Size	Structure	Value
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x15C	0008	INT - reportElementEndOffset	0x0000000000000130
	000A	ReportElementEnd	
0x164	0001	BYTE - elementEnd	0xFE
0x165	0008	INT- offset	0x000000000000013A
0x16D	0001	BYTE - delimiter	0xFF
0x16E	0001	BYTE - delimiter	0xFF
	0064	Measurements	
0x16F	0001	BYTE - measurementsStart	0x10
0x170	0008	INT- offset	0x000000000000002A
0x178	0004	INT- count	0x00000003
	0057	measurementsContent	
0x17C	0004	FLOAT - left	0x00000000
0x180	0004	FLOAT - top	0x0000CC41
0x184	0004	FLOAT - width	0x00001843
0x188	0004	FLOAT - height	0x00003243
0x18C	0004	INT - zIndex	0x00000000
0x190	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0

Offset	Size	Structure	Value
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x191	0008	INT - reportElementEndOffset	0x00000000000000B2
0x199	0004	FLOAT - left	0x00000000
0x19D	0004	FLOAT - top	0x00000000
0x1A1	0004	FLOAT - width	0x00001843
0x1A5	0004	FLOAT - height	0x0000CC41
0x1A9	0004	INT - zIndex	0x00000000
0x1AD	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x1AE	0008	INT - reportElementEndOffset	0x0000000000000118
0x1B6	0004	FLOAT - left	0x00000000
0x1BA	0004	FLOAT - top	0x00804B43
0x1BE	0004	FLOAT - width	0x00001843
0x1C2	0004	FLOAT - height	0x0000CC41
0x1C6	0004	INT - zIndex	0x00000000
0x1CA	0001	BYTE - state	
	1 bit	BIT - omitTop	0x0
	1 bit	BIT - omitBottom	0x0
	1 bit	BIT - omitLeft	0x0
	1 bit	BIT - omitRight	0x0
	1 bit	BIT - hasToggle	0x0

Offset	Size	Structure	Value
	1 bit	BIT - toggleCollapse	0x0
	1 bit	BIT - reserved	0x0
	1 bit	BIT - reserved	0x0
0x1CB	0008	INT - reportElementEndOffset	0x00000000000000164
	000A	ReportElementEnd	
0x1D3	0001	BYTE - elementEnd	0xFE
0x1D4	0008	INT- offset	0x0000000000000016F
0x1DC	0001	BYTE - delimiter	0xFF
	0015	OffsetsArrayElement	
0x1DD	0001	BYTE- offsetsArrayElementStart	0x12
0x1DE	0008	INT- offset	0x0000000000000012
0x1E6	0004	INT- count	0x00000001
	0008	OffsetsPageContent	
0x1EA	0008	INT- offset	0x000000000000001D3
	000A	ReportElementEnd	
0x1F2	0001	BYTE - elementEnd	0xFE
0x1F3	0008	INT- offset	0x000000000000001DD
0x1FB	0001	BYTE - delimiter	0xFF
	0006	Version	
0x1FC	0001	BYTE- majorVersion	0x0A
0x1FD	0001	BYTE- minorVersion	0x03
0x1FE	0004	INT- build	0x00000000

Report: A Report record specifies the contents of the report.

RPLStamp: The "RPLIF" value specifies the value for the stamp.

Version: A [Version](#) structure specifies the RPL version.

majorVersion: 0x0A specifies that the major version is 10.

minorVersion: 0x03 specifies that the minor version is 3.

build: 0x00000000 specifies that the build is 0.

reportStart: 0x00 specifies the start token of the **Report** record.

ReportProperties: A [ReportProperties](#) record specifies properties of the report.

reportPropertiesStart: 0x02 specifies the start token of the **ReportProperties** record.

ItemProperties: An array of item properties for the **Report** record.

reportNameStart: 0x0F specifies the start token of the [ReportName](#) property.

reportNameValue: *Report1* specifies the name of the report.

autoRefreshStart: 0x0E specifies the start token of the [AutoRefresh](#) property.

autoRefreshValue: 0x0000001E specifies that the automatic refresh interval is 30 seconds.

delimiter: 0xFF specifies the end of the **ReportProperties** record.

PageContent: A [PageContent](#) (RPL 10.3) record specifies the pages of a report.

pageContentStart: 0x13 specifies the start token of the **PageContent** structure.

BodyAreaElement: A [BodyAreaElement](#) (RPL 10.3) record specifies an area of the body of **PageContent**.

Columns: 0x14 specifies the start token of the **BodyAreaElement** record.

BodyArea: A [BodyElement](#) record specifies the content of the main area of **BodyAreaElement**.

body: 0x06 specifies the start token of the **BodyArea** record.

ElementProperties: An [ElementProperties](#) record that specifies the properties for the **BodyArea** record.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A [SharedElementProperties](#) record that specifies the [InlineSharedElementProperties](#) record of the **BodyArea** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **BodyAreaElement** record.

idStart: 0x00 specifies the start token of the [ID](#) property.

idValue: *BodyArea* specifies **ID** for the **BodyArea** record.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A [ReportItem](#) record specifies items in the report.

Image: An [Image](#) record specifies an **Image** report item in the **BodyArea** record. See the **Image** example (section [3.2](#)) for additional details.

Measurements: A [Measurements](#) record specifies the measurements of an **Image** report item.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x000000000000002C specifies the position of the body token in the RPL stream.

count: 0x00000001 specifies that there is one measurement record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of measurements.

left: 0x00000000 specifies that the image is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the image is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the image is 152 millimeters wide.

height: 0x00003243 specifies that the image is 178 millimeters tall.

zIndex: 0x00000000 specifies that the image is drawn first.

State: A [State](#) property specifies the state information for the **Measurement** record of the report item.

A: 0x0 specifies that the top border is not omitted.

B: 0x0 specifies that the bottom border is not omitted.

C: 0x0 specifies that the left border is not omitted.

D: 0x0 specifies that the right border is not omitted.

E: 0x0 specifies that the report item does not toggle visibility.

F: 0x0 specifies that the report item is not set to collapse.

Reserved: 0x0 specifies that the bit MUST be set to 0.

Reserved: 0x0 specifies that the bit MUST be set to 0.

reportElementEndOffset: 0x000000000000004A specifies the position of the **ReportElementEnd** record for the **Image** report item structure in the RPL stream.

ReportElementEnd: A [ReportElementEnd](#) record specifies the end of the **BodyArea** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x0000000000000054 specifies the position of the **measurementsStart** token for the **BodyArea** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Measurements: A **Measurements** record specifies the measurements of the body areas.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x000000000000002B specifies the position of the columns token in the RPL stream.

count: 0x00000001 specifies that there is one measurement record.

MeasurementsContent: A **MeasurementsContent** structure specifies an array of measurements.

left: 0x00000000 specifies that the body area is placed 0 millimeters to the left of the parent.

top: 0x0000CC41 specifies that the body area is placed 25.5 millimeters below the parent.

width: 0x00001843 specifies that the body area is 152 millimeters wide.

height: 0x00003243 specifies that the body area is 178 millimeters tall.

zIndex: 0x00000000 specifies that the body area is drawn first.

State: A **State** property specifies the state information for the [Measurement](#) record of the report item.

reportElementEndOffset: 0x000000000000007E specifies the position of the **ReportElementEnd** record for the **BodyElement** structure in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **BodyAreaElement** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x0000000000000088 specifies the position of the **measurementsStart** token for the **BodyAreaElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Page: A [Page](#) record specifies a **Page** record in [PageContent](#).

pageStart: 0x01 specifies the start token of the **Page** record.

PageProperties: A [PageProperties](#) record specifies the properties of a page.

pagePropertiesStart: 0x03 specifies the start token of the **PageProperties** record.

ItemProperties: An array of properties for the **Page** record.

idStart: 0x00 specifies the start token of the **ID** property.

idValue: *PageID01* specifies the identifier for the page.

columnsStart: 0x17 specifies the start token of the **ColumnCount** property.

columnsValue: 0x00000001 specifies that there is one column in this page.

delimiter: 0xFF specifies the end of the **PageProperties** record.

PageHeaderElement: A [PageHeaderElement](#) record specifies the header of a page.

pageHeader: 0x04 specifies the start token of the **PageHeaderElement** record.

ElementProperties: An **ElementProperties** record specifies the properties for the **PageHeaderElement** record.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the shared properties of a **pageHeader** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **PageHeaderElement** record.

printOnFirstPageStart: 0x2C specifies the start token of the **PrintOnFirstPage** property.

printOnFirstPageValue: 0x01 specifies a true value, which indicates that the page header will print on the first page.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A ReportItem record that specifies the items in the report.

Line: A [Line](#) record specifies a **Line** report item in the **PageHeader** record. See the **Line** example (section [3.1](#)) for additional details.

Measurements: A **Measurements** record specifies the measurements of the report items.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x00000000000000D6 specifies the position of the **pageHeader** token in the RPL stream.

count: 0x00000001 specifies that there is one **Measurement** record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the line is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the line is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the line is 152 millimeters wide.

height: 0x0000CC41 specifies that the line is 25.5 millimeters tall.

zIndex: 0x00000000 specifies that the line is drawn first.

State: A **State** property specifies the state information for the Measurement record of the report item.

reportElementEndOffset: 0x00000000000000E4 specifies the position of the **ReportElementEnd** record of the **Line** report item in the **PageHeaderElement** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **PageHeaderElement** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000000EE specifies the position of the **measurementsStart** token for the **PageHeaderElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

PageFooterElement: A [PageFooterElement](#) record specifies the footer of a page.

pageFooter: 0x05 specifies the start token of the **PageFooterElement** record.

ElementProperties: An ElementProperties record specifies the properties for the **PageFooterElement** record.

elementPropertiesStart: 0x0F specifies the start token of the **ElementProperties** record.

SharedElementProperties: A **SharedElementProperties** record that specifies the shared properties of a **PageFooter** record.

shared: 0x00 specifies the start token of the **SharedElementProperties** record.

ItemProperties: An array of properties for the **PageFooterElement** record.

printOnFirstPageStart: 0x2C specifies the start token of the **PrintOnFirstPage** property.

printOnFirstPageValue: 0x00 specifies a false value, which indicates that the page footer will not print on the first page.

delimiter: 0xFF specifies the end of the **SharedElementProperties** record.

delimiter: 0xFF specifies the end of the **ElementProperties** record.

ReportItems: A **ReportItem** record specifies items in the report.

Line: A **Line** record specifies a **Line** report item in the **PageFooter** record. See the **Line** example for additional details.

Measurements: A **Measurements** record specifies the measurements of the report items.

measurementsStart: 0x10 specifies the start token of the **Measurements** structure.

offset: 0x0000000000000122 specifies the position of the **pageFooter** token in the RPL stream.

count: 0x00000001 specifies that there is one **Measurement** record.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the line is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the line is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the line is 152 millimeters wide.

height: 0x0000CC41 specifies that the line is 25.5 millimeters tall.

zIndex: 0x00000000 specifies that the line is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x0000000000000130 specifies the position of the **ReportElementEnd** record of the **Line** report item in the **PageFooterElement** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the **PageFooterElement** record.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x000000000000013A specifies the position of the **measurementsStart** token for the **PageFooterElement** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Measurements: A **Measurements** record specifies the measurements of the **PageContent (RPL 10.3)** record.

measurementsStart: 0x10 specifies the start token of the **Measurements** record.

offset: 0x000000000000002A specifies the position of the **pageContentStart** token in the RPL stream.

count: 0x00000003 specifies that there are three **Measurement** records.

MeasurementsContent: A **MeasurementsContent** record specifies an array of **Measurement** records.

left: 0x00000000 specifies that the body area is placed 0 millimeters to the left of the parent.

top: 0x0000CC41 specifies that the body area is placed 25.5 millimeters below the parent.

width: 0x00001843 specifies that the body area is 152 millimeters wide.

height: 0x00003243 specifies that the body area is 178 millimeters tall.

zIndex: 0x00000000 specifies that the body area is drawn first.

State: A **State** property specifies the state information for the **Measurement** record of the report item.

reportElementEndOffset: 0x000000000000007E specifies the position of the **ReportElementEnd** record for the **Body** record in the RPL stream.

left: 0x00000000 specifies that the page header is placed 0 millimeters to the left of the parent.

top: 0x00000000 specifies that the page header is placed 0 millimeters below the parent.

width: 0x00001843 specifies that the page header is 152 millimeters wide.

height: 0x0000CC41 specifies that the page header is 25.5 millimeters all.

zIndex: 0x00000001 specifies that the page header is drawn second.

State: A **State** property specifies the state information for the **Measurement** record of the page header.

reportElementEndOffset: 0x0000000000000118 specifies the position of the **ReportElementEnd** record for the **PageHeader** record in the RPL stream.

left: 0x00000000 specifies that the page footer is placed 0 millimeters to the left of the parent.

top: 0x00804B43 specifies that the page footer is placed 203.5 millimeters below the parent.

width: 0x00001843 specifies that the page footer is 152 millimeters wide.

height: 0x0000CC41 specifies that the page footer is 25.5 millimeters tall.

zIndex: 0x00000002 specifies that the page footer is drawn third.

State: A **State** property specifies the state information for the **Measurement** record of the page footer.

reportElementEndOffset: 0x0000000000000164 specifies the position of the **ReportElementEnd** record for the **PageFooter** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of **PageContent**.

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x000000000000016F specifies the position of the **measurementsStart** token for the **PageContent** record in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

OffsetsArrayElement: An [OffsetsArrayElement](#) record specifies the **offset** for each page.

offsetsArrayElementStart: 0x12 specifies the start token of the **OffsetsArrayElement** structure.

offset: 0x0000000000000012 specifies the position of the **reportStart** token in the RPL stream.

count: 0x00000001 specifies that there is one **PageContent** record.

OffsetsPageContent: An **OffsetsPageContent** record specifies an array with offsets to each **reportElementEnd** field of a **PageContent** record in the RPL stream.

offset: 0x00000000000001D3 specifies the position of the **ReportElementEnd** record for the **PageContent** record in the RPL stream.

ReportElementEnd: A **ReportElementEnd** record specifies the end of the [Report](#).

elementEnd: 0xFE specifies the start token of the **ReportElementEnd** record.

offset: 0x00000000000001DD specifies the position of the **offsetsArrayElementStart** token in the RPL stream.

delimiter: 0xFF specifies the end of the **ReportElementEnd** record.

Version: A Version structure specifies the RPL version.

majorVersion: 0x0A specifies that the major version is 10.

minorVersion: 0x03 specifies that the minor version is 3.

build: 0x00000000 specifies that the build is 0.

4 Security Considerations

None.

5 Appendix A: Product Behavior

The information in this specification is applicable to the following Microsoft products and technologies:

- Microsoft® SQL Server® 2008
Supports the following RPL versions: 10.3
- Microsoft® SQL Server® 2008 R2
Supports the following RPL versions: 10.3, 10.4, 10.5, and 10.6
- Microsoft® Visual Studio® 2010
Supports the following RPL versions: 10.3

Exceptions, if any, are noted below. Unless otherwise specified, any statement of optional behavior in this specification prescribed using the terms SHOULD or SHOULD NOT implies that the aforementioned Microsoft products' behavior is in accordance with the SHOULD or SHOULD NOT prescription. Unless otherwise specified, the term MAY implies that these Microsoft products do not follow the prescription.

[<1> Section 2.2.1: RPLStamp](#) value is currently defined as "RPLIF". This value is not validated by Microsoft ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<2> Section 2.2.2:](#) Version 0x03 corresponds to SQL Server 2008, and versions 0x04, 0x05, and 0x06 correspond to SQL Server 2009.

[<3> Section 2.2.5.1:](#) An additional byte is written in the stream at the start of the **Measurement** record. The value of this byte is 0xFF.

[<4> Section 2.2.5.2:](#) An additional byte is written in the stream at the start of the **Measurement** record. The value of this byte is 0xFF.

[<5> Section 2.2.10:](#) An additional byte is written in the stream at the start of the **Measurement** record. The value of this byte is 0xFF.

[<6> Section 2.2.11:](#) An additional byte is written in the stream at the start of the **Measurement** record. The value of this byte is 0xFF.

[<7> Section 2.2.13.1:](#) While reading the **BodyAreaElement** structure, Microsoft ReportViewer controls do not enforce the validation that the number of elements MUST NOT be greater than the value of the **ColumnCount** property specified in the **SectionProperties** record. ReportViewer controls are the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010.

[<8> Section 2.2.13.2:](#) While reading the **BodyAreaElement** structure, Microsoft ReportViewer controls do not enforce the validation that the number of elements MUST NOT be greater than the value of the **ColumnCount** property specified in the **Page** record. ReportViewer controls are the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010.

[<9> Section 2.2.22:](#) The parent record is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<10> [Section 2.2.22](#): The parent record is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<11> [Section 2.2.32](#): The restriction that **Chart**, **Map**, **GaugePanel**, **SubReport**, and **Tablix** records MUST NOT be part of **PageHeaderElement** and **PageFooterElement** is not imposed by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<12> [Section 2.2.41](#): The number of coordinates based on shape type is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<13> [Section 2.2.57](#): The value of the **Width** property is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<14> [Section 2.2.59](#): The **Height** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<15> [Section 2.2.59](#): **SharedLayoutRow** and **UseSharedLayoutRow** being set at the same time is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<16> [Section 2.2.59](#): **SharedLayoutRow** and **UseSharedLayoutRow** being set at the same time is not validated by the Microsoft RPL Reader.

<17> [Section 2.3.9](#): ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010) do not validate that the **ToggleItem** property MUST NOT be used in **PageHeader** and **PageFooter**.

<18> [Section 2.3.29](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<19> [Section 2.3.34](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<20> [Section 2.3.35](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<21> [Section 2.3.37](#): ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010) do not validate whether the **IsSimple** property specifies a **RichTextBox** with one or multiple **TextRun** records.

<22> [Section 2.3.39](#): The Microsoft implementation uses (C/M/G)_UniqueName_PageNumber, where C is used for **Chart**, M is used for **Map**, and G is used for **Gauge**.

<23> [Section 2.3.46](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<24> [Section 2.3.46](#): ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010) do not validate the MIMETYPE.

<25> [Section 2.3.47](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<26> [Section 2.3.48](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<27> [Section 2.3.48](#): The value of **Width, Height, HorizontalResolution, VerticalResolution,** and **RawFormat** being present, all together, is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<28> [Section 2.3.49](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<29> [Section 2.3.49](#): The value of **Width, Height, HorizontalResolution, VerticalResolution,** and **RawFormat** being present, all together, is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<30> [Section 2.3.50](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<31> [Section 2.3.50](#): The value of **Width, Height, HorizontalResolution, VerticalResolution,** and **RawFormat,** all together, being present is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<32> [Section 2.3.51](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<33> [Section 2.3.51](#): The value of **Width, Height, HorizontalResolution, VerticalResolution,** and **RawFormat,** all together, being present is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<34> [Section 2.3.52](#): When a property is part of both shared and nonshared **ElementProperties** structures, the nonshared property takes precedence over the shared property.

<35> [Section 2.3.52](#): The value of **Width, Height, HorizontalResolution, VerticalResolution,** and **RawFormat,** all together, being present is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<36> [Section 2.3.62](#): The **BorderStyle** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<37> [Section 2.3.63](#): The **BorderStyleLeft** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<38> [Section 2.3.64](#): The value of the **BorderStyleRight** property is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<39> [Section 2.3.65](#): The **BorderStyleTop** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<40> [Section 2.3.66](#): The **BorderStyleBottom** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<41> [Section 2.3.76](#): The **FontStyle** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<42> [Section 2.3.79](#): The **FontWeight** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<43> [Section 2.3.81](#): The **TextDecoration** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<44> [Section 2.3.82](#): The **TextAlign** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<45> [Section 2.3.83](#): The **VerticalAlign** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<46> [Section 2.3.84](#): The **Color** value is not validated against the rules specified in the description of **Color** property.

<47> [Section 2.3.86](#): The **Direction** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<48> [Section 2.3.87](#): The **WritingMode** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<49> [Section 2.3.88](#): The **UnicodeBidi** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<50> [Section 2.3.90](#): The **BackgroundColor** value is not validated against the rules specified in the description of **Color** property.

<51> [Section 2.3.91](#): The **BackgroundRepeat** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<52> [Section 2.3.93](#): The **NumeralVariant** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<53> [Section 2.3.94](#): The **Calendar** value is not validated against the enumeration by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

<54> [Section 2.3.95](#): The **ColumnHeaderRows** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<55> Section 2.3.96:](#) The **RowHeaderColumns** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<56> Section 2.3.97:](#) The **ColsBeforeRowHeader** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<57> Section 2.3.106:](#) The **ColumnIndex** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<58> Section 2.3.107:](#) The **RowIndex** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

[<59> Section 2.3.112:](#) The **ParagraphNumber** value is not validated by ReportViewer controls (the ReportViewer Windows Forms control and the ReportViewer ASP.NET Web server control that ship with Visual Studio 2010).

6 Change Tracking

This section identifies changes made to [MS-RPL] protocol documentation between November 2009 and March 2010 releases. Changes are classed as major, minor, or editorial.

Major changes affect protocol interoperability or implementation. Examples of major changes are:

- A document revision that incorporates changes to interoperability requirements or functionality.
- An extensive rewrite, addition, or deletion of major portions of content.
- A protocol is deprecated.
- The removal of a document from the documentation set.
- Changes made for template compliance.

Minor changes do not affect protocol interoperability or implementation. Examples are updates to fix technical accuracy or ambiguity at the sentence, paragraph, or table level.

Editorial changes apply to grammatical, formatting, and style issues.

No changes means that the document is identical to its last release.

Major and minor changes can be described further using the following revision types:

- New content added.
- Content update.
- Content removed.
- New product behavior note added.
- Product behavior note updated.
- Product behavior note removed.
- New protocol syntax added.
- Protocol syntax updated.
- Protocol syntax removed.
- New content added due to protocol revision.
- Content updated due to protocol revision.
- Content removed due to protocol revision.
- New protocol syntax added due to protocol revision.
- Protocol syntax updated due to protocol revision.
- Protocol syntax removed due to protocol revision.
- New content added for template compliance.
- Content updated for template compliance.

- Content removed for template compliance.
- Obsolete document removed.

Editorial changes always have the revision type "Editorially updated."

Some important terms used in revision type descriptions are defined as follows:

Protocol syntax refers to data elements (such as packets, structures, enumerations, and methods) as well as interfaces.

Protocol revision refers to changes made to a protocol that affect the bits that are sent over the wire.

Changes are listed in the following table. If you need further information, please contact protocol@microsoft.com.

Section	Tracking number (if applicable) and description	Major change (Y or N)	Revision Type
1.6 Versioning and Localization	340010 Added information for new version 10.6.	N	New content added due to protocol revision.
1.6 Versioning and Localization	340446 Added information about the RPL versions this specification applies to. Moved support details to Product Behavior section.	Y	Content updated due to protocol revision.
2.2.2 Version	340010 Added new field value.	N	Content updated due to protocol revision.
2.2.5.1 PageContent (RPL 10.6)	340010 Added information for new version 10.6.	N	New content added due to protocol revision.
2.2.5.1 PageContent (RPL 10.6)	388764 Added product behavior note to describe the extra delimiter that the product code is writing.	N	New product behavior note added.
2.2.5.2 PageContent (RPL 10.4 and 10.5)	388764 Added product behavior note to describe the extra delimiter that the product code is writing.	N	New product behavior note added.
2.2.10 SimpleSection	388764 Added product behavior note to describe the extra delimiter that the product code is writing.	N	New product behavior note added.
2.2.11 MixedSection	388764 Added product behavior note to describe the	N	New product behavior note

Section	Tracking number (if applicable) and description	Major change (Y or N)	Revision Type
	extra delimiter that the product code is writing.		added.
2.2.31 ImageConsolidationOffsets	343192 Added ImageConsolidationOffsets section.	N	New content added due to protocol revision.
5 Appendix A: Product Behavior	340446 Added information about SQL Server 2008 and about which products support which RPL versions.	Y	New protocol syntax added.

7 Index

A

[Action packet](#) 45
[ActionImageMapAreas packet](#) 45
[ActionInfo packet](#) 43
[ActionInfoContent packet](#) 44
[ActionInfoWithMaps packet](#) 46
[Augmented Backus-Naur Form \(ABNF\)](#) 15
[AutoRefresh packet](#) 94

B

[BackgroundRepeatTypes enumeration](#) 166
[big-endian](#) 13
binary records
 [about](#) 15
 [RPL file structure](#) 15
 [RPL stream](#) 15
[BodyAreaElement \(RPL 10.3\) packet](#) 31
[BodyAreaElement \(RPL 10.4\) packet](#) 30
[BodyElement packet](#) 34
Boolean data type ([section 2.1.1](#) 15, [section 2.1.3](#) 15)
[BorderStyles enumeration](#) 166
[byte boundary](#) 15
[byte ordering](#) 13

C

[Calendars enumeration](#) 165
[Change tracking](#) 231
[Chart packet](#) 56
[ColumnInfo packet](#) 71
[ColumnsWidths packet](#) 71
[ConsumeContainerWhiteSpace packet](#) 91

D

data types
 [about](#) 15
 [values](#) 15
[Datetime data type](#) 15
[Directions enumeration](#) 164
[DynamicImageData packet](#) 47

E

[ElementProperties packet](#) 35
[Enumerations](#) 162

F

fields
 [unaligned](#) 15
[Float data type](#) 15
[FontStyles enumeration](#) 163
[FontWeights enumeration](#) 163

G

[GaugePanel packet](#) 57

I

[Image packet](#) 50
[ImageConsolidationOffsets packet](#) 47
[ImageData packet](#) 54
[ImageDataProperties packet](#) 51
[ImageMapArea packet](#) 55
[ImageMapAreas packet](#) 54
[ImageRawFormat enumeration](#) 162
[InlineSharedElementProperties packet](#) 37
[InlineSharedImageDataProperties packet](#) 52
Int32 data type ([section 2.1.1](#) 15, [section 2.1.3](#) 15)
Int64 data type 15

L

[left properties](#) 15
[Line packet](#) 49
[ListStyles enumeration](#) 166
[little-endian](#) 13
[Long data type](#) 15

M

[Map packet](#) 58
[MarkupStyles enumeration](#) 167
[Measurement packet](#) 82
[Measurements packet](#) 81
[MixedSection packet](#) 27

N

[NonSharedElementProperties packet](#) 38
[NonSharedImageDataProperties packet](#) 53
[NonSharedStyleProperties packet](#) 43
[numeric values](#) 15

O

[offsets](#) 15
[OffsetsArrayElement packet](#) 19

P

[Page packet](#) 23
[PageContent \(RPL 10.3\) packet](#) 22
[PageContent \(RPL 10.6\) packet](#) 20
[PageContent packet](#) 21
[PageFooterElement packet](#) 33
[PageHeaderElement packet](#) 32
[PageLayout packet](#) 25
[PageProperties packet](#) 24
[Paragraph packet](#) 65

[ParagraphContent packet](#) 64
[Properties](#) 85

R

[record type](#) 15
[Rectangle packet](#) 59
[rendering runtime sizes](#) 15
[report hierarchy](#) 15
[report layout](#) 15
[Report structure](#) 16
[report structures](#) 16
[ReportElementEnd packet](#) 84
[ReportProperties packet](#) 18
[RichTextBox packet](#) 62
[RichTextBoxStructure packet](#) 67
[RowHeights packet](#) 72
[RowInfo packet](#) 73
RPL
 [about](#) 12
 version ([section 1.6](#) 14, [section 2.2.2](#) 18)
RPL stream
 [about](#) 15
 [file structure](#) 15
 [protocols](#) 14
 [reading strings](#) 16
 [root record](#) 16
 [Unicode characters](#) 13
 writing strings to ([section 2.1.3.1](#) 16, [section 2.1.3.2](#) 16)
[RPLSize packet](#) 170
[RPLSize structure](#) 170

S

[SectionProperties packet](#) 29
[ShapeType enumeration](#) 162
[SharedStyleProperties packet](#) 42
[SimpleSection packet](#) 26
[Sizings enumeration](#) 162
[SortOptions enumeration](#) 162
[StateValues structure](#) 167
[String data type](#) 15
structure example
 [Chart](#) 174
 [GaugePanel](#) 176
 [Image](#) 173
 [Line](#) 172
 [Report](#) 193
 [Report 2008](#) 209
 [RichTextBox](#) 180
 [SubReport](#) 178
 [Tablix](#) 186
structures
 [enumerations](#) 162
 [examples](#) 172
 [properties](#) 85
 [report structures](#) 16
 [unaligned fields](#) 15
[Style packet](#) 40
[SubReport packet](#) 61

T

[Tablix packet](#) 68
[TablixBodyCell packet](#) 78
[TablixBodyRow packet](#) 78
[TablixBodyRowCells packet](#) 77
[TablixColMembersDef packet](#) 80
[TablixColumnHeader packet](#) 75
[TablixCorner packet](#) 74
[TablixMeasurements packet](#) 70
[TablixMemberDef packet](#) 80
[TablixMemberDefStateValues structure](#) 169
[TablixMemberStateValues structure](#) 169
[TablixRow packet](#) 74
[TablixRowHeader packet](#) 76
[TablixRowMembersDef packet](#) 79
[TablixStructure packet](#) 69
[TextAlignments enumeration](#) 164
[TextDecorations enumeration](#) 163
[TextRun packet](#) 64
[top properties](#) 15
[Tracking changes](#) 231
[TypeCode enumeration](#) 167

U

[unaligned fields](#) 15
[Unicode characters](#) 13
[UnicodeBiDiTypes enumeration](#) 165
[UseSharedElementProperties packet](#) 36
[UseSharedImageDataProperties packet](#) 51
UTF-16 encoding ([section 1.4](#) 13, [section 2.1.3.1](#) 16)

V

version
 RPL ([section 1.6](#) 14, [section 2.2.2](#) 18)
[Version packet](#) 18
[Version structure](#) 18
[VerticalAlignments enumeration](#) 164

W

[WritingModes enumeration](#) 165